



# Transportation Research Division



## **Technical Report 14-12**

*Advanced Bridge Safety Initiative*

*Investigation of Floor Beam Performance in  
Three Steel Through-Truss Bridges*

*Task 7*

Technical Report Documentation Page

1. Report No. ME 14-12	2.	3. Recipient's Accession No.	
4. Title and Subtitle Advanced Bridge Safety Initiative: Investigation of Floor Beam Performance in Three Steel Through-Truss Bridges		5. Report Date August 2014	
		6.	
7. Author(s) Keenan Goslin, P.E. Bill Davids, Ph.D., P.E.		8. Performing Organization Report No.	
9. Performing Organization Name and Address University of Maine		10. Project/Task/Work Unit No. Project 017666.00 Task 7	
		11. Contract © or Grant (G) No. Contract # 20100506*5729	
12. Sponsoring Organization Name and Address Maine Department of Transportation 16 State House Station Augusta, Maine 04333		13. Type of Report and Period Covered	
		14. Sponsoring Agency Code	
15. Supplementary Notes			
16. Abstract (Limit 200 words)			
<p>The Advanced Structures and Composites Center at the University of Maine (UMaine) performed live load testing and rating adjustment factor analysis for three truss bridges. The Maine Department of Transportation (DOT) indicated that the floor beams are not sufficient for carrying the legal loads for these bridges. Each bridge is a steel through-truss bridge with floor beams, stringers and a variable depth concrete slab that was not designed to be composite with the steel framing. The bridges were all located in Maine in Brownville, Chester and T-3 Indian Purchase. Live load testing was conducted on April 8th, April 10th and April 15th, 2014 by UMaine with assistance from Maine DOT personnel to evaluate the performance of typical floor beams. Stringers were considered to be of secondary concern to the Maine DOT, and were not heavily instrumented.</p> <p>The strain measurements were consistent, and the results appear reliable. Measured floor beam strains were less than expected based on a lever rule analysis for live load distribution. If the MaineDOT agrees with our assessment, a conventional, lever rule load rating of the floor beams for these three structures that accounts for the condition of the floor beams including section losses must be completed. The rating factors determined from these analyses can then be increased by the values of K reported. Any existing cracking near copes or connections and remaining fatigue life have not been considered as part of this analysis, and should also be considered given the age of these structures.</p>			
17. Document Analysis/Descriptors Bridge load rating, live load testing, truss, floor beam		18. Availability Statement	
19. Security Class (this report)	20. Security Class (this page)	21. No. of Pages 81	22. Price

**Investigation of Floor Beam Performance in  
Three Steel Through-Truss Bridges**

**Prepared for:  
Dale Peabody P.E.  
Director Transportation Research  
Maine Department of Transportation  
16 State House Station  
Augusta, Maine 04333**

**University of Maine's Advanced Structures and Composites Center  
Report Number: 15-6-979**

August 14, 2014

**Prepared by:**



Keenan Goslin P.E.  
Structural Engineer

**Reviewed by:**



William Davids Ph.D. P.E.  
Professor of Civil and  
Environmental Engineering

This report shall not be reproduced, except in full, without the written approval of  
University of Maine's Advanced Structures and Composites Center.



**ACCREDITED**

*An ISO 17025 accredited testing laboratory, accredited by the International Accreditation Service.*

The Advanced Structures and Composites Center at the University of Maine (UMaine) performed live load testing and rating adjustment factor analysis for three truss bridges. The Maine Department of Transportation (DOT) indicated that the floor beams are not sufficient for carrying the legal loads for these bridges. Each bridge is a steel through-truss bridge with floor beams, stringers and a variable depth concrete slab that was not designed to be composite with the steel framing. The bridges were all located in Maine in Brownville, Chester and T-3 Indian Purchase. Live load testing was conducted on April 8<sup>th</sup>, April 10<sup>th</sup> and April 15<sup>th</sup>, 2014 by UMaine with assistance from Maine DOT personnel to evaluate the performance of typical floor beams. Stringers were considered to be of secondary concern to the Maine DOT, and were not heavily instrumented.

### TEST SETUP & INSTRUMENTATION

Each bridge was instrumented with strain gages using a semi-wireless structural testing system. These gages were generally located on the bottom flange, mid-height and under the top flange of the steel members. On each bridge, two floor beams and one stringer were instrumented. Eighteen gages were used for both the Brownville and Chester bridges each and 24 gages were installed on the Indian Purchase bridge test. Gage locations at each cross section are shown in Figure 1, Figure 2, and Figure 3.




Figure 1 - Gage location on Brownville cross section of floor beams and stringers respectively




Figure 2 - Gage location on Chester cross section of floor beams and stringers respectively




Figure 3 - Gage location on Indian Purchase cross section of floor beams and stringers respectively

Bridge number 3222 in Brownville had 6 cross sections with three gages each. Four cross-sections were on the floor beams and two on the centerline stringer spanning between the instrumented floor beams. The third and fourth floor beams from the south abutment were instrumented and can be seen in Figure 4. The bridges in Chester and Indian Purchase are instrumented similarly and are shown in Figure 5 and Figure 6 respectively.




Figure 4 – Gage locations for Bridge No. 3222 in Brownville, ME




Figure 5 – Gage locations for Bridge No. 3790 in Chester, ME




Figure 6 – Gage locations for Bridge No. 3666 in T-3 Indian Purchase, ME

**TEST VEHICLES**

Four loaded, dual rear axle dump trucks were used to load each bridge. The weight of each set of wheels and the spacing of the axles and wheels were recorded on site prior to loading the bridge. These measurements are given in Appendix A. The average weight of the trucks is shown in Table 1 and a typical truck can be seen in Figure 7.

Table 1 – Average truck weight during bridge testing

	Brownville (#3222)	Chester (#3790)	T3-Indian Purchase (#3366)
<b>Average truck weight</b>	54,840 lb.	64,050	60,825



Figure 7 – Typical test truck

## TESTING

Three series of tests were conducted at each bridge, each with increasing loads to the bridge members. Initially, a single truck was driven across the bridge at low speed (see Figure 7). The second test had two trucks traveling side by side at low speed across the bridge. The final series consisted of two static tests with four trucks positioned to maximize load to the floor beams of interest. Truck position was captured during the rolling tests with the AutoClicker, which records tire revolutions from a starting point on the bridge.

The load cases for the Brownville bridge are shown in Figure 8, Figure 9 and Figure 10. Similarly, the load cases for Chester are shown in Figure 11, Figure 12 and Figure 13 and Indian Purchase in Figure 14, Figure 15, and Figure 16.




Figure 8 – One truck loading of Brownville




Figure 9 – Two truck loading of Brownville




Figure 10 – Four truck loading of Brownville




Figure 11- One truck loading of Chester




Figure 12 – Two truck loading of Chester




Figure 13 – Four truck loading of Chester




Figure 14 – One truck loading of Indian Purchase bridge




Figure 15 – Two truck loading at Indian Purchase bridge




Figure 16 – Four truck loading at Indian Purchase bridge

## RESULTS

Strain data were collected with three different loadings at each bridge. Representative strain plots for key locations and peak values for all gages are detailed as follows for each structure.

### BROWNVILLE (No. 3222)

Data for the rolling single truck load case for Brownville is shown in Figure 17 and Table 2. The peak strain values for the rolling two truck case is given in

Table 3 and the peak values for Brownville's static four truck loading is given in Table 4. A plot of critical strain gage data during the four truck loading is also shown Figure 18.




Figure 17 – Plot of strain during first test at Brownville (Bridge No. 3222)

Table 2 - Peak Values for Single Truck Loading of the Brownville Bridge (No. 3222)

Sensor	B3060	B3057	B3062	B3068	B3069	B3070	B3811	B3067	B3075
Max Strain (µε)	4.68	20.32	30.78	13.12	4.49	20.31	44.42	37.59	31.33
Min Strain (µε)	-1.49	-2.86	0.52	1.03	-4.58	-0.79	-4.20	-7.52	1.24
Sensor	B3055	B3058	B3056	B3063	B3066	B3074	B3064	B3810	B3071
Max Strain (µε)	3.79	16.31	32.73	50.48	57.91	21.57	16.42	6.79	11.80
Min Strain (µε)	0.14	-1.09	-1.21	-1.56	-0.13	0.91	-2.08	0.65	0.54

Table 3 - Peak Values for Two Truck Loading of the Brownville Bridge (No. 3222)

Sensor	B3060	B3057	B3062	B3068	B3069	B3070	B3811	B3067	B3075
Max Strain (µε)	9.93	38.20	47.19	18.09	12.07	36.61	84.13	77.18	48.21
Min Strain (µε)	-2.14	-5.43	-1.44	-0.94	-8.35	-5.15	-8.91	-10.40	-1.15
Sensor	B3055	B3058	B3056	B3063	B3066	B3074	B3064	B3810	B3071
Max Strain (µε)	4.72	22.77	42.41	84.39	92.76	24.17	23.40	7.85	17.32
Min Strain (µε)	-0.10	-0.40	-1.54	-1.50	-3.16	-1.72	-1.15	-0.10	-0.29




Figure 18 – Plot of peak strain during static positioning of four trucks across two floor beams for Brownville (No. 3222)

Table 4 - Peak Values for Four Truck Loading of the Brownville Bridge (No. 3222)

<b>Sensor</b>	<b>B3060</b>	<b>B3057</b>	<b>B3062</b>	<b>B3068</b>	<b>B3069</b>	<b>B3070</b>	<b>B3811</b>	<b>B3067</b>	<b>B3075</b>
<b>Max Strain (μϵ)</b>	12.44	39.91	72.26	25.53	13.03	34.73	79.71	75.02	74.95
<b>Min Strain (μϵ)</b>	-1.84	-3.92	-2.35	-2.05	-5.90	-4.52	-10.97	-9.53	-3.64
<b>Sensor</b>	<b>B3055</b>	<b>B3058</b>	<b>B3056</b>	<b>B3063</b>	<b>B3066</b>	<b>B3074</b>	<b>B3064</b>	<b>B3810</b>	<b>B3071</b>
<b>Max Strain (μϵ)</b>	6.53	36.82	66.52	132.37	144.91	29.90	35.37	11.81	26.23
<b>Min Strain (μϵ)</b>	-0.21	-0.48	-2.55	-3.45	-3.20	-4.94	-1.70	-0.01	-2.11

## CHESTER (No. 3790)

Data for the rolling single truck load case for Chester is shown in Table 5. The peak strain values for the rolling two truck case is given in Table 6 and the peak values for Chester's static four truck loading is given in Table 7.

Table 5 - Peak Values for Single Truck Loading of the Chester bridge (No. 3790)

<b>Sensor</b>	<b>B3067</b>	<b>B3811</b>	<b>B3070</b>	<b>B3060</b>	<b>B3064</b>	<b>B3066</b>	<b>B3062</b>	<b>B3068</b>	<b>B3071</b>
<b>Max Strain (μϵ)</b>	145.37	13.36	12.65	31.09	67.77	136.52	3.95	1.68	40.63
<b>Min Strain (μϵ)</b>	-18.64	-11.31	116.09	-36.84	-2.78	-3.53	-113.01	-111.86	-26.07
<b>Sensor</b>	<b>B3057</b>	<b>B3075</b>	<b>B3069</b>	<b>B3810</b>	<b>B3074</b>	<b>B3063</b>	<b>B3056</b>	<b>B3058</b>	<b>B3055</b>
<b>Max Strain (μϵ)</b>	18.22	10.69	-0.67	5.00	2.10	136.99	73.07	4.55	13.34
<b>Min Strain (μϵ)</b>	-41.94	-11.01	122.62	-2.49	-59.63	-3.53	-5.59	-4.70	-68.90

Table 6 – Peak Values for Two Truck Loading of the Chester bridge (No. 3790)

<b>Sensor</b>	<b>B3067</b>	<b>B3811</b>	<b>B3070</b>	<b>B3060</b>	<b>B3064</b>	<b>B3066</b>	<b>B3062</b>	<b>B3068</b>	<b>B3071</b>
<b>Max Strain (μϵ)</b>	230.52	17.44	13.14	22.39	90.81	229.31	10.57	2.72	55.80
<b>Min Strain (μϵ)</b>	-25.45	-18.27	-171.95	-15.09	-6.41	-5.18	-10.48	-165.74	-43.07
<b>Sensor</b>	<b>B3057</b>	<b>B3075</b>	<b>B3069</b>	<b>B3810</b>	<b>B3074</b>	<b>B3063</b>	<b>B3056</b>	<b>B3058</b>	<b>B3055</b>
<b>Max Strain (μϵ)</b>	28.93	5.03	-0.02	2.85	0.40	219.17	99.91	6.14	20.13
<b>Min Strain (μϵ)</b>	-41.23	-18.42	-195.18	-5.44	-85.95	-2.66	-5.86	-4.34	-90.80

Table 7 – Peak Values for Four Truck Loading at the Chester bridge (No. 3790)

<b>Sensor</b>	<b>B3067</b>	<b>B3811</b>	<b>B3070</b>	<b>B3060</b>	<b>B3064</b>	<b>B3066</b>	<b>B3062</b>	<b>B3068</b>	<b>B3071</b>
<b>Max Strain (μϵ)</b>	225.63	24.29	15.72	43.21	165.02	410.24	5.33	1.25	77.32
<b>Min Strain (μϵ)</b>	-20.80	-5.80	-137.77	-66.54	-4.22	-1.99	-25.58	-333.20	-53.66
<b>Sensor</b>	<b>B3057</b>	<b>B3075</b>	<b>B3069</b>	<b>B3810</b>	<b>B3074</b>	<b>B3063</b>	<b>B3056</b>	<b>B3058</b>	<b>B3055</b>
<b>Max Strain (μϵ)</b>	38.59	0.62	0.57	8.58	0.00	375.49	176.99	0.42	14.10
<b>Min Strain (μϵ)</b>	-43.01	-25.86	-317.32	-7.87	-162.46	-1.88	-6.88	-12.94	-156.08

## INDIAN PURCHASE (NO. 3666)

Data for the rolling single truck load case for Indian Purchase is shown in Figure 19 and Table 8. The peak strain values for the rolling two truck case is given in Table 9 and the peak values for Brownville's static four truck loading is given in Table 10. A plot of critical strain gage data during the four truck loading is also shown Figure 20.

Table 8 – Peak strain values during 1 truck loading of Indian Purchase bridge (No. 3666)

<b>Sensor</b>	<b>B3068</b>	<b>B3811</b>	<b>B3067</b>	<b>B3062</b>	<b>B3056</b>	<b>B3055</b>	<b>B3058</b>	<b>B3072</b>
<b>Max Strain (μϵ)</b>	63.79	1.91	1.94	3.92	40.68	1.85	5.15	97.43
<b>Min Strain (μϵ)</b>	-4.11	-6.56	-64.82	-100.15	-2.66	-0.72	-36.43	-2.15
<b>Sensor</b>	<b>B3060</b>	<b>B3057</b>	<b>B3075</b>	<b>B3076</b>	<b>B3066</b>	<b>B3810</b>	<b>B3064</b>	<b>B3074</b>
<b>Max Strain (μϵ)</b>	78.56	42.70	7.51	0.22	54.07	35.17	0.78	0.67
<b>Min Strain (μϵ)</b>	-9.77	-2.89	-10.74	-3.81	-11.80	-3.72	-2.96	-29.13
<b>Sensor</b>	<b>B3073</b>	<b>B3059</b>	<b>B3061</b>	<b>B3065</b>	<b>B3071</b>	<b>B3069</b>	<b>B3070</b>	<b>B3063</b>
<b>Max Strain (μϵ)</b>	1.44	64.59	0.80	4.78	108.78	3.02	13.50	15.11
<b>Min Strain (μϵ)</b>	-93.05	-3.15	-7.25	-61.76	-3.17	-2.53	-6.18	-35.28

Table 9 – Peak strain values during 2 truck loading of Indian Purchase bridge (No. 3666)

<b>Sensor</b>	<b>B3068</b>	<b>B3811</b>	<b>B3067</b>	<b>B3062</b>	<b>B3056</b>	<b>B3055</b>	<b>B3058</b>	<b>B3072</b>
<b>Max Strain (μϵ)</b>	94.08	3.38	2.30	7.26	103.80	6.99	10.87	147.69
<b>Min Strain (μϵ)</b>	-8.28	-10.82	-92.09	-147.56	-6.93	-6.59	-89.01	-5.19
<b>Sensor</b>	<b>B3060</b>	<b>B3057</b>	<b>B3075</b>	<b>B3076</b>	<b>B3066</b>	<b>B3810</b>	<b>B3064</b>	<b>B3074</b>
<b>Max Strain (μϵ)</b>	121.91	52.55	11.73	-0.06	71.62	91.07	7.07	0.43
<b>Min Strain (μϵ)</b>	-14.73	-6.11	-24.91	-5.80	-17.15	-8.68	-9.23	-72.91
<b>Sensor</b>	<b>B3073</b>	<b>B3059</b>	<b>B3061</b>	<b>B3065</b>	<b>B3071</b>	<b>B3069</b>	<b>B3070</b>	<b>B3063</b>
<b>Max Strain (μϵ)</b>	1.94	89.27	0.81	9.37	163.14	6.81	31.84	20.08
<b>Min Strain (μϵ)</b>	-138.78	-6.68	-9.82	-86.45	-7.35	-4.18	-8.95	-36.58

Table 10 – Peak strain values during 4 truck loading of Indian Purchase bridge (No. 3666)

<b>Sensor</b>	<b>B3068</b>	<b>B3811</b>	<b>B3067</b>	<b>B3062</b>	<b>B3056</b>	<b>B3055</b>	<b>B3058</b>	<b>B3072</b>
<b>Max Strain (μϵ)</b>	168.24	0.57	7.14	17.53	195.84	8.01	4.24	300.32
<b>Min Strain (μϵ)</b>	-3.33	-15.14	-164.21	-190.15	-6.90	-8.09	-171.33	-5.65
<b>Sensor</b>	<b>B3060</b>	<b>B3057</b>	<b>B3075</b>	<b>B3076</b>	<b>B3066</b>	<b>B3810</b>	<b>B3064</b>	<b>B3074</b>
<b>Max Strain (μϵ)</b>	144.23	66.58	27.71	0.79	94.82	176.02	5.99	6.33
<b>Min Strain (μϵ)</b>	-11.62	-5.23	-48.97	-13.68	-20.87	-2.64	-10.72	-126.12
<b>Sensor</b>	<b>B3073</b>	<b>B3059</b>	<b>B3061</b>	<b>B3065</b>	<b>B3071</b>	<b>B3069</b>	<b>B3070</b>	<b>B3063</b>
<b>Max Strain (μϵ)</b>	1.18	166.06	3.89	1.70	330.49	9.49	62.88	33.45
<b>Min Strain (μϵ)</b>	-270.39	-5.65	-12.24	-162.22	-2.88	-21.26	-4.77	-33.46




Figure 19 – Chart of strain during 2 truck load case for Indian Purchase (No. 3666)




Figure 20 – Plot of strain versus time for Indian Purchase (No. 3666)

## ANALYSIS OF STRAIN DATA AND CALCULATION OF THE RATING FACTOR MODIFIER

Calculations in Appendix B detail the analysis of the truss bridge floorbeams in Chester, Brownville and Indian Purchase under both the test loading and HL-93 tandem and lane loading, which would control the flexural rating of the floorbeams. Important assumptions of the analyses are detailed below:

- 1) The lever rule was used to distribute all loads. The deck was assumed simply supported and spanning one way between stringers, and the simply supported stringers carried live load to the floorbeams.
- 2) Floorbeam spans were calculated based on available drawings provided by the MaineDOT.
- 3) Nominal properties were assumed for all the floorbeams, and no section loss was accounted for.

The field-measured strains indicate full composite action for the Brownville truss during the test, and no significant composite action at either Indian Purchase or Chester. These responses are consistent with details in the design drawings and visual inspection of the structures, which show significant floorbeam top flange slab embedment at Brownville and very little or no floorbeam top flange embedment in the slab for Chester or Indian Purchase. The measured strains indicate no significant rotational fixity at the floorbeam end connections for all three structures. Response for all structures remained linearly elastic, and measured strains produced by the two truck and four truck loading were approximately proportional to the increase in applied moment. The peak moments produced at Chester due to the four-truck loading were approximately 90% of the calculated moment due to an HL-93 loading with impact; at Brownville and Indian Purchase 81% and 102% of the calculated moment due to HL-93 loading with impact was applied, respectively.

Based on the calculations in Appendix B, floorbeam rating factors calculated per a conventional AASHTO lever rule analysis can be increased by the following:  $K = 1.30$  for Chester;  $K = 1.30$  for Brownville;  $K = 1.46$  for Indian Purchase. The calculations show that composite action cannot be relied upon at Brownville at higher loads, and this is reflected in the value of 1.30. These calculated values are likely influenced by less conservative live load distribution than predicted using the lever rule. The factor of safety against yielding was calculated for Chester under full service DL + HL-93 with impact to be approximately 1.56. This calculation was performed for Chester since it has the lightest floorbeams of all three structures, and the measured floorbeam strains were significantly larger than those measured at the other two bridges. While this value of 1.56 does not account for any section loss, it does indicate that these floorbeams may have substantial residual capacity beyond that required to carry current design loads.

## CONCLUSIONS

The strain measurements were consistent, and the results appear reliable. Measured floorbeam strains were less than expected based on a lever rule analysis for live load distribution. If the MaineDOT agrees with our assessment, a conventional, lever rule load rating of the floorbeams for these three structures that accounts for the condition of the floorbeams including section losses must be completed. The rating factors determined from these analyses can then be increased by the values of  $K$  reported above. Any existing cracking near copes or connections and remaining fatigue life have not been considered as part of this analysis, and should also be considered given the age of these structures.

## REFERENCES

1. The Manual for Bridge Evaluation, 2<sup>nd</sup> Ed. with interim revisions. AASHTO. Washington D.C. 2011.
2. Brownville Junction Bridge Plans (#3222). November 1983. Provided by Maine DOT.
3. Penobscot River Bridge Plans (#3790). January 1948. Provided by Maine DOT.
4. West Branch Bridge Plans (#3666). November 1939. Provided by Maine DOT.

**APPENDIX A: TRUCK MEASUREMENTS – BROWNVILLE, CHESTER, T3 INDIAN PURCHASE**

Insert 3 PDFs (12 pages total)

“Brownville\_Truck\_Wts.pdf”

“Chester\_Truck\_Wts.pdf”

“T3\_Indian\_Purchase\_Truck\_Wts.pdf”



Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

Project: Bridge Load Testing/Rating - Brownville


By: KMG Date: 4/8/14

Subject: Test Vehicle Measurements

Checked: Date:

License Plate Number T01-443  
Truck Designation (1 or 2) 4

Weighed By: DOT  
Dimensions by: CF



Total Vehicle Weight 51,850



Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

Project: Bridge Load Testing/Rating - Brownville

By: KMG Date: 4/8/14

Subject: Test Vehicle Measurements


Checked: Date:

License Plate Number 701-835

Weighed By: DOT

Truck Designation (1 or 2) 3

Dimensions by: CP



Total Vehicle Weight 53,000



Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

Project: Bridge Load Testing/Rating - Brownville


By: KMG Date: 4/8/14

Subject: Test Vehicle Measurements

Checked: Date:

License Plate Number TO 1-241  
Truck Designation (1 or 2) 2

Weighed By: DOT  
Dimensions by: CF



Total Vehicle Weight 57,900



Phone: (207) 581-2123  
 Fax: (207) 581-2074  
 www.aewc.umaine.edu

Page:	
Project No.:	
By:	Date:
KMG	4/8/14
Checked:	Date:

Project: Bridge Load Testing/Rating - Brownville

Subject: Test Vehicle Measurements

License Plate Number T01-707 Weighed By: DOT

Truck Designation (1 or 2) 1 Dimensions by: CF

Axle Weight <u>20,000</u>	<u>9,700</u>	<u>10,300</u>	Axle Spacing <u>53"</u>
Axle Weight <u>19700</u>	<u>10,800</u>	<u>8,900</u>	
		<u>22"</u>	
Axle Weight <u>16500</u>	<u>8,500</u>	<u>8,400</u>	Axle Spacing <u>191"</u>
		<u>11 1/2"</u>	
	Wheel Spacing <u>91"</u>		
Total Vehicle Weight <u>56,600</u>			



Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

Project: Chester Bridge Test

By: KMG Date: 4/10/14


Subject: Test Vehicle Measurements

Checked: \_\_\_\_\_ Date: \_\_\_\_\_

*DWANE*

License Plate Number 701-194  
Truck Designation (1 or 2) 2

Weighed By: CSF  
Dimensions by: KMG



742

Total Vehicle Weight 55500

*Front*



Advanced Structures & Composites Center

Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

Project:

Chester Bridge

By:

Date:

KMG

4/10/14

Subject:

Test Vehicle Measurements

Checked:

Date:

License Plate Number Pa1-228

Weighed By: CSF

Truck Designation (1 or 2) 1

Dimensions by: KMG

MMT/14



Axle Weight 9100



=93'



11750

54"  
Axle Spacing

#1

Axle Weight 10000



11000




16'-8"  
Axle Spacing

52'-3"  
for 5 revolutions


Axle Weight 7400



8700



FRONT



Total Vehicle Weight 58050



Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

Project: CHESTER BRIDGE TEST


By: KMG Date:

Subject: Test Vehicle Measurements

Checked: Date:

License Plate Number TD1-225  
Truck Designation (1 or 2) \_\_\_\_\_

Weighed By: CSF  
Dimensions by: CSF





Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

Project: CHESTER BRIDGE TEST

By: \_\_\_\_\_ Date: \_\_\_\_\_  
KMG

Subject: Test Vehicle Measurements


Checked: \_\_\_\_\_ Date: \_\_\_\_\_

License Plate Number 701-180

Weighed By: CSP

Truck Designation (1 or 2) \_\_\_\_\_

Dimensions by: CSP



#4



Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.: 979

Project: T3-INDIAN PURCHASE U TEST


By: KMG Date: 4/15/14

Subject: Test Vehicle Measurements

Checked: Date:

License Plate Number 101-228  
Truck Designation (1 or 2) #2

Weighed By: KMG  
Dimensions by: KMG



Total Vehicle Weight 55,050



Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

979

Project:

Bridge Load Testing/Rating T3- Indian Purchase

By:

Date: 4/15/14

KMG

Subject:


Test Vehicle Measurements

Checked:

Date:

License Plate Number 701-180  
Truck Designation (1 or 2) 44

Weighed By: KMG  
Dimensions by: KMG



Total Vehicle Weight 68,750






Phone: (207) 581-2123  
Fax: (207) 581-2074  
www.aewc.umaine.edu

Page:
Project No.: 979
By: KMG Date: 4/15/14
Checked: Date:

Project: Bridge Load Testing/Rating <u>TS-Indian Purchase</u>
Subject: Test Vehicle Measurements

License Plate Number 701-225  
Truck Designation (1 or 2) #1

Weighed By: KMG  
Dimensions by: KMG



Total Vehicle Weight 58,150

**APPENDIX B: TEST CALCULATIONS**

“Brownville\_calcs\_05\_14\_2014.pdf”

“Chester\_FB\_Analysis.pdf”

“T3\_Indian\_Purchase\_FB\_analysis\_04\_24\_2014.pdf”

## BROWNVILLE

### BRIDGE PROPERTIES


- STRINGERS: W21x73.5 (interior) @ 5'-6" (5'-0" exterior), 23.21' span
- FB: W33x130, SPAN = 28'-7" - 4'-1/2" = 23'-2 1/2" = 23.21'
- DECK: 11" CONCRETE (4" WS)

### MAX MEASURED FB STRAINS:

- 145  $\mu\epsilon$  max w/ 4 trucks
- 92.8  $\mu\epsilon$  max w/ 2 trucks
- Strains very linear, high degree of composite action observed.
- top flange cool at least over flange edges in slab.

### FB MOMENTS DUE TO TRUCK LOADS:

- Computed using lower rule, field-measured wheel loads, previously verified spreadsheet
- 2 truck moment = 220.3 ft-k } @ gage location.
- 4 truck moment = 368.2 ft-k }
- HL-93+1NA (tandem + lane) =  
(see pp. 3 & 4)



$$\frac{145 - 25.4}{27.855} = 4.294 \text{ mft}$$

$$145 - 4.294 \times 16.48 = 74.2 \approx 72.5$$

∴ Dimension response

W53 x 130

BROWNVILLE

W. DAVIDS


4/28/14

3/

HL-93 + IM LOAD

Tandem moments computed w/ spreadsheet = 301.8 k-ft (e millspan)  
(two lanes, no IM)

Due to lane:



$$P_1 = P_5 = \left(0.064 \times 4.5 \times \frac{4.5}{2} \times \frac{1}{5}\right) \times 23.21' = 3.01^k \quad (\times 2 = 6.02)$$

$$P_2 = P_4 = 0.064 \times \left(4.5 \times \frac{2.75}{5} + \frac{5.5}{2}\right) \times 23.21 = 7.76^k \quad (\times 2 = 15.52)$$

$$P_3 = 0.064 \times 5.5' \times 23.21' = 8.17^k \quad (\times 1 = 8.17)$$

$$\Sigma 29.76^k$$

$$0.064 \times 23.21 \times 20' = 29.71^k$$

$$M_{lane} = \frac{8.17 \times 23.21}{4} \rightarrow 47.4$$

$$+ \frac{15.52 \times 6.11 \times 17.11}{23.21} \times \frac{11.61}{17.11} \rightarrow 47.4$$

$$+ \frac{6.02 \times 1.11 \times 22.11}{23.21} \times \frac{11.61}{22.11} \rightarrow 3.34$$

$$\underline{98.2^k}$$

BROWNVILLE

W DAVIDS  
4/28/14  
4/

HL 93 + IM LOADS

$$M_{LL+IM} = 1.33 \times 301.8 + 98.2 = 500^{lb}$$


$$\text{Max 4-truck moment} = 403.3^{lb}, \quad T/W = \frac{403.3}{500} = 0.81 > 0.7$$

OK

ASSESS STRAIN RESPONSE

- FB flange is embedded in 11" deck, girder is exhibiting composite action.

- Assume  $f'_c = 3 \mu\text{si}$ ,  $n = 10$ , eff flange width TBD.



- Strain measurements under 4-truck load indicate

$$\bar{y} = 27.855" + 25.4 \frac{\text{kg}}{4.29 \text{ m}^2/\text{in}} = 33.8" = \text{top of girder, just in slab}$$

increased to 0.87 to give correct I for Non-composite section

$b_e$	calculated $\bar{y}$
60"	30.5"
80"	31.9"
120"	33.7" $\approx$ 33.8" $\leftarrow$ say $b_e = 120"$

-  $w/b_e = 120"$ ,  $I = 224737 \text{ in}^4$ ,  $S_{bot} = 6625 \text{ in}^3$ ;  $Q_{deck} = 654 \text{ in}^3$   
(see next page)

- Computed strain:  $\epsilon_c = \frac{368.2 \text{ k} \times 12}{29000 \times 6625} \times 10^6 = 230 \mu\epsilon$  vs  $\epsilon_t = 145$  measured

$$\epsilon_c / \epsilon_t = 230 / 145 = 1.59$$

Girder Section Properties -- W33x130

interior girder, slab = 8.76" at girder CL

haunch =	0									
component	width	thickness	modular ratio	transf. area	y	Area*y	I_bar	A*y^2		
Slab	120.00	11	10	132.00	38.62	5098.1	1331.0	3242.9		
Top Bars	0	0	1	0.00	38.62	0.0	0.0	0.0		
Top Flange	11.51	0.87	1	10.03	32.69	327.7	0.6	9.6		
Web	31.38	0.58	1	18.20	16.56	301.4	1493.5	5324.8		
Bot. Flange	11.51	0.87	1	10.03	0.44	4.4	0.6	11070.2		
				170		5731.6	2825.8	19647.4		

Note: flange thicknesses increased slightly to give correct I for non-composite section

$y_{bar} = 33.7$  in from bottom  
 Moment of Inertia =  $22473$  in<sup>4</sup>  
 $Q_{deck} = 654$   
 $S_{bottom} = 667.5$

654 in<sup>3</sup> -- three calculations, all the same

W. DAVIDS  
4/28/14  
6/

ASSESS STRAIN RESPONSE:

Can we extrapolate composite action to 1.33W?

- per NCHRP Research Results Digest 234, 100 psi bond stress can be reliably developed @ interface

- Max FB shear from test = 63.0 k

$$- \frac{VQ}{Ib} \approx \frac{63 \times 65 \text{ in}^3}{22473 \times 11.51"} \times 1000 \frac{\text{lb}}{\text{ft}} = 159 \text{ psi} > 100 \text{ psi}$$

∴ composite action is NOT reliable

- However, the ratio  $E_c/E_f = 1.59$  is correctly (and conservatively) based on the presence of composite action.

-  $T/W \geq 0.7$ ; results cannot be directly extrapolated to 1.33W, since composite action was observed but is not likely to be reliable


- Girder flange is clearly fully braced against LTB, and capacity calculations can be based on the section developing  $M_p$ .

- A safe estimate of the RF modification is


$$K = 1 + 0.5 \times (1.59 - 1) = \underline{\underline{1.30}}$$

VERIFY

Assume 7.5'



Trucks traveled from end of span to past midspan during test





Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

Project: Bridge Load Testing/Rating - Brownville


By: KMG Date: 4/8/14

Subject: Test Vehicle Measurements

Checked: \_\_\_\_\_ Date: \_\_\_\_\_

License Plate Number T01-443  
Truck Designation (1 or 2) 4

Weighed By: DOT  
Dimensions by: CF



Total Vehicle Weight 51,850



Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

Project: Bridge Load Testing/Rating - Brownville

By: KMG Date: 4/8/14

Subject: Test Vehicle Measurements


Checked: Date:

License Plate Number 701-835

Weighed By: DOT

Truck Designation (1 or 2) 3

Dimensions by: CP



Total Vehicle Weight 53,000



Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

Project: Bridge Load Testing/Rating - Brownville


By: KMG Date: 4/8/14

Subject: Test Vehicle Measurements

Checked: Date:

License Plate Number TO 1-241  
Truck Designation (1 or 2) 2

Weighed By: DOT  
Dimensions by: CF



Total Vehicle Weight 57,900



Phone: (207) 581-2123  
Fax: (207) 581-2074  
www.aewc.umaine.edu

Page:
Project No.:
By: <u>KMG</u> Date: <u>4/8/14</u>
Checked: _____ Date: _____

Project: Bridge Load Testing/Rating - Brownville

Subject: Test Vehicle Measurements

License Plate Number T01-707 Weighed By: DOT

Truck Designation (1 or 2) 1 Dimensions by: CF

Axle Weight <u>20,000</u>	<u>9,700</u>	<u>10,300</u>	Axle Spacing <u>53"</u>
Axle Weight <u>19700</u>	<u>10,800</u>	<u>8,900</u>	
		<u>22"</u>	
Axle Weight <u>16500</u>	<u>8,500</u>	<u>8,400</u>	Axle Spacing <u>191"</u>
		<u>11 1/2"</u>	
	Wheel Spacing <u>91"</u>		
Total Vehicle Weight <u>56,600</u>			

TOP  
MIDDLE  
BOTTOM

T01-241

T01-207

3810  
3064  
3074

3066  
3062

3068

5'-6"

3060  
3057  
3067

6"

3069  
3070  
3811

T01-835

T01-447


5'-6"

3055  
3058  
3056

3071  
3075  
3063

1'-9"

1'-9"



# CHESTER

W. DAVIDS

4/28/14

✓

## BRIDGE PROPERTIES:

STRINGERS - W18x55 (interior) @ 5'-0", 2' to FB and

FBs - W30x124, span = 24', spaced @ 25'-0"

DECK - 5 3/4" CONCRETE + 2" ASPHALT WS.

## MAX MEASURED FB STRAINS

- 410.3  $\mu\epsilon$  max w/ 4 trucks
  - 229.3  $\mu\epsilon$  max w/ 2 trucks
- } see p. 2

strains @ mid-depth  $\approx 0$ , large compression @ top, girders are non-composite. Consistent with construction details. Moments near ends do not indicate fixity.

## FB MOMENTS DUE TO TRUCK LOADS:

- Computed using lever rule, field-measured wheel loads, previously verified spread sheet.
- 2 truck moment: 239.6 ft-k @ gage location, 258.0 @ mid-span
- 4 truck moment: 457.2 ft-k @ gage location, 487.3 @ mid-span
- HL-93+IM: 540<sup>ft-k</sup> @ mid-span (see p. 3)



CHESTER

W. DAVIDS  
4/20/2014  
2/


-165.4 ME (2 trucks)  
-333 ME (4 trucks)




2 trucks: 2.93 ME  
4 trucks: -2.82 ME



3066  
2 trucks: 229.3 ME  
4 trucks: 410.2 ME  
1767



HL-9.3 LOADING



LANE LOAD:  $P_1 = P_5 = 0.064 \times 2.5 \times 25' = 4^k$   $\frac{2 \times 4}{+ 3 \times 8}$   
 $P_2 = P_3 = P_4 = 0.064 \times 5 \times 25' = 8^k$   
 $\Sigma 32 = 0.064 \times 25 \times 20 = 32 \checkmark$

$M_{lane} = \frac{2 \times 4 \times 22 \times 2}{24} \times \frac{12}{22} + \frac{2 \times 8 \times 17 \times 7}{24} \times \frac{12}{17} + \frac{8 \times 24}{4}$   
 $= 84.6 + 56 + 48 = 112 \text{ ft}\cdot\text{k} \text{ (mid-span)}$

$M_{random} = 322^m \text{ @ mid-span (No Im)}$

$M_{HL9.3+im} = 1.33 \times 322 + 112 = 540^m$

our 4-truck moment =  $487.3^m \text{ @ mid-span}$

$T/W = 487.3 / 540 = 0.90 > 0.70 \checkmark$  OK

ASSESS STRAIN RESPONSE

2 trucks:  $M/s = \frac{239.6 \times 12}{29000 \times 355 \text{ in}^2} \times (1 \times 10^6) = 279 \mu\epsilon$  vs. 229.2  $\mu\epsilon$  measured

4 trucks:  $M/s = \frac{457.2 \times 12}{29000 \times 355} \times 10^6 = 533 \mu\epsilon$  vs. 410.2  $\mu\epsilon$  measured.

$\frac{279.2}{239.6} = 1.16 \mu\epsilon/\mu\epsilon$

$\frac{533 \mu\epsilon}{457.2} = 1.16 \mu\epsilon/\mu\epsilon$

} Very linear response, consistent w/ non-composite section @ all load levels.  $\therefore$  can extrapolate

$E_c/E_T = 533/410.2 = 1.30$

RF modifier:  $K = 1 + K_a K_b = 1 + (1.30 - 1.0) \times 1.0 = 1.30$

$\therefore$  Can increase RF by 1.30

EXAMINE RESIDUAL CAPACITY: say 3" ws; 2" mduns + 5 3/4" SLABS

DL @ each FB  $\approx \left( \frac{8.75" \times 150 \text{pcf} \times 5' + 55 \#}{12} \right) \times \frac{25'}{1000} = 15.0 \text{ k/stranger}$

$M_{DL} \approx \frac{15 \times 24}{4} + 2 \times 15 \times \frac{7 \times 17}{24} \times \frac{12}{17} + 2 \times 15 \times \left( \frac{2 \times 22}{24} \right) \times \frac{12}{22} + \frac{0.124 \times 24^2}{8}$


$= 90 + 105 + 30 + 9 = 234 \mu\epsilon$

expected stress @  $M_{DL} + 1.33 \text{ HL93} + 1M$ :

$\frac{234 \times 12}{355} + 410.2 \mu\epsilon \times \left( \frac{540 \text{ in}}{487 \text{ in}} \right) \times \frac{29000}{1 \times 10^6} = 7.9 \text{ ksi} + 13.2 \text{ ksi} = 21.1 \text{ ksi}$

ratio up to HL-93+1M

$FS = \frac{33}{21.1} = \underline{\underline{1.56}}$







Project: Chester Bridge Test

By: KMG Date: 4/10/14


Subject: Test Vehicle Measurements

Checked: \_\_\_\_\_ Date: \_\_\_\_\_

*DWANE*

License Plate Number 701-194  
 Truck Designation (1 or 2) 2

Weighed By: CSF  
 Dimensions by: KMG



H42

Total Vehicle Weight 55500

*Front*



Advanced Structures & Composites Center

Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

Project:

Chester Bridge

By:

Date:

KMG

4/10/14

Subject:

Test Vehicle Measurements

Checked:

Date:

License Plate Number Pa1-228

Weighed By: CSF

Truck Designation (1 or 2) 1

Dimensions by: KMG

MMT/LP



Axle Weight 9100



=93'



11750

54"  
Axle Spacing

#1

Axle Weight 10000



11000



16'8"  
Axle Spacing

52'3"  
for 5 revolutions


Axle Weight 7400



FRONT



8700



Total Vehicle Weight 58050



Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

Project: CHESTER BRIDGE TEST


By: KMG Date:

Subject: Test Vehicle Measurements

Checked: Date:

License Plate Number TDI-225  
Truck Designation (1 or 2) \_\_\_\_\_

Weighed By: CSF  
Dimensions by: CSF



#3



Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

Project: CHESTER BRIDGE TEST

By: \_\_\_\_\_ Date: \_\_\_\_\_  
KMG

Subject: Test Vehicle Measurements


Checked: \_\_\_\_\_ Date: \_\_\_\_\_

License Plate Number 701-180

Weighed By: CSP

Truck Designation (1 or 2) \_\_\_\_\_

Dimensions by: CSP



#4

# T3 - INDIAN PURCHASE

W. DAVIDS

4/23/14

✓

## BRIDGE PROPERTIES:

- STRINGERS: W21x68x5'-3" o/c (EXTERIOR SMALLER)
- FB: W36x150 SPALED @ 20'-0", 26.16' SPAN
- DECK: 8'4" (INCL 3" CONCR WS, FIELD VERIFIED)


## MAX. MEASURED FB STRAINS:

- 330  $\mu\epsilon$  tension w/ 4 trucks
  - 163  $\mu\epsilon$  tension w/ 2 trucks
- } See p. 2
- strains @ mid-depth  $\approx 0$ , significant compression @ top, girders are non-composite. Consistent w/ construction details, which shows no flange embedment in deck.
  - strains nearer ends indicate no fracturing @ FB splices.

## FB MOMENTS DUE TO TRUCK LOADS:

- Computed using lever rule, field-measured wheel loads, previously verified spread sheet
- 4 truck moment = 587.4  $\text{k}\cdot\text{ft}$  @ gage location (21" off midspan)
- 2 truck moment = 214.5  $\text{k}\cdot\text{ft}$  @ gage location.
- 12-93 + 1m (tandem + lane) = 624.4  $\text{k}\cdot\text{ft}$  @ mid-span (see pp. 3 & 4)

T3- INDIAN PURCHASE




T-3 INDIAN PURCHASE

W. DAVIDS

4/23/14

3/

H<sub>93</sub> + 1m LOAD:



Due to Tandems:

$$P_1 = \left(1 + \frac{26.16}{30}\right) \times \frac{1.866}{5.25} \times \frac{2.75}{5.25} \times 12.5 = 12.22 = P_5$$

$$P_2 = 1.866 \times \left(\frac{2.75}{5.25} + \frac{2}{5.25}\right) \times 12.5 = 20k = P_4$$

$$P_3 = 1.866 \times 2 \times \frac{3.25}{5.25} \times 12.5 = 28.89k$$

agree w/ spreadsheet

$M_{tandem} = 352 \text{ ft-k (spreadsheet)}$

Due to lane:

$$P_1 = P_5 = \left(0.064 \times \frac{4.75 \times 4.75}{2} \times \frac{1}{5.25}\right) \times 30' = 4.13k$$

$$P_2 = P_4 = 0.064 \times \left(\frac{4.75 \times 2.875}{5.25} + \frac{5.25}{2}\right) \times 30' = 10.03k$$

$$P_1 = 0.064 \times 5.25 \times 30' = 10.08k$$

$$\left. \begin{aligned} &2 \times 4.13 + 2 \times 10.03 \\ &+ 10.08 = 38.4k \\ &0.064 \times 20' \times 20' = 38.4k \end{aligned} \right\}$$

$$M_{lane} = \frac{10.08 \times 26.16}{4} + 2 \times \left( \frac{10.03 \times 18.33 \times 7.83}{26.16} \times \frac{13.08}{18.33} \right) + 2 \times \left( \frac{4.13 \times 2.58 \times 23.58}{26.16} \times \frac{13.08}{23.58} \right)$$

$$= 65.92 + 2 \times 39.27 + 2 \times 5.33 = 155.1 \text{ ft-k}$$

T3 - INDIAN PURCHASE

W. DAVIDS

4/23/14

4/

TOTAL HL-93 + 1M LOAD:

$$1.33 \times 352'' + 155.1'' = 624.4'' \quad (\text{peak @ mid-span})$$

Using lever rule calculations, test produced 634'' > HL-93!

## T3- INDIAN PURCHASE

W. DAVIDS

4/23/14

51

### ASSESS STRAIN RESPONSE

$$2 \text{ trucks: } M = 314.5^{\text{m}}; \epsilon_c = \frac{M}{ES} = \frac{314.5 \times 12}{29000 \times 504} \times 1 \times 10^6 = 258 \mu\epsilon$$

$$\text{measured strain} = \epsilon_t = 163 \mu\epsilon; \frac{\epsilon_c}{\epsilon_t} = 1.58$$

$$4 \text{ trucks: } M = 587.4^{\text{m}}; \epsilon_c = \frac{587.4 \times 12}{29000 \times 504} \times 1 \times 10^6 = 482 \mu\epsilon$$

$$\text{measured strain} = \epsilon_t = 330 \mu\epsilon; \frac{\epsilon_c}{\epsilon_t} = 1.46$$

$$\text{linearity of strain response: } \frac{587.4}{314.5} \times 163 = 304 \mu\epsilon \text{ vs. } 330 \mu\epsilon$$


$$\frac{330 - 304}{304} \times 100 = 8.6\%$$

very close to linear increase

- Given that 4-truck load produced moment in excess of  $HL93 + 1M$ , the nearly linear increase in measured strain when going from 2 truck to 4 truck loading, & the lack of composite action, extrapolation to 1.33W is reasonable.

$$\text{- BE modifier} = K = 1 + K_a K_b = 1 + (1.46 - 1) \times 1 = \underline{\underline{1.46}}$$


IT- INDIAN PURCHASE



to Bramble


Trucks traveled from end of span to past midspan during test

T3- INDIAN PURCHASE



T3- INDIAN PURCHASE

T3 - INDIAN PURCHASE



Project: T3-INDIAN PURCHASE U TEST


By: KMG Date: 4/15/14

Subject: Test Vehicle Measurements

Checked: \_\_\_\_\_ Date: \_\_\_\_\_

License Plate Number 101-228  
Truck Designation (1 or 2) #2

Weighed By: KMG  
Dimensions by: KMG



Total Vehicle Weight 55,050



Phone: (207) 581-2123

Fax: (207) 581-2074

www.aewc.umaine.edu

Page:

Project No.:

979

Project:

Bridge Load Testing/Rating T3- Indian Purchase

By:

Date: 4/15/14

KMG

Subject:


Test Vehicle Measurements

Checked:

Date:

License Plate Number 701-180  
Truck Designation (1 or 2) 44

Weighed By: KMG  
Dimensions by: KMG



Total Vehicle Weight 68,750






Phone: (207) 581-2123  
Fax: (207) 581-2074  
www.aewc.umaine.edu

Page:
Project No.: 979
By: KMG      Date: 4/15/14
Checked:      Date:

Project: Bridge Load Testing/Rating <u>TS-Indian Purchase</u>
Subject: Test Vehicle Measurements

License Plate Number 701-225  
Truck Designation (1 or 2) #1

Weighed By: KMG  
Dimensions by: KMG



Total Vehicle Weight 58,150


## APPENDIX C: PRELIMINARY CALCULATIONS

“preliminary\_FB\_analysis.pdf”

BROWNVILLE - PRELIMINARY FB ANALYSIS

FB  $\approx$  W35x130, span  $\approx$  25'

HEAVIEST 4-TRUCK LOADING:




$$P_1 = \frac{1.8}{5} [0.131 \times 8.5 + (0.8133 + 1 + 0.677 + 0.490) \times 10] = \frac{1.8}{5} \times 30.92 = 11.13^k$$

$$P_2 = \left(\frac{3.2}{5} + \frac{1.3}{5.5}\right) \times 30.92 = 27.1^k \quad ; \quad P_3 = \left(\frac{4.2}{5} + \frac{4.2}{5}\right) \times 30.92 = 51.95^k$$

$$P_4 = \left(\frac{1.3}{5.5} + \frac{3.2}{5}\right) \times 30.92 = 27.1^k \quad ; \quad P_5 = \frac{1.8}{5} \times 30.92 = 11.13^k$$

# BROWNVILLE - PRELIMINARY FB ANALYSIS

W. Davids 2/  
3/10/2014



$$\begin{aligned} \sum M_i = 0: & 11.13 \times 1 \rightarrow 11.13 \\ & + 27.1 \times 6 \rightarrow 162.6 \\ & + 52.0 \times 11.5 \rightarrow 598 \\ & + 27.1 \times 17 \rightarrow 460.7 \\ & + 11.13 \times 22 \rightarrow 244.9 \\ & - R_2 \times 23 \rightarrow 1477.3 \\ & = 0 \end{aligned}$$

$\Rightarrow R_2 = 64.23$   
 $R_1 = 64.23$

$$M_{test} = 472.73 \Rightarrow \sigma_{test} \approx \frac{472.73 \times 12}{406} = 14.0 \text{ ksi} \Rightarrow \epsilon_{test} = 483 \mu\epsilon$$

$$\sigma_{DL} \text{ (plans)} \approx \frac{3356700/1000}{406} \approx 8.27$$


(peak @ Howland = 245  $\mu\epsilon$ , observed, predicted)  
 $\frac{707 \times 12}{580 \times 29000} = 504$ )

$$FS \text{ against yield} \approx \frac{30.0}{22.3} = 1.35$$

(1935)

REDUNVILLE

Future Sidewalk  
Not part of con-  
tract.



24'4"  
9" holes through webs of end floor beams between all stringers to facilitate painting.

TYPICAL SECTIONS


FB spacing = 23'-2 1/2"

ROADWAY STRINGERS

FB span  $\approx 11' + 5' + 5' + 1' + 1' \approx 23'$   
 $= 23.21'$

<u>INTERIOR</u>	<u>EXTERIOR ROADWAY</u>	<u>EXTERIOR SIDEWALK</u>
Slab 479	Slab 300	Slab 300
WS 275	WS 150	WS 150
Cur 73	Cur 81	Cur 81
<u>827</u>	Beam 55	SW 236
	<u>586</u>	Beam 59
D.L.M. 656600	D.L.M. 468500	D.L.M. 655800
L.L.M. 1012000	L.L.M. 662400	L.L.M. 662400
Imp 302100	Imp 223900	Imp 223700
100% 1354100	100% 886300	100% 886300
<u>3360800</u>	<u>2201100</u>	<u>2828400</u>
S-100.2 B21.73 S-150.7	S-93.4 B18.55 S-98.2	S-101.2 B21.59 S-11

FLOOR BEAM



DEAD LOAD

$R_L = \frac{19000 \cdot 167 + 19021 \cdot 50 \cdot 51 + 13500 \cdot 22 \cdot 67}{24 \cdot 33} = 42426$

D.L.M.  $(42426 \cdot 12 \cdot 11 + 19021 \cdot 55 + 13500 \cdot 10 \cdot 5) / 12 = 3239500$

Uniform Mom  $132 \cdot 24 \cdot 33 \cdot 15 = 117200$

3356700

L.L.M. 2430950

Imp 709850

100% 3100800

9638300

RL - 24660

$\approx W33 \times 120$   
 $S = 406 \text{ in}^2$


S 401.6 B-3-132 S-4

OWN  
 BRIDGE 3:

CHESTER - PRELIMINARY FB ANALYSIS

W. DAVIDS  
3/10/2014

4/



$$P_1 = \frac{2.3}{5} \left( 0.193 \times 8.5 + (0.827 + 1.0 + 0.72 + 0.527) \times 10 \right) = \frac{2.3}{5} \times 32.4 = 14.9^k$$

$$P_2 = \left( \frac{2.7}{5} + \frac{1.3}{5} \right) \times 32.4 = 25.9^k$$

$$P_3 = \left( \frac{3.7}{5} + \frac{3.7}{5} \right) \times 32.4 = 48.0^k$$


$$P_4 = \left( \frac{1.3}{5} + \frac{2.7}{5} \right) \times 32.4 = 25.9^k$$

$$P_5 = \frac{2.3}{5} \times 32.4 = 14.9^k$$

# CHESTER - PRELIMINARY FB ANALYSIS

W. DAVIDS  
3/10/2014

5/



$$M_U = 64.8 \times 2 + 49.9 \times 5 + 24 \times 5 = 499.1 \text{ ft}\cdot\text{k}$$

$$f_{LL} = \frac{499.1 \times 12}{355 \text{ in}^3} = 16.9 \text{ ksi} \Rightarrow \epsilon_{\text{test}} = \underline{\underline{583 \mu\epsilon}}$$

- say 3" ws today

$$DL = \left( \frac{8.75 \times 150}{12} \times 5' + 55 \right) \frac{25'}{1000} = 15^k / \text{stringer}$$


$$M_{DL} = 15 \times \frac{24}{4} + 2 \times 15 \times \left( \frac{7 \times 17}{24} \times \frac{12}{17} \right) + 2 \times 15 \times \left( \frac{2 \times 22}{24} \times \frac{12}{22} \right) + \frac{0.124 \times 24^2}{8}$$

$$= 90 + 105 + 30 + 8.93 = 234 \text{ ft}\cdot\text{k}$$

$$f_{DL} = \frac{234 \times 12}{355} = 7.91 \text{ ksi} \sim FS = \frac{33}{16.9 + 7.91} = 1.33$$

CHESTER

6/



FB Spacing = 25'-0"

11'-0"

9'-11"

Roadway

15'-0" Min. Vert. Clearance

(of washer) with slab

Note 809-2  
Can we verify?

5/8" Reinf. Conc. Slab  
2" Bit. Conc. Wearing Surface  
Set Stringers into slab 1/2"

2" Crown

Interior Stringers  
18" WF x 55#  
Conn. Ls 4 x 3 1/2 x 1/8"

Provide shims between stringer conn. Ls and floor beam web.

Exterior Stringers  
18" WF x 50#  
Conn. Ls 4 x 3 1/2 x 1/8"

Floor beams 30" WF x 124#

say 2'-0" (Full width)

5'-0"

5'-0"

12'-8"

2'-8"

3'-4"

2'-8"

4'-0"

# I3-INDIAN PURCHASE - PRELIMINARY FB ANALYSIS

W. DAVIDS

2/11/2014

REFER TO P.4 - STRINGER SPACING = 5'-3" & FB SP. = 30'

$$\text{COEFF. TOP-TO-BOTTOM} = \frac{30 - 15.83' - 4.33'}{30} = 0.328$$

$$\frac{30 - 4.33}{30} = 0.856$$

$$\frac{30 - 7.5}{30} = 0.75$$

$$\frac{30 - 7.5 - 4.33}{30} = 0.606$$

$$\frac{30 - 7.5 - 4.33 - 15.83'}{30} = 0.078 \quad (\text{stem axle on lower truck contributes})$$

$$P_1 = \frac{2.05}{5.25} \left( \overset{3.45}{(0.328 + 0.078)} \times 8.5 + \overset{3.212 \times 10 = 32.12}{(0.856 + 1.0 + 0.75 + 0.606)} \times 10 \right) = \frac{2.05}{5.25} \times 35.6 = 13.9^k$$

$$P_2 = \left( \frac{3.2}{5.25} + \frac{1.3}{5.25} \right) \times 35.6 = 30.5^k$$

$$P_3 = \left( \frac{3.95}{5.25} + \frac{3.95}{5.25} \right) \times 35.6 = 53.6^k$$


$$P_4 = \left( \frac{1.3}{5.25} + \frac{3.2}{5.25} \right) \times 35.6 = 30.5^k$$

$$P_5 = \frac{2.05}{5.25} \times 35.6 = 13.9^k$$

T3 - INDIAN PURCHASE - PRELIMINARY FB ANALYSIS

W. DAVIDS  
3/11/2014

8/



$$R_1 = R_2 = 13.9 + 30.5 + \frac{53.6}{2} = 71.2 \text{ k}$$

$$\sigma_{LL} = \frac{625.2 \times 12}{504 \text{ in}^3} = 14.9 \text{ ksi} \Rightarrow \epsilon \approx 514 \mu\epsilon$$

(W36x150)

$$DL \text{ stringer} \approx \left( \frac{8.75 \times 5.25 \times 150}{12} + 68 \right) \frac{\times 30'}{1000} = 19.3 \text{ k}$$

$$M_{DL} \approx \frac{19.3 \times 26.2^2}{4} + \left( \frac{19.3 \times 7.25 \times 18.35}{26.2} \times \frac{13.1}{18.75} \right) \times 2 + \frac{19.3 \times 26 \times 23.6 \times \frac{13.1}{23.6}}{26.2} + \frac{0.150 \times 26.2^2}{8} \approx 126.4 + 141.1 + 50.2 + 12.9 = 331 \text{ k-in}$$

$$\sigma_{DL} = \frac{331 \times 12}{504} = 7.9 \text{ ksi}$$

$$FS \approx \frac{33}{14.9 + 7.9} = 1.45 \checkmark \text{ OK}$$

