58668	



\$1,771.10

LUPC Received 7/1/2025

Tracking No.

Permit No.

Fee Received

# Property Information – LUPC Nonresidential Development Application

**PROPERTY INFORMATION.** Provide the following details about your property location. Tax map, plan, and lot numbers are listed on your property tax bill. If you lease your property, check your lease to find out whether any unique lease lot numbers have been assigned to the property.

Applicant	Township, Town	or Plantation	County			
Burnt Jacket Holding I, LLC	Beaver Cove		Piscataquis			
Tax Map, Plan, and Lot Numbers [list all applicable; check tax bill(s)]						
001-001-A						
Lot size (in acres, or in square feet if	less than 1 acre)	Deed Book and Page applicable (include of assigned by a prope	any lessor or lease			
1423.5 acres		, , ,	ok 2873 Page	52		
All Zoning on Property (check the LU Guidance Map)	PC Land Use	Zoning at Developm General Manager	ment (M-GN), Re			
M-GN, D-RS, P-WL1, P-WL3, I	P-GP, P-SL2	(D-RS), Protection Forested (P-WL3)		retianus -		
Road Frontage: List the name(s) and feet) for any public or private roads, of-way adjacent to your lot:  Lily Bay Rd. Road #1 Fron	or other rights-	Water Frontage: Listed feet) for any lakes, punnamed), or coastilot:  Moowwaterbody #1	oonds, rivers, stre al wetlands on or	ams (named and adjacent to your		
Burnt Jacket Rd pvt.*  Road #2 Allagash Rdpvt.*  From	ntage <u>5,500</u> ft.	Waterbody #2		Frontageft.		
If there is no road frontage, describe *Note: Burnt Jacket Road and All			f lot 001-001-A			
<b>LUPC Approved Subdivision:</b> If the loand lot numbers:	ot is part of an LU	PC approved subdiv	ision, provide the	subdivision permit		
Subdivision Permit #	and Lot #	IA (usually inc	cluded in deed des	scription)		
BRIEF PROJECT SUMMARY (include proposed zoning if submitting an application for zone change; include proposed project name, if applicable)  The project consists of a utility line extension comprised of: two CMP poles and overhead wires extending westerly from Lily Bay Road for +/-60 ft, then underground utility line extension along Burnt Jacket Road for +/-12,651 ft, consisting of underground trench, +/-3' width, containing conduit, cables and electrical vaults, and will then branch off to follow a proposed new road on the applicant's property. A separate permit for this road (and the conduit within the trench was issued by LUPC on 6/25/25 (RP-3313).						
APPLICATION FEE (see the <u>Application Fee exhibit</u> for more information, including surcharges if paying						
online) Please check <b>one</b> of the boxe		, mar amplication for				
<ul><li>✓ I have enclosed a check or money order to pay my application fee.</li><li>☐ I would like to pay my application fee online. Please contact me with the necessary information.</li></ul>						
	idon lee olillie. F	icase contact me wi	un une necessary	iiiioiiiiatioii.		




#### NARRATIVE DIRECTIONS:

The site is located on the Burnt Jacket Mountain peninsula off of Lily Bay Road. From Greenville, ME, head north on Main Street for approximately 7.9 miles. Turn west onto Burnt Jacket Road.

LUPC Received onto Burnt Jacket Road. The site commences near the intersection of Lily Bay Road and Burnt Jacket Road. Page 5


# EXHIBIT 1 - DIRECTIONS AND LOCATION MAP - CONTINUED:



The project site is located off Lily Bay Road along and off Burnt Jacket Road. The project begins near the intersection of Lily Bay Road and Burnt Jacket Road, and is located entirely on private property.

- - Property Line

Proposed Utility Line Extension



## **EXHIBIT 2 - PROJECT DESCRIPTION:**

The Burnt Jacket Holding I, LLC ownership has been used as commercial timberland. The property and the proposed project site are currently undeveloped and are crossed by a number of land management roads, including Burnt Jacket Road. BP-17544 has been issued for a residence and ancillary structures. A Non-residential Permit (RP-3313) was issued by LUPC on 6/25/2025 for construction of a new road to serve residential and land management uses on the applicant's property.

The project consists of an underground utility line extension to serve residential and land management uses on the applicant's property. The proposed line extension will extend westerly from poles along Lily Bay Road. Central Maine Power will install two additional poles and overhead wires on the applicant's property near Lily Bay Road. The utility line will then transition underground via a privately owned underground conduit with line and low voltage cables.

The CMP installation of two poles and overhead wires will extend +/-60 feet extending westerly from the applicant's easterly boundary at Lily Bay Road and will then transition underground. The proposed underground utility line extension (see Exhibit 10 and the detailed site plan of infrastructure showing location of conduit and underground electrical vaults to be located below ground within the shoulder of the existing roadway of Burnt Jacket Road. The underground utility lines will then leave the Burnt Jacket Road area and be installed within the conduit shown as part of the detailed site plans included in Non-Residential Permit RP-3313 (see dotted line on Site Plan previous page).

Once the underground utility extension project is completed, except for the initial CMP poles near Lily Bay Road, the project infrastructure will be below ground within the shoulder of the existing roadway of Burnt Jacket Road.

EXHIBIT 3 - DEED:

LUPC Received
7/1/2025

Please refer to BP-17544 and to the Non-Residential Permit received on 6/25/2025 (RP-3313). The Burnt Jacket Holding I, LLC deed information has not changed.

Book 2873, Page 52

# **Section 4 - Application Fee Calculation**

	Fee	
1	\$500.00	Base Fee - Non-residential development (1.02.B.1.r.)
2	\$1,271.10	Activity Specific Fee
3	\$0.00	Fees for Uses Allowed by Special Exception (see Ch 10.21)
4	\$0.00	After-the-Fact-Fee
	\$1,771.10	

### **Activity Specific Fees**

2g	Utility	Lines	and	Pipe	lines
----	---------	-------	-----	------	-------

0.10	Per linear foot of utility line or pipe
12,711	Linear feet
\$1,271.10	Fee

#### **EXHIBIT 5B - FINANCIAL CAPACITY:**

1735 Market Street | 26<sup>th</sup> Floor| Philadelphia, PA 19103 |Tel: 215-814-7223| gaspare.cintorrino@gs.com

Gaspare Cintorrino
Vice President
Private Wealth Management
Asset and Wealth Management Division

Goldman Sachs

April 29, 2025

Maine Land Use Planning Commission (LUPC) 22 State House Sta, Augusta, ME 04333

Re: Burnt Jacket Holding I, LLC (EA0-xxx08-3)

To Whom It May Concern:

We are providing this letter to you at the request of our client, Burnt Jacket Holding I, LLC, to confirm certain information regarding assets and/or funds held in the above-referenced account (the "Account") maintained with Goldman Sachs & Co. LLC.

As of the close of business on April 28, 2025, the approximate market value of the Account was in excess of \$2,250,000.

This letter is provided for your information only and should be handled in a confidential manner. The content of this letter is based on information we believe to be reliable, but we do not represent that such information is accurate or complete, and it should not be relied on as such. Market values are current as of the date set forth above and are subject to change for various reasons, including market fluctuation, client trading and withdrawals. The above market value does not take into consideration any liabilities or indebtedness the client may have outside of the Account either at Goldman Sachs or with another party.

Please contact us if we can be of further assistance.

Very truly yours,

cc: Burnt Jacket Holding I, LLC

Cintorrino



Proposal Submitted To

Beaconsfield

Greenville, ME 04441

Date

Feb.28, 2025

Street

Job Name

Underground electrical trench

City, State and Zip Code

We propose hereby to furnish material and labor - complete in accordance with specifications below for the sum of: please see below

All material is guaranteed to be as specified. All work is to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from specifications below involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strike, accidents or delays beyond our control. Our workers are fully covered by insurance.

**Authorized Signature** 

Mike Theriault

Note: This proposal may be withdrawn by us if not accepted within 30 days.

We hereby submit specifications and estimates for:

#### **Proposal to Include:**

Mobilization and all erosion control measures in place.

Coordination with dig safe, safety controls and inspection.

Excavation of approximately 12,717ft of underground electrical trench.

Depth and width TBD by code and actual conditions on the ground.

Trench bottom will be 6" of bedding sand and following with all back fill consisting of compacted 1/2"minus sand per code.

Cost for ledge rock removal will be extra.

Conduits installed by others.

All permits by owner.

This proposal is for estimating purposes only. Actual quote will be determined when all of the construction details are worked out.

- #1. Estimate for ideal conditions with very little rock removal.  $$31.00 \text{ per/ft} \times 12,717 =$ \$394,227.00
- #2. Estimate for difficult digging with alot of ledge and rocks.  $$45.00 \text{ per/ft} \times 12,717 =$ \$572,265.00
- #3. Removal of rocks/ledge on shoulder of road......Price to be determined..... Many possibilities for moving and sizing these rocks for future use on the project

Acceptance of Proposal - The above prices, specifications and	Signature
conditions are satisfactory and are hereby accepted. You are authorized	
to do the work as specified. Payment will be made as outlined above.	
Date of Acceptance	

# **EXHIBIT 5B - FINANCIAL CAPACITY:**

### **ESTIMATE**

Powerline Construction Inc. 1328 Milo Rd Sebec, ME 04481 pwrlineconstruction@outlook.com +1 (207) 949-6777



Bill to

Karen Thomas Associates, Inc.

#### Estimate details

Estimate no.: 1158

Estimate date: 01/08/2025

#	B		01	Б.	
#	Product or service	Description	Qty	Rate	Amount
1.	Line Extension	12,500'-13,000' Primary URD line extension Powerline to show up once all conduit is laid, all 11 concrete pull boxes are installed and all 3 sectionalizer volts are installed. Powerline to build riser pole on third pole in, using (4) stand off brackets, running conduit up the pole, furnish & install (1) cross arm (3) arm brackets (3) cable positioning brackets (3) terminations (3) Lightning arrestors, coated copper tap wire. Copper down ground, copper ground rod, staples & aluminum connectors.  Powerline to install 40,000' of customer supplied 4/0 Aluminum primary URD wire. Will need (18 reels of 2500') equaling a total of 45,000 feet.  Provide & Install approximately (15) 200 Amp Elbows, (15) Splices & (3) Terminations BFS to supply all wire.	1	\$281,250.00	\$281,250.00
2.	Job	Powerline to provide and install (3) Sectionalizer Cabinets	1	\$34,750.00	\$34,750.00
3.	Job	Provide & Install Milbank S2718FBXLC Provide & Install conduit riser and supports per CMP Details Electrical Permit	1	\$7,400.00	\$7,400.00
4.	Job	Furnish & Install Fiberglass Conduit Complete, Labor & Equipment Estimated lead time once the order is placed is 5 weeks Sales tax & permit included  If conduit is furnished by BFS Value \$465,000	1	\$1,219,500.00	\$1,219,500.00

LUPC Received

7/1/2025

If Misc. Materials are furnished by BFS

Value \$145,000

- -Fiberglass Fittings
- -Adhesive
- -Conduit Spacers
- -Mule Line
- -Burial Tape
- -Grounding (per details)

#### \*\*\*NOTE\*\*\*

Substitute the Fiberglass conduits for schedule 80 PVC for a credit of \$200,000

from base bid

-Substitute the Fiberglass conduits for schedule 40 PVC for a credit of \$290,000 from base bid

Bid Excludes:

Cutting, Patching & Painting Saw Cutting or Concrete

Digging, Trenching, Ledge removal, or

backfill

Precast Vaults or Boxes

Press-Seal Gaskets (Come in precast

vaults)

Utility Charges

Bond

Wage Scale

Tariffs

Quotes good for 30 days

Total

\$1,542,900.00

Note to customer
LEDGE IS NOT INCLUDED

Accepted date

Accepted by

# **EXHIBIT 5B - FINANCIAL CAPACITY:**

### **ESTIMATE**

Powerline Construction Inc. 1328 Milo Rd Sebec, ME 04481 pwrlineconstruction@outlook.com +1 (207) 949-6777



Bill to

Karen Thomas Associates, Inc.

#### Estimate details

Estimate no.: 1176

Estimate date: 03/31/2025

# Product or service	Description	Qty	Rate	Amount
1. Job	Furnish and deliver the following Precast to	1	\$86,500.00	\$86,500.00
	the site.			
	Placement will be by earthwork contractor.			
	3- Sectionalizer Cabinet Vaults (detail 2 on			
	U201)			
	11- Electrical MV Pull Box with Covers			
	"Power" (detail 3 on U201)			
	5 - Communications Concrete Vault with			
	Covers "Communications" (detail 5 on			
	U201)			
	Bid Excludes:			
	Cutting, Patching & Painting			
	Saw Cutting or Concrete			
	Digging, Trenching, Ledge removal, or			
	Backfill			
	Stone or drainage pipe			
	Estimated lead time once the order is			
	placed 4-6 weeks			
	Quote is good for 30 Days			

Total

\$86,500.00

Note to customer
LEDGE IS NOT INCLUDED

Accepted date

Accepted by

#### **Project Team:**

#### Karen Thomas Associates (Owner's Representative):

Karen Thomas Associates is a multidisciplinary firm specializing in project management and owner's representation. They have completed well over \$3.5B worth of residential projects in locations throughout the US, inclusive of extensive private site civil development supporting residential projects. Ms. Thomas, a licensed architect, has over 35 years of experience in architecture, engineering, and construction for complex projects, including extensive participation in land use management, planning, environmental stewardship and materials resource management, logistics planning, scheduling and cost containment and centralized team coordination and precision workflow processes.

Name	License Type	License Number	Expiration
Karen Thomas	Architect	NY: 022386	08/31/26
Dmitriy Polyakov	Architect	NY: 042790	04/30/28
Phil Reville	Architect	NY: 045384	03/31/26

#### **Sevee & Maher Engineers (Civil Engineers)**

Daniel P. Diffin, P.E., LEED AP - Site Design and Permitting – Mr. Diffin has more than 20 years of experience on a wide variety of civil engineering design and construction management projects for private and public sector clients. Mr. Diffin has been responsible for the engineering, design, and construction services for land development projects, commercial, industrial, and medical site developments, educational campuses, stormwater management and erosion control projects, and local, state, and federal permitting. Typical projects include: Bath Iron Works, Bath, Maine – Facility Build-out Plan; Woodland Pulp Mill – Tissue Machine Project at the Baileyville, Maine mill; Backyard Farms, Madison, Maine R&D Station and other facility upgrades and Long Creek Watershed, Westbrook, Maine stormwater retrofits in Catchment B21 of the Long Creek Watershed Management Plan.

Name	License Type	License Number	Expiration
Daniel P. Diffin	Professional Engineer	PE11841	12/31/25

#### **Axiom Engineering Group (Structural Engineer)**

Axiom is a multidisciplinary firm specializing in structural, mechanical, plumbing, and low voltage engineering. They work on residential and commercial projects across the US and have provided engineering services on large-scale residential and commercial projects. Travis Kukay, PE, leads the structural engineering group.

Mr. Kukay has a combined 20 years of providing consulting services in the Mechanical, Civil, and Structural fields. He has been Engineer of Record and responsible for the design, engineering and construction administration on a variety of retention/foundation design systems including micro piles, helical piers, soil nail walls, supported and cantilevered gravity/semi gravity walls in areas with a seismic design categories D and high snow load areas up to 200 psf. Projects include private

roadway systems, residential and commercial building structural foundations, deck assemblies as well as private bridges rated for HS lane loading per AASHTO specifications.

Name	License Type	License Number	Expiration
Paul DeWolfe	Professional Engineer	PE11052	12/31/2025

#### JPI Engineering (Electrical Engineer)

JPI is an electrical engineering firm with over 30 years of experience on a wide range of project types. They have worked with numerous utility companies on both residential and commercial development projects.

Name	License Type	License Number	Expiration
James Ingalls	Professional Engineer	PE19019	12/31/2025

#### JLF & Associates (Architect)

JLF has over forty years of experience designing large-scale residential projects. They have built a reputation for leading complex projects with multi-disciplinary design teams. Based in Bozeman, Montana, they work on projects across the US.

Name	License Type	License Number	Expiration				
Jeremy Scott	Architect	ARC5668	6/30/2025				

#### **Verdone Landscape Architects (Landscape Architects)**

Verdone Landscape Architects has over 30 years of experience on private, commercial, and municipal projects. Brannon Bleggi leads the landscape design team and is a licensed Landscape Architect in Maine.

Name	License Type	License Number	Expiration				
Brannon Bleggi	Landscape Architect	LAR5891	06/30/2025				

#### Flycatcher, LLC (Natural Resource Science Consultants)

Flycatcher LLC (Flycatcher) is a land use consulting company based in Yarmouth, Maine. They provide project consultation based on the best available science, the regulatory requirements, and the needs of our clients and projects. They support a wide range of clients and projects across multiple disciplines, including environmental studies; strategic permit execution at the federal, state and local levels; project siting and land acquisition; constraints analyses; GIS services; stakeholder engagement; natural resource mitigation and restoration; coastal restoration permitting and design; stakeholder identification and consultation; and compliance/construction inspection. Flycatcher has direct experience working for clients within The LUPC jurisdiction, assisting to collect natural resource data and permit projects on ski mountains, lakes, and even coastal islands.

Rodney is the Project Manager for Flycatcher, conducting and overseeing work performed on this Project. He is a Managing Partner and Senior Scientist with over 25 years' experience in the environmental consulting industry. He has several licenses and certifications, is currently the President of the Maine Association of Professional Soil Scientists (MAPSS) and was the former Chair of both the Planning Board and Comprehensive Planning Committee in the Town of Dedham, Maine. Additionally, in 2023 he was an adjunct professor at the University of Maine at Orono.

#### PROFESSIONAL CERTIFICATIONS

- Certified Wildlife Biologist #102308 (CWB), The Wildlife Society
- Certified Professional Soil Scientist #353740 (CPSS), Soil Science Society of America
- Professional Wetland Scientist #1518 (PWS), Society of Wetland Scientists
- Certified Professional in Erosion & Sediment Control #4625 (CPESC), EnviroCert International, Inc.
- Certified Erosion, Sediment and Stormwater Inspector #12451 (CESSWI), EnviroCert International, Inc.
- Licensed Soil Scientist #SS552 (CSS), State of Maine
- Licensed Site Evaluator #S371 (LSE), State of Maine
- Maine Certification in Erosion Control Practices (1432), State of Maine
- Maine Department of Environmental Protection Qualified Third-Party Inspector
- Former President (Maine Chapter) and Member, The Wildlife Society, Maine
- President and Member, Maine Association of Professional Soil Scientists

Name	License Type	License Number	Expiration				
Rodney Kelshaw	Soil Scientist	SS552	06/30/2025				

Required Form EXHIBIT 7

# NOTICE OF FILING OF APPLICATION WITH THE MAINE LAND USE PLANNING COMMISSION

LUPC Received 7/1/2025

Within seven days prior to filing an application with the Maine Land Use Planning Commission, the applicant must send by regular mail a completed copy of this notice to: all persons owning or leasing property within 1,000 feet of the proposed project; co-owners and co-lessors that are not co-applicants; the landowner(s) (if applicant is a lessee); plantation assessors or town select board (if applicable); county commissioners if any area proposed for development is within a township; and any persons who have made timely requests to be notified of this application or project.

This is to notify you that	Burn	nt Jacket Holding I, LLC
	(n-	ame and address of applicant)
has filed an application with the Main	e Land Use Plan	ning Commission, pursuant to provisions of 12 M.R.S.
Section 685-B and the Commission's r	ule Chapter 10,	Land Use Districts and Standards, to
		nd utility extension of +/- 12,651 feet along Burnt Jacket Road, affecting
(genero	al description of prop	osed activity, use, and acreage)
approximately 0.87 acres. Installatio	n of utility cable	es within conduits included as part of Permit RP-3313.
	ocated in	Town of Beaver Cove, Piscataguis County
		(name of town, township, or plantation, and county)
The application will be filed for public	inspection at th	ne Maine Land Use Planning Commission office circled
below (circle the appropriate office) o	n	July 1, 2025
	(spec	ify the date that this application will be filed with the LUPC).
AUGUSTA OFFICE		NORTHERN REGION

AUGUSTA C	FFICE	NORTHERN REGION								
		Serving most of Aroostook County and northern Penobscot								
18 Elkins Lane - Harlow Bldg.	Tel. (207) 287-2631	45 Radar Road	Tel. (207) 435-7970							
22 State House Station	TTY (888) 577-6690	Ashland, ME 04732-3600	Tel. (207) 435-7969							
Augusta, ME 04333-0022	FAX (207) 287-7439		FAX (207) 435-7184							
DOWNEAST	REGION	EASTER	N REGION							
Serving Hancock, Knox, Lincoln, ar	nd Sagadahoc Counties, and	Serving southern Penobscot Co	unty, southern Aroostook County,							
portions of Washington, Kennebec counties; and the coastal islands		and portions of Piscataquis County								
106 Hogan Rd, Suite 8	Tel. (207) 215-4685	191 Main Street	Tel. (207) 485-8354							
Bangor, ME 04401	Tel. (207) 592-4448  FAX (207) 941-4222	East Millinocket, ME 04430	Tel. (207) 399-2176							
MOOSEHEAD	\ /									
Serving Somerset County and m		WESTERN REGION Serving Franklin County and Oxford County								
, ,		1	•							
43 Lakeview Street	Tel. (207) 349-0941	932 US Route 2 East	Tel. (207) 670-7492 FR							
P.O. Box 1107 Greenville, ME 04441	Tel. (207) 731-4398	Wilton, ME 04294	Tel. (207) 670-7493 OX							
OTCOTTVINO, IVIL OTTT										

Written comments and requests for a public hearing should be sent to the Maine Land Use Planning Commission at the address circled above and **must be submitted in a timely manner**. The Commission prefers that all written comments and requests for a public hearing be submitted within 20 days of the date an application is accepted for processing. Requests for a public hearing must clearly state the reason(s) a public hearing is warranted on this project.

For questions about submitting written comments, requesting a public hearing, or for any additional information, contact Commission staff at the office circled above.

The Land Use Planning Commission's legal authority is established by 12 M.R.S. Section 683-A.

# LIST OF PROPERTY OWNERS WITHIN 1000 FT OF PROPOSED UTLITY LINE EXTENSION PROJECT ON BURNT JACKET HOLDING I, LLC PROPERTY - EXHIBIT 7 NOTICE MAILED TO EACH OWNER ON 6/27/2025\*

Tax Map-Lot	Owners' Names	Subdivision Lot#	Mailing Address	Book-Page
Beaver Cove				
010-004	Malloy, Edward M.	Subdivision Lot S1	8 Upton Way	2717/281
	Malloy, Maureen A.		Sewell NJ 08080	
010-005	Johnson, Kelley (trustee)	Subdivision Lot S2	2765 Crystal Way	2848/136
	Johnson, Scott (trustee)		Naples FL 34119	
010-016	Common Area (exempt)	Subdivision Lot C2	·	
010-018	Hughes, Raymond L II	Subdivision Lot S5	13 Talia Road	2351/13
	Hughes, Christine E.		Flemington NJ 08822	2638/151
010-018	Hughes, Raymond L II	Subdivision Lot S6	13 Talia Road	2351/21
	Hughes, Christine E.		Flemington NJ 08822	2638/151
010-021	Koopman White, Jane	Subdivision Lot S7	147 Daniels Road	2343/168
	White, Stephen Joseph II		Rowley MA 01969	3033/304
	(Trustees of White Family			
	Trust)			
010-022	Perkins, John A, Jr.	Subdivision Lot S8	795 Lily Bay Rd, #706	2701/145
	Perkins, Kathleen		Beaver Cove ME 04441	
210.000		0. 1. 1. 1. 1. 1	50.5	0507/51
010-023	Kenney, David	Subdivision Lot S9	59 Engel Lane	2587/54
240.004	Kenney, Lori	Cubalidate at 1 1 040	Freeport ME 04032	0.470./000
010-024	Brewster, David T., Trustee	Subdivision Lot S10	8 Prospect Street	2479/290
	Kew, Julia M., Trustee		Winchester MA 01890	
010-025	Shepard, David	Subdivision Lot S11	53 Brown Rd	2765/303
010-025	Shepard, Geraldine	Subdivision Lot 311	Hampton Falls NH	2/05/303
	Sheparu, Geratume		03844	
010-026	Hall, Nathan Darrel	Subdivision Lot S12	159 Jewett Road	TODD
010 020	Trace, Nathan Barret	Oubdivision Lot 012	Pittston, ME 04345	2886/163
010-029	Young, David F.	n/a	238 Far Reach Road	2508/181
010 023	Young, Deanna M	ii/u	Westwood MA 02090	2000/101
010-031	Beaver Cove Sewer & Water		c/o John Guerin,	
010 001	Association		President 795 Lily Bay	
			Rd Unit 211, Beaver	
			Cove, ME 04441	
			·	
* NOTE: The Exhibit	7 Notice of Filing of Application was	also mailed on 6/27/25 to	the Town of Beaver Cove	Select Board
at the following addr	ress: 795 Lily Bay Road, Unit #101, E	Beaver Cove, Maine 0441.		
_				
Greenville: FM 13 Lot 2-16	Wayne H. Plummer, Jr. and		3405 Lily Bay Rd,	2040/202
11-1 13 LUI Z-16	Barbara S. Plummer			2848/262
	barbara S. Plummer		Frenchtown Twp, ME 0441	
ΓM 13, Lot 2-15	Joy E. Harrington		PO Box 1183,	1277/278
11-1 13, LUI Z-13	Joy L. Hallington		Greenville ME 04441	12///2/0
ΓM 13, Lot 2-17	Richard Andrew Graves and		2340 Conewago Dr.	2970/178;
11.10, LUCZ-17	Jody Lynne Graves		Dover, PA 17315	2933/161;
	Jody Lynnic Oraves		50001,1717010	1340/230
ΓM 13, Lot 2-18	Moosehead Real Estate		PO Box 1181,	2712/204
10, LUIZ 10	Management Inc.		Greenville, ME 04441	
	. Tanagomone mo.		51001111110,111107741	
ΓM 13, Lot 7	Beaver Creek, Inc.		PO Box 1181,	2712/199;
TM 13, Lot 9	Scammon Ridge Headwaters		45 Exchange St,	2953/246
10, 2010	LLC		Portland ME 04101	2000,240
ΓM 12, Lot 7	Niall M. Ferguson and Elizabeth		15 Spring Rock Road	2835/278;
	J. Ferguson		Branford CT 06405	986/207
	7. 1 CI 6 USO II		Didiliola of 00400	500/207

# **EXHIBIT 8 - LAND DIVISION HISTORY:**

Please refer to BP-17544 and to Non-residential Permit RP-3313 issued on 6/25/2025. The Land Division History set forth therein has not changed.

LUPC Received 7/1/2025

For Use with **Exhibit 9**: Structures Table

Applicant/Project Name: Burnt Jacket Holding I, LLC

Refer to Structures, Features, Uses (Exhibit 9) for instructions. Name structures consistent with the labeling used on the Site Plans (Exhibit 10).

						ed alt							Number of:		Distance (in feet) of structure from nearest:						
Structure Type and Use (specify if temporary)	Year Built or Duration (if temporary)	Change in Use	New Construction	Expand or Add On	Reconstruct or Replace	Permanent foundation	Relocate or Remove	Enclose deck or porch	Change Dimensions or Setbacks	Other	Exterior Dimensions (LxWxH) in ft Indicate Current (C) & Proposed (P)	Type of Foundation	Bedrooms	Plumbing or water fixtures	Road	Property line	Lake or pond	River or stream	Wetland	Ocean/Coastal Wetland	
Existing Structures																					
Proposed Structures																					
			<b>▼</b>																		
			Ø																		

# For Use with Exhibit 9: Infrastructure Table

Refer to Structures, Features, Uses (Exhibit 9) for instructions. Name infrastructure consistent with the labeling used on the Site Plans (Exhibit 10).

Infrastructure Type and Use (specify if temporary)				sed alte				Dimensions (LxW) in ft	Year Built or Duration (if temporary)	Average Slope (%)	Max. Sustain. Slope (%)	Distance (in feet) of							
	Change in Use	New Construction	Change Dimensions	Reconstruct or Replace	Relocate	Change Setbacks	Other				,	Road	Property line	Lake or pond	River or stream	Wetland	Ocean/Coastal Wetland		
Existing Infrastructure																			
Proposed Infrastructure																			
CMP utility line extension		<b>⊿</b>						60'	2025	5	12	0	0	3,580	N/A	18	N/A		
Private utility line extension		V						12,651'x3'	2025	8.9	12	0	0	3,580	N/A	18	N/A		

# EXHIBIT 9 - STRUCTURES, FEATURES, AND USES:

LUPC Received 7/1/2025

The Burnt Jacket Holding I, LLC ownership has been used as commercial timberland. The property and the proposed project site is currently undeveloped.

The proposed utility line extension is 2.4 miles long, 3' wide, and will be approximately 4' below grade. It includes 17 buried electrical vaults. The project is located entirely on private property owned by the applicant. Construction is scheduled to be completed in 2025.

Please refer to the attached detailed site plan and infrastructure list for additional information.

# **EXHIBIT 10 - OVERALL SITE PLAN:**








EXHIBIT 12 - FIRE, POLICE, AND AMBULANCE PROTECTION:

The project will not require fire, police, or emergency services. Services required by residential and land management structures are covered under separate permits.

# EXHIBIT 13 - SOLID WASTE DISPOSAL:

No solid waste generation is anticipated for the project.

### **Electrical:**

Any electrical power required during construction will be provided through generators.

Construction of the utility line extension will include the installation of underground conduit which will house electrical and communication services to serve residential and land management uses on the applicant's property. The conduit will be located along or beneath the traveled surface of Burnt Jacket Road and then within the shoulder of the private road extending off of Burnt Jacket Road (see Non-residential Permit RP-3313 issued on 6/25/2025). Electrical vaults for access to the conduit will be located below ground within the shoulder of Burnt Jacket Road. See detailed site plan attached.

CMP maintains distribution poles and lines along Lily Bay Road, the nearest public road. The applicant has worked with electrical engineers and CMP on an electrical design to bring power into the Burnt Jacket Holding I, LLC property to serve residential and land management uses of the applicant's property. The CMP infrastructure will consist of two CMP poles and overhead wires installed adjacent to Burnt Jacket Road within the initial approximately 60 feet of the applicant's property westerly of Lily Bay Road.

# **Telephone Service:**

There will be no telephone service required for the construction of the utility line.

# EXHIBIT 15 - WATER SUPPLY:

No water service is required for the proposed power extension.

# EXHIBIT 16 - WASTEWATER DISPOSAL:

Wastewater disposal is not required for the proposed power extension.

## EXHIBIT 17 - VEHICLE ACCESS, CIRCULATION, AND PARKING:

Once complete, the utility line extension will only require occasional access for maintenance. Maintenance crews will park along the shoulder of Burnt Jacket Road or along the proposed route on the applicant's property (refer to Exhibit 10).

The construction period is anticipated to last two to four months. During construction, the site will be accessed by construction vehicles and delivery trucks daily, which will park on the shoulder and a portion of the existing road surface in order to accommodate all through-traffic along Burnt Jacket Road. Once constructed, the underground utility service will not interfere with vehicular access over Burnt Jacket Road. During construction, any delays to vehicular traffic over Burnt Jacket Road will be minimized.

The construction will not impede emergency vehicle access.

# **EXHIBIT 18 - EXTERIOR LIGHTING:**

LUPC Received 7/1/2025

The project does not require exterior lighting.

There will be no measurable noise impacts from the project after construction.

Construction of the project will be completed during normal working hours and noise impacts will be buffered by the distance to the nearest property line.

Blasting may be required for the construction of the utility trench. The contractor selected for any necessary blasting will prepare and submit a blasting plan for approval prior to the start of blasting.

### EXHIBIT 20 - HARMONIOUS FIT AND NATURAL CHARACTER:

Except for CMP's installation of poles and wires within the first approximately sixty feet on applicant's property near Lily Bay Road, the proposed utility line extension will be entirely underground and not visible. There will be no negative visual impacts from public roads, public properties, scenic byways, permanent trails, or Moosehead Lake located within three miles of the project area.

The surrounding area is mainly undeveloped woodland along the shore of Moosehead Lake within a combination of D-RS, P-WL1, P-WL3 and M-GN zones. The most recent aerial imagery for the property and surrounding woodlands shows that the property has been used as commercial timberland, which has been periodically harvested by prior landowners. Aerial imagery of the larger property shows it crossed by numerous woods roads and land management roads.

Moosehead Lake is at its closest, 921 feet from the project site. A summary of trails, scenic areas, parks, and conserved lands within five miles of the project location is set forth below:

- •Lily Bay State Park 2.4 miles
- •Sugar Island (Conserved Land) 2.5 miles
- •Prong Pond Trail 1 mile

LUPC Received 7/1/2025

EXHIBIT 21 - ARCHAEOLOGICAL AND HISTORIC RESOURCES:

Please see the attached exhibit for correspondence from the Maine Historic Preservation Commission (MHPC). The project area has no archaeologically sensitive areas, structures listed in the National Register of Historic Places, or significant archaeological sites or structures.



4 Blanchard Road, P.O. Box 85A Cumberland, ME 04021 Tel: 207.829.5016 • Fax: 207.829.5692 info@smemaine.com smemaine.com

March 10, 2025

VIA EMAIL

Kirk F. Mohney, Director Maine Historic Preservation Commission

Email: MHPCprojectreview@maine.gov

Subject:

**Utility Line** 

Burnt Jacket Holding I, LLC

Burnt Jacket Road, Beaver Cove, Maine

Dear Kirk:

Burnt Jacket Holding I, LLC is seeking approval for construction of an approximate 12,500 linear foot private underground utility line in Beaver Cove, Maine to serve residential and land management uses. We are requesting a review by the Maine Historic Preservation Commission to support the LUPC permit application.

#### PROJECT DESCRIPTION

The project area is a portion of Burnt Jacket Road, from the intersection with Lily Bay Road to the intersection with Evergreen Point Road. The project location is outlined in the attached Figure 1 - Site Location Map.

#### HISTORICAL FINDINGS

A search of the National Register of Historic Places online maps did not identify any historic places adjacent to the project area or subject parcel.

In addition to searching the National Register of Historic Places, records of neighboring properties were searched for any buildings over fifty (50) years old. No properties dated before 1975 were found.

Please feel free to contact me at 207.829.5016 or mrr@smemaine.com if you have any questions or need additional information.

Sincerely,

SEVEE & MAHER ENGINEERS, INC.

Michael M. Roy Senior Civil Engineer

Attachments: Figure 1 - Site Location Map

Based on the information submitted, I have concluded that there will be no historic properties affected by the proposed undertaking, as defined by Section 106 of the National Historic Preservation Act. Consequently, pursuant to 36 CFR 800.4(d)(1), no further Section 106 consultation is required unless additional resources are discovered during project implementation pursuant to 36 CFR 800.13.

State Historic Preservation/Officer Maine Historic Preservation Commission

# **EXHIBIT 22 - RARE OR SPECIAL PLANT COMMUNITIES:**

There are no critically imperiled (S1) or imperiled (S2) natural communities or plant species in the project vicinity. Please see the attached Exhibit 22A for the letter from the Maine Natural Areas Program (MNAP).

A project review request was submitted to the Maine Department of Inland Fisheries and Wildlife on March 10, 2025 - see request followed by the MDIFW response received on June 26, 2025 response on the following pages. Note that MDIFW found no concerns affected by this project.



4 Blanchard Road, P.O. Box 85A Cumberland, ME 04021 Tel: 207.829.5016 • Fax: 207.829.5692 info@smemaine.com smemaine.com

March 10, 2025

**VIA EMAIL** 

John Perry

Maine Department of Inland Fisheries and Wildlife

Email: ifwenvironmentalreview@maine.gov.

Subject: Utility Line

Burnt Jacket Holding I, LLC

Burnt Jacket Road, Beaver Cove, Maine

#### Dear John:

Burnt Jacket Holding I, LLC is seeking approval for construction of an approximate 12,500 linear foot private underground utility line in Burnt Jacket Road in Beaver Cove, Maine to serve residential and land management uses. The project location is outlined in the attached Figure 1 – Site Location Map.

We would appreciate receiving any information relative to rare, threatened, or endangered species or the presence of important wildlife or fisheries habitat at or in the immediate vicinity of the project.

Please feel free to contact me at 207.829.5016 or <a href="mrr@smemaine.com">mrr@smemaine.com</a> if you have any questions or need additional information.

Sincerely,

SEVEE & MAHER ENGINEERS, INC.

Michael R. Roy Senior Civil Engineer

Attachments: Figure 1-Site Location Map

MDIFW Environmental Review and Resource Map Request



# Maine Department of Inland Fisheries and Wildlife 353 Water Street, 41 SHS, Augusta, ME 04333 IFWEnvironmentalReview@maine.gov

# **MDIFW Environmental Review and Resource Map Request**

Th - 1/4-	
recomr sites, a	nine Department of Inland Fisheries and Wildlife provides environmental project reviews, mendations, and agency resource maps for landowners, preliminary reviews of potential project and formal agency regulatory reviews that include information on important fisheries, wildlife, and habitat resources. To facilitate your request, please provide the following information:
1.	This is a request for a:
8	New Project Follow-up for an existing project or prior information request.
2.	Project Location (provide ONE of the following options):  Street address (include town) – Preferred option:  Burnt Jacket Road, Beaver Cove, ME
	UTM East [ ] & UTM North [ ] coordinates (integers only).  Latitude [ ] & Longitude [ ] coordinates (decimal degrees, e.g., 45.03020)45.53099, -69.56425  Provide a GIS shapefile of the project footprint.  Provide a GoogleEarth KML/KMZ File of the project footprint.
	<u>Please also attach a project site map with location coordinates.</u> GoogleEarth is a popular tool to create project site maps. If you click over the location in GoogleEarth, it will reveal the latitude/longitude coordinate of that spot.
	If the project footprint is based on a parcel boundary, in addition to the street address, please provide the parcel map $[\ ]$ and lot $[\ ]$ numbers. 001-001-A
3.	Project Description:
	Please provide the name and as much detail as possible for your proposed project. If this a general request for information, please indicate so.
	Construction of an approximate 12,500 linear foot private underground utility line in Burnt Jacket Road in Beaver Cove, Maine.
4.	Permit Application Number:
••	If this request is related to a project currently or previously subject to regulatory review, please indicate your permit application number(s) and the agency(s) involved.  N/A

# **MDIFW Environmental Review and Resource Map Request**

# 5. <u>Contact Information:</u>

Last name: Roy

First name: Michael

Relationship to project: Consultant

Organization: Sevee & Maher Engineers, Inc

Street Address: 4 Blanchard Road

City: Cumberland

State: Maine

Zip Code: 04021

Phone Number: 207-829-5016

Email Address: mrr@smemaine.com

<u>Please provide all information requested. Omission of information may delay or prevent the ability to fulfill requests.</u> Please submit this request and any other supplemental information (e.g. site plans, if available) to <a href="mailto:IFWEnvironmentalReview@maine.gov">IFWEnvironmentalReview@maine.gov</a>. Thank you.



# STATE OF MAINE DEPARTMENT OF INLAND FISHERIES & WILDLIFE 353 WATER STREET 41 STATE HOUSE STATION AUGUSTA ME 04333-0041



June 26, 2025

Michael R. Roy Sevee & Maher Engineers 4 Blanchard road, P.O. Box 85A Cumberland, ME 04021

RE: Information Request - Burnt Jacket Road Utility Line Project, Beaver Cove (ID 8995-10412)

Dear Mike:

Per your request, we have reviewed current Maine Department of Inland Fisheries and Wildlife (MDIFW) information sources for known locations of Endangered, Threatened, and Special Concern (Rare) species; designated Essential and Significant Wildlife Habitats; inland fisheries and aquatic habitats; and other protected natural resource concerns within the vicinity of the *Burnt Jacket Road Utility Line Project* in Beaver Cove, pursuant to MDIFW's authority.

Our Department has not mapped any Essential or Significant Wildlife Habitats that would be affected by this project.

# ENDANGERED, THREATENED, AND SPECIAL CONCERN SPECIES

# **Bat Species**

Of the eight species of bats that occur in Maine, four species are afforded protection under Maines Endangered Species Act (MESA, 12 M.R.S 12801 et. seq.): little brown bat (State Endangered), northern long-eared bat (State Endangered), eastern small-footed bat (State Threatened), and tri-colored bat (State Threatened). The four remaining bat species are designated as Species of Special Concern: big brown bat, red bat, hoary bat, and silver-haired bat. While a comprehensive statewide inventory for bats has not been completed, based on historical evidence it is likely that several of these species occur within the project area during spring/fall migration, the summer breeding season, and/or for overwintering. However, our Agency does not anticipate significant impacts to any of the bat species as a result of this project.

# **Fisheries Habitat**

Stream crossings should be avoided, but if a stream crossing is necessary the line should be installed so as to not impede fish passage. Small streams, including intermittent streams, can provide crucial rearing habitat, cold water for thermal refugia, and abundant food for juvenile salmonids on a seasonal basis and undersized crossings may inhibit these functions. Construction Best Management Practices should be closely followed to avoid erosion, sedimentation, alteration of stream flow, and other impacts as eroding soils from construction activities can travel significant distances as well as transport other pollutants resulting in direct impacts to

June 26, 2025

Letter to Michael R. Roy, Sevee & Maher Engineers Comments RE: Burnt Jacket Road Utility Line Project, Beaver Cove

fisheries and aquatic habitat. In addition, we recommend that any necessary instream work occur between July 15 and October 1.

This consultation review has been conducted specifically for known MDIFW jurisdictional features and should not be interpreted as a comprehensive review for the presence of other regulated features that may occur in this area. Prior to the start of any future site disturbance, we recommend additional consultation with the municipality, and other state resource and regulatory agencies including the Maine Natural Areas Program and the Maine Department of Environmental Protection in order to avoid unintended protected resource disturbance.

Please feel free to contact my office if you have any questions regarding this information, or if I can be of any further assistance.

Best regards,

John Perry


Environmental Review Program Supervisor



# Maine Department of Inland Fisheries and Wildlife 7/1/2025Project Area Review of Fish and Wildlife Observations and Priority Habitats

# **Burnt Jacket Road, Utility Line, Beaver Cove**

Project ID 8995, Version ID 10412



Legend only lists resources visible in the map; see response letter for all resources that were evaluated.

County Boundary
Inland Waterfowl/Wading Bird
LUPC - Fish & Wildlife Zone
Project Footprint
Wild Lake Trout Habitats
Search Area
Approx\_ Project Area

Date: 3/19/2025 UTM Zone 19N, NAD83



# **EXHIBIT 22A - RARE OR SPECIAL PLANT COMMUNITIES:**

# STATE OF MAINE

LUPC Received 7/1/2025

# DEPARTMENT OF AGRICULTURE, CONSERVATION & FORESTRY

177 STATE HOUSE STATION AUGUSTA, MAINE 04333

JANET T. MILLS GOVERNOR AMANDA E. BEAL COMMISSIONER

March 11, 2025

Michael Roy Sevee & Maher Engineers PO Box 85A Cumberland, ME 04021

Via email: mrr@smemaine.com

Re: Rare and exemplary botanical features in proximity to: #231136, Underground Utility Line, Burnt Jacket Road, Beaver Cove, Maine

Dear Michael Roy:

I have searched the Maine Natural Areas Program's Biological and Conservation Data System files in response to your request received March 10, 2025 for information on the presence of rare or unique botanical features documented from the vicinity of the project in Beaver Cove, Maine. Rare and unique botanical features include the habitat of rare, threatened, or endangered plant species and unique or exemplary natural communities. Our review involves examining maps, manual and computerized records, other sources of information such as scientific articles or published references, and the personal knowledge of staff or cooperating experts.

Our official response covers only botanical features. For authoritative information and official response for zoological features you must make a similar request to the Maine Department of Inland Fisheries and Wildlife, 284 State Street, Augusta, Maine 04333.

According to the information currently in our Biological and Conservation Data System files, there are no rare botanical features documented specifically within the project area. Based on the information in our files and the landscape context of this project, there is a low probability that rare or significant botanical features occur at this project location.

This finding is available and appropriate for preparation and review of environmental assessments, but it is not a substitute for on-site surveys. Comprehensive field surveys do not exist for all natural areas in Maine, and in the absence of a specific field investigation, the Maine Natural Areas Program cannot provide a definitive statement on the presence or absence of unusual natural features at this site.

The Maine Natural Areas Program (MNAP) is continuously working to achieve a more comprehensive database of exemplary natural features in Maine. We would appreciate the contribution of any information obtained should you decide to do field work. MNAP welcomes coordination with individuals or organizations proposing environmental alteration or conducting environmental assessments. If, however, data provided by MNAP are to be published in any form, the Program should be informed at the outset and credited as the source.

MOLLY DOCHERTY, DIRECTOR
MAINE NATURAL AREAS PROGRAM
90 BLOSSOM LANE, DEERING BUILDING



PHONE: (207) 287-8044 WWW.MAINE.GOV/DACF/MNAP

# EXHIBIT 22A - RARE OR SPECIAL PLANT COMMUNITIES - CONTINUED:

Letter to SME Comments RE: Utility Line, Beaver Cove March 11, 2025 Page 2 of 2 LUPC Received 7/1/2025

The Maine Natural Areas Program has instituted a fee structure of \$75.00 an hour to recover the actual cost of processing your request for information. You will receive an invoice for \$150.00 for two hours of our services.

Thank you for using MNAP in the environmental review process. Please do not hesitate to contact me if you have further questions about the Natural Areas Program or about rare or unique botanical features on this site.

Sincerely,

Lisa St. Hilaire

Lisa St. Hilaire | Information Manager | Maine Natural Areas Program 207-287-8044 | <u>lisa.st.hilaire@maine.gov</u>

# SOIL SUITABILITY SUPPLEMENT: PROPOSED UNDERGROUND UTILITY PROJECT

Burnt Jacket Mountain and Moosehead Lake Beaver Cove, Maine





Prepared by: Flycatcher LLC 106 Lafayette Street, Suite 2A Yarmouth, ME 04096 http://www.flycatcherllc.com

June 2025

# Soil Suitability Supplement Proposed Underground Utility Project

# **Contents**

Арр	endix A	Figures	4
Apı	pendic	ces	
5.0	Find	ings	2
		Wetland Delineation	
4.0	Met	hods	2
3.0	LUPO	C Non-Residential Development Standards – Soil	1
2.0	Surv	ey Area	1
1.0	Intro	oduction	1



# 1.0 Introduction

It is our understanding that JLF Architecture (JLF) is submitting an "Application for Nonresidential Development" to the Land Use Planning Commission (LUPC) for a proposed development off Burnt Jacket Road, in Beaver Cove Township (Project). Part of the Project includes the installation of an electric transmission utility line beginning at Lily Bay Road and extending along Burnt Jacket Road, approximately 2.5-miles to the Evergreen Point Road intersection, where it will then extend westerly along a new driveway to the proposed buildings. The first section of line will be overhead from the existing poles on the east side of Lily Bay Road to a pole set along the edge of Burnt Jacket Road; from there it will go underground and be buried in the edge of the Burnt Jacket Road until it reaches the buildings. In two places there will be permanent above-ground splice box structures located outside the existing roadway edge of fill.

As requested by JLF, in February 2025 Flycatcher LLC (Flycatcher) conducted a natural resources field review along 2.5-miles of Burnt Jacket Road (Survey Area). The purpose of this reconnaissance level survey was to identify the general locations of protected natural resources so as to inform the potential development of the underground utility, and for siting the above-ground splice boxes. The survey was completed during this timeframe to help the client continue site planning and design during the winter months. The results of this survey provided information for planning purposes and was not suitable for final engineering or permitting purposes in all areas. On May 2, 2025 a Flycatcher biologist returned to the Survey Area to perform a wetland delineation and vernal pool survey in the sections of the Survey Area in potential locations where the utility may transfer from above to below ground near the intersection of Burnt Jacket Road with Lily Bay Road and for above ground splice boxes.

# 2.0 Survey Area

As depicted on Figure 1, the approximately 18-acre Survey Area consists of a 40-foot swath, 20 feet on either side, of a 2.5 mile section of Burnt Jacket Road. The Survey Area extends westerly along Burnt Jacket Road from the intersection with Lily Bay Road to a previously delineated area at the intersection with Evergreen Point Road. Burnt Jacket Road is maintained to allow vehicle travel to Burnt Jacket Mountain and to the few existing houses and camps along Moosehead Lake.

# 3.0 LUPC Non-Residential Development Standards – Soil

The LUPC standards must be met for subdivisions and commercial, industrial and other nonresidential development. Soil types must be determined by a site-specific soil survey, according to the "Guidelines for Maine Certified Soil Scientists for Soil Identification and Mapping", Maine Association of Professional Soil Scientists, 2009. The soil survey class that best matches the proposed Project is the Class L for linear projects, which is for project components that involve soil disturbance, such as road construction, fairway construction or trail construction and that have little or no adjacent development.

Determination of soil suitability is based on the NRCS soils potential ratings for low density development. Soils with a low or very low development potential rating will not be developed unless the Commission determines that adequate corrective measures will be used to overcome those limitations that resulted in the low or very low rating. Additionally, hydric soil map units and map units with a low or very low development potential rating for low density development must be clearly identified on the soil survey map as being hydric soils or as having a low or very low development potential rating.

A soil survey meeting the standards described in Section 3 was not performed for the underground utility area in/along Burnt Jacket Road. However, the standards do allow for exceptions to be considered for



various circumstances. This situation appears to qualify for an exception based on best professional judgment but the final determination is made by the LUPC.

# 4.0 Methods

The May 2025 wetland delineation was performed by an individual that is a Professional Wetland Scientist (PWS), State of Maine Licensed Soil Scientist (LSS) and a State of Maine Licensed Site Evaluator (LSE). The LSS has performed wetland delineation, soil survey/mapping and preliminary site evaluation services in other areas to support planning of other portions of the Project, such as for driveways and buildings. Therefore, he has firsthand knowledge of the general soil types in the Project area.

# 4.1.1 Wetland Delineation

Wetland delineations were conducted in accordance with the USACE Wetland Delineation Manual<sup>1</sup> and the Northcentral and Northeast Regional Supplement (Version 2.0).<sup>2</sup> The manual and supplement provide a repeatable methodology to identify and map wetland areas and are the accepted wetland delineation methodology of the LUPC and the USACE. Hydric soil determinations were based on *Field Indicators for Identifying Hydric Soils in New England, Version 4,*<sup>3</sup> *Field Indicators of Hydric Soils in the United States, Version 8.2,*<sup>4</sup> and the Maine Association of Professional Soil Scientist (MAPSS) Key for the Identification of Soil Drainage Class<sup>5</sup>.

Sections of the Survey Area where the utility line will be outside the road fill and above ground were investigated by the LSS. When a location appeared to have the requisite three factors that constitute a wetland (i.e., hydrophytic vegetation, indicators of hydrology, and the presence of hydric soils) the scientist analyzed the site-specific data to determine if the area met the criteria to be considered a wetland. Wetland boundaries were marked with pink survey flagging labelled with the word "Wetland Delineation" and numbered in sequential order. Wetlands flags were geolocated using a mapping grade global positioning system (GPS) unit (Juniper Systems' Geode GPS Antenna and ESRI's ArcGIS Field Maps software). The data were collected using real-time correction and standards specified by the manufacturer to achieve sub-meter accuracy.

# 5.0 Findings

The two locations of proposed above-ground splice boxes were investigated in May 2025 by an LSS and no wetlands or hydric soils were identified within these proposed areas (Figure 2 Map 1 and 2 Map 2). The goal at the time the fieldwork was performed did not include documenting soil data for a soil survey. However, the soil scientist did auger borings in these locations to view the soil properties.

The NRCS map (Figure 3) depicts the Survey Area as:

- MSC: Masardis gravelly fine sandy loam, strongly sloping
- BP: Brayton-Peacham association, 0-8% slopes, extremely stony

<sup>&</sup>lt;sup>5</sup> Maine Association of Professional Soil Scientists. 2013. Key for the Identification of Soil Drainage Class. Revised.



<sup>&</sup>lt;sup>1</sup> Environmental Laboratory. 1987. "Corps of Engineers Wetlands Delineation Manual," Technical Report Y-87-1, U.S. Army Engineer Waterways Experiment Station, Vicksburg, Miss.

<sup>&</sup>lt;sup>2</sup> U.S. Army Corps of Engineers. 2012. Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast Region (Version 2.0), ed. J. S. Wakeley, R. W. Lichvar, C. V. Noble, and J. F. Berkowitz. ERDC/EL TR-12-1. Vicksburg, MS: U.S. Army Engineer Research and Development Center.

<sup>&</sup>lt;sup>3</sup> New England Hydric Soils Technical Committee. 2018 Version 4, Field Indicators for Identifying Hydric Soils in New England. New England Interstate Water Pollution Control Commission, Lowell, MA.

<sup>&</sup>lt;sup>4</sup> United States Department of Agriculture, Natural resources Conservation Service. 2018. Field Indicators of Hydric Soils in the United States, Version 8.2. L.M. Vasilas, G.W. Hurt, and J.F. Berkowitz (eds.). USDA, NRCS, in cooperation with the National Technical Committee for Hydric Soils.

Soil Suitability Supplement Proposed Underground Utility Project

- CPB: Colonel-Brayton-Peru association, 0-8% slopes, very stony
- TLC: Telos-Chesuncook-Elliottsville association, 3-15% slopes, very stony
- THC: Telos-Chesuncook association, 3-15% slopes, very stony

Since the proposed use is a shallow excavation to install a splice box, we reviewed the NRCS "Shallow Excavations" soil rating to evaluate this Project. In both proposed splice box locations the rating is "Very Limited" (Figure 4). Very limited indicates that "the soil has one or more features that are unfavorable for the specified use. The limitations generally cannot be overcome without major soil reclamation, special design, or expensive installation procedures. Poor performance and high maintenance can be expected".

The splice box near Lily Bay Road where the utility will transition to underground is on the south side of Burnt Jacket Road, in an old road with a gravel and sand base. In this area the water table was moderately well drained (or better). The NRCS mapped this area as MSC; the Masardis series consists of very deep, somewhat excessively drained soils formed in glaciofluvial deposits on outwash plains, terraces, deltas, kames, and eskers. This mapping appears to be generally accurate as evidenced by the on-site auger borings performed during the wetland delineation and that wetland W-RDK-500 appears to be an old aggregate borrow area. The very limited shallow excavation rating in this location is due to unstable excavation walls. This limitation can be overcome by installing a trench box to hold up pit sidewalls during excavation.

The second splice box location is in a forested upland on the northeast side of Burnt Jacket Road. Auger borings in this location found stony sandy loam soil with a water table that was somewhat poorly to moderately well drained. The NRCS mapped this area as CPB; the Colonel series consists of somewhat poorly drained soils that formed in loamy lodgment till on hills and mountains in glaciated uplands. They are shallow to a dense substratum and very deep to bedrock. This mapping appears to be generally accurate as evidenced by the on-site auger borings performed during the wetland delineation. The very limited shallow excavation rating in this location is due to depth to saturated zone and organic matter content. The excavation can be conducted during a season with a low groundwater table (such as July or August) and groundwater infiltrating the excavation during construction can be pumped to an upland away from the Project. After the box is installed the organic matter content and groundwater table should not affect this Project because the utility line splice will be encased in a subsurface, waterproof box and will not be in contact with the surrounding soil. If unstable excavation walls end up being a concern at this site it can be overcome by installing a trench box to hold up pit sidewalls during excavation.

As stated above, this is not a soil survey report and on-site soil mapping was not performed for the underground utility project. However, the wetland delineation/hydric soil mapping in the area proximal to the two splice box locations documents that these will not be located in wetlands. Additionally, an LSS with general experience with the proximal soil and landscape features observed the splice box areas and their soil properties and has identified suitable corrective measures. As proper planning and the implementation of typical engineering protocols in these locations should make these sites suitable for the proposed splice boxes, we believe that this Project should qualified for an exception to the soil survey requirement.

Thank you for contacting Flycatcher and providing the opportunity to continue to support this Project. If you have questions, please do not hesitate to contact me.

Rodney Kelshaw, LSS/CPSS/CPESC/CESSWI/LSE/CWB/PWS rodney@flycatcherllc.com (207) 944-6776




Rody D. Kel


 $\begin{array}{c} LUPC \; Received \\ 7/1/2025 \\ \text{Soil Suitability Supplement} \\ \text{Proposed Underground Utility Project} \end{array}$ 

# **Appendix A Figures**

Figure 1. USGS Survey Area Location Map
Figure 2. Natural Resource Maps
Figure 3. NRCS Soil Map
Figure 4. NRCS. Shallow Excavtions Rating Map









inate System; NAD 1983 StatePlane Maine East FIPS 1801 Fee

# LUPC Received 7/1/2025





## MAP LEGEND

### Area of Interest (AOI)

Area of Interest (AOI)

### Soils

Soil Map Unit Polygons



Soil Map Unit Lines



Soil Map Unit Points

### Special Point Features

Blowout (0)



Borrow Pit



Clay Spot



Closed Depression



Gravel Pit



**Gravelly Spot** 



Landfill



Lava Flow Marsh or swamp





Mine or Quarry Miscellaneous Water



Perennial Water



Rock Outcrop



Saline Spot



Sandy Spot



Severely Eroded Spot





Sinkhole Slide or Slip



Sodic Spot



Spoil Area Stony Spot



Very Stony Spot



Wet Spot Other



Special Line Features

### Water Features



Streams and Canals

### Transportation



Rails



Interstate Highways



**US Routes** 



Major Roads



Local Roads

# Background



Aerial Photography

# MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24.000.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Piscataquis County, Maine, Southern Part Survey Area Data: Version 27, Aug 26, 2024


Soil map units are labeled (as space allows) for map scales 1:50.000 or larger.

Date(s) aerial images were photographed: Jul 23, 2021—Oct 29, 2021

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

# **Map Unit Legend**

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
BP	Brayton-Peacham association, 0 to 8 percent slopes, extremely stony	84.2	15.7%
CFD	Chesuncook-Elliottsville-Telos association, 15 to 35 percent slopes, very stony	46.3	8.7%
СРВ	Colonel-Brayton-Peru association, 0 to 8 percent slopes, very stony	88.5	16.5%
CQB	Colonel-Brayton-Lyman complex, undulating, very stony	9.3	1.7%
DBC	Danforth channery silt loam, 3 to 15 percent slopes, extremely stony	0.3	0.0%
DBD	Danforth channery silt loam, 15 to 25 percent slopes, extremely stony	0.3	0.0%
DYC	Peru-Colonel-Lyman association, 3 to 15 percent slopes, very stony	0.2	0.0%
MSC	Masardis gravelly fine sandy loam, strongly sloping	20.5	3.8%
MYD	Monson-Elliottsville-Knob Lock complex, 8 to 30 percent slopes, very rocky	145.4	27.2%
ROD	Ricker-Rock outcrop complex, moderately steep	29.3	5.5%
THC	Telos-Chesuncook association, 3 to 15 percent slopes, very stony	49.2	9.2%
TLC	Telos-Chesuncook-Elliottsville association, 3 to 15 percent slopes, very stony	21.4	4.0%
ТМВ	Monarda-Telos complex, 0 to 8 percent slopes, very stony	40.4	7.5%
Totals for Area of Interest		535.3	100.0%



# MAP LEGEND

# Area of Interest (AOI) Area of Interest (AOI) Background Aerial Photography Soils Soil Rating Polygons Very limited Somewhat limited Not limited

### Soil Rating Lines

Very limited

Somewhat limited

Not limited

Not rated or not available

Not rated or not available

### Soil Rating Points

Very limited

Somewhat limited

Not limited

Not rated or not available

### **Water Features**

Streams and Canals

## Transportation

Rails

Interstate Highways

US Routes

Major Roads

Local Roads

# MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24.000.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Piscataquis County, Maine, Southern Part Survey Area Data: Version 27, Aug 26, 2024

Soil map units are labeled (as space allows) for map scales 1:50.000 or larger.

Date(s) aerial images were photographed: Jul 23, 2021—Oct 29, 2021

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

# **Shallow Excavations**

Map unit symbol	Map unit name	Rating	Component name (percent)	Rating reasons (numeric values)	Acres in AOI	Percent of AOI							
ВР	Brayton- Peacham association, 0	Very limited	Brayton, extremely stony (53%)	Depth to saturated zone (1.00)	83.7	16.5%							
	to 8 percent slopes, extremely stony			Unstable excavation walls (0.01)									
			Peacham,	Ponding (1.00)									
			extremely stony (26%)	Depth to saturated zone (1.00)									
				Organic matter content (1.00)									
				Unstable excavation walls (0.01)									
					Wonsqueak	Ponding (1.00)	1						
			(11%)	Depth to saturated zone (1.00)									
				Unstable excavation walls (0.01)									
			Colonel, extremely stony (8%)	Depth to saturated zone (1.00)									
				Organic matter content (1.00)									
											Unstable excavation walls (0.01)		
				Depth to saturated zone (1.00)									
				Depth to hard bedrock (1.00)									
				Unstable excavation walls (0.01)									
			Peru, extremely stony (1%)	Depth to saturated zone (1.00)									
				Unstable excavation walls (0.01)									

Map unit symbol	Map unit name	Rating	Component name (percent)	Rating reasons (numeric values)	Acres in AOI	Percent of AOI								
CFD			Very limited	Chesuncook	Slope (1.00)	53.2	10.5%							
	Elliottsville- Telos association, 15 to 35		(40%)	Depth to saturated zone (1.00)										
	percent slopes, very stony			Dense layer (0.50)										
	Storry			Unstable excavation walls (0.01)										
			Elliottsville (30%)	Slope (1.00)										
				Depth to hard bedrock (1.00)										
				Unstable excavation walls (0.01)										
			Telos (15%)	Slope (1.00)										
				Depth to saturated zone (1.00)										
				Organic matter content (1.00)										
				Unstable excavation walls (0.01)										
				Depth to hard bedrock (1.00)										
				Slope (1.00)										
				Organic matter content (1.00)										
												Unstable excavation walls (0.01)		
	SLOPES	Chesuncook, SLOPES <15% (4%)	Depth to saturated zone (1.00)											
				Dense layer (0.50)										
				Slope (0.16)										
				Unstable excavation walls (0.01)										
		 	Telos, SLOPES <15% (1%)	Depth to saturated zone (1.00)										
				Organic matter content (1.00)										

Map unit symbol	Map unit name	Rating	Component name (percent)	Rating reasons (numeric values)	Acres in AOI	Percent of AOI						
				Unstable excavation walls (0.01)								
CPB	Peru stony (40%) sat (1.0 (4.0 (4.0 (4.0 (4.0 (4.0 (4.0 (4.0 (4	Depth to saturated zone (1.00)	84.0	16.5%								
	to 8 percent slopes, very stony			Organic matter content (1.00)								
				Unstable excavation walls (0.01)								
			Brayton, very stony (24%)	Depth to saturated zone (1.00)								
			Unstable excavation walls (0.01)									
								(18%)		Depth to saturated zone (1.00)		
									Unstable excavation walls (0.01)			
			stony (8%)	Ponding (1.00)								
				Depth to saturated zone (1.00)								
				Organic matter content (1.00)								
						Unstable excavation walls (0.01)						
			Skerry, very stony (6%)	Depth to saturated zone (1.00)								
				Dense layer (0.50)								
				Unstable excavation walls (0.09)								
			Lyman, very stony (2%)	Depth to hard bedrock (1.00)								
			Unstable excavation walls (0.01)									
			Tunbridge, very stony (2%)	Depth to hard bedrock (1.00)								

Map unit symbol	Map unit name	Rating	Component name (percent)	Rating reasons (numeric values)	Acres in AOI	Percent of AOI					
				Unstable excavation walls (0.01)							
CQB	Colonel-Brayton- Lyman complex,	Very limited	Colonel, very stony (40%)	Depth to saturated zone (1.00)	4.9	1.0%					
	undulating, very stony			Organic matter content (1.00)							
				Unstable excavation walls (0.01)							
			Brayton (30%)	Depth to saturated zone (1.00)							
			Unstable excavation walls (0.01)								
				Lyman, very stony (15%)	Depth to hard bedrock (1.00)						
									Unstable excavation walls (0.01)		
						Peru (5%)	Depth to saturated zone (1.00)				
				Dense layer (0.50)							
				Unstable excavation walls (0.01)							
			Peacham (4%)	Ponding (1.00)							
				Depth to saturated zone (1.00)							
				Organic matter content (1.00)							
				Large stones (1.00)							
				Dense layer (0.50)							
			Abram (3%)	Abram (3%)	Depth to hard bedrock (1.00)						
				Organic matter content (1.00)							
				Unstable excavation walls (0.01)							

Map unit symbol	Map unit name	Rating	Component name (percent)	Rating reasons (numeric values)	Acres in AOI	Percent of AOI
			Tunbridge (3%)	Depth to hard bedrock (1.00)		
				Unstable excavation walls (0.01)		
DBC	Danforth channery silt loam, 3 to 15	Somewhat limited	Danforth (85%)	Unstable excavation walls (0.02)	0.2	0.0%
	percent slopes, extremely stony		Berkshire (5%)	Unstable excavation walls (0.01)		
DBD	Danforth	Very limited	Danforth (85%)	Slope (1.00)	0.0	0.0%
	channery silt loam, 15 to 25 percent slopes,			Unstable excavation walls (0.02)		
	extremely		Berkshire (5%)	Slope (1.00)		
	Storiy	stony	Unstable excavation walls (0.01)			
		Tunbridge (5%)	Depth to hard bedrock (1.00)			
				Slope (0.63)		
				Unstable excavation walls (0.01)		
			Peru (3%)	Depth to saturated zone (1.00)		
				Slope (0.16)		
				Unstable excavation walls (0.01)		
			Colonel (2%)	Depth to saturated zone (1.00)		
				Organic matter content (1.00)		
				Unstable excavation walls (0.01)		
DXC	Peru-Colonel association, 3 to 15 percent	Very limited	Peru, very stony (55%)	Depth to saturated zone (1.00)	0.0	0.0%
	slopes, very stony	slopes, very		Slope (0.04) Unstable		
				excavation walls (0.01)		

Map unit symbol	Map unit name	Rating	Component name (percent)	Rating reasons (numeric values)	Acres in AOI	Percent of AOI
			Colonel, very stony (27%)	Depth to saturated zone (1.00)		
				Organic matter content (1.00)		
				Slope (0.04)		
				Unstable excavation walls (0.01)		
			Brayton, very stony (6%)	Depth to saturated zone (1.00)		
				Slope (0.04)		
				Unstable excavation walls (0.01)		
			Tunbridge, very stony (4%)	Depth to hard bedrock (1.00)		
				Slope (0.04)		
				Unstable excavation walls (0.01)		
			Lyman, very stony (2%)	Depth to hard bedrock (1.00)		
				Slope (0.04)		
				Unstable excavation walls (0.01)		
MSC	Masardis gravelly fine sandy loam,	Very limited	Masardis (85%)	Unstable excavation walls (1.00)	23.7	4.7%
	strongly sloping			Slope (0.16)		
			Brayton (3%)	Depth to saturated zone (1.00)		
				Dense layer (0.50)		
				Unstable excavation walls (0.01)		
			Wonsqueak (3%)	Depth to saturated zone (1.00)		
				Flooding (0.60)		
				Unstable excavation walls (0.01)		

Map unit symbol	Map unit name	Rating	Component name (percent)	Rating reasons (numeric values)	Acres in AOI	Percent of AOI
MYD	Elliottsville-	Very limited	Monson (35%)	Depth to hard bedrock (1.00)	104.0	20.5%
	Knob Lock complex, 8 to 30 percent			Organic matter content (1.00)		
	slopes, very			Slope (1.00)		
	rocky			Unstable excavation walls (0.01)		
			Elliottsville (30%)	Depth to hard bedrock (1.00)		
				Slope (1.00)		
				Unstable excavation walls (0.01)		
			Knob Lock (20%)	Depth to hard bedrock (1.00)		
				Organic matter content (1.00)		
				Slope (1.00)		
				Unstable excavation walls (0.01)		
				Depth to hard bedrock (1.00)		
				Slope (1.00)		
		Chesuncook (4%)	Unstable excavation walls (0.01)			
			Depth to saturated zone (1.00)			
				Slope (0.63)	-	
			Dense layer (0.50)			
				Unstable excavation walls (0.01)		
			Telos (1%)	Depth to saturated zone (1.00)		
				Organic matter content (1.00)		
				Unstable excavation walls (0.01)		
ROD	Ricker-Rock outcrop	Very limited	Ricker (50%)	Depth to hard bedrock (1.00)	29.3	5.8%

Map unit symbol	Map unit name	Rating	Component name (percent)	Rating reasons (numeric values)	Acres in AOI	Percent of AOI
	complex, moderately			Slope (1.00)		
	steep			Organic matter content (1.00)		
				Unstable excavation walls (0.01)		
			Monson (10%)	Depth to hard bedrock (1.00)		
				Organic matter content (1.00)		
				Slope (1.00)		
				Unstable excavation walls (0.01)		
			Abram (10%)	Depth to hard bedrock (1.00)		
				Organic matter content (1.00)		
				Slope (1.00)		
				Unstable excavation walls (0.01)		
			Monarda (3%)	Depth to saturated zone (1.00)		
				Dense layer (0.50)		
				Unstable excavation walls (0.01)		
			Elliottsville (2%)	Depth to hard bedrock (1.00)		
				Slope (1.00)		
				Unstable excavation walls (0.01)		
THC	Telos- Chesuncook association, 3 to 15 percent slopes, very stony	Very limited	Telos (50%)	Depth to saturated zone (1.00)	60.3	11.9%
		slopes, very		Organic matter content (1.00)		
				Unstable excavation walls (0.01)		
			Chesuncook (35%)	Depth to saturated zone (1.00)		

Map unit symbol	Map unit name	Rating	Component name (percent)	Rating reasons (numeric values)	Acres in AOI	Percent of AOI
				Dense layer (0.50)		
				Unstable excavation walls (0.01)		
			Monarda (6%)	Depth to saturated zone (1.00)		
				Dense layer (0.50)		
				Unstable excavation walls (0.01)		
			Ragmuff (4%)	Depth to saturated zone (1.00)		
				Depth to hard bedrock (1.00)		
				Unstable excavation walls (0.01)		
			Elliottsville (4%)	Depth to hard bedrock (1.00)		
				Slope (0.16)		
				Unstable excavation walls (0.01)		
			Monson (1%)	Depth to hard bedrock (1.00)		
				Organic matter content (1.00)		
				Slope (0.63)		
				Unstable excavation walls (0.01)		
TLC	Telos- Chesuncook- Elliottsville	hesuncook- Iliottsville ssociation, 3 o 15 percent lopes, very	Telos (40%)	Depth to saturated zone (1.00)	24.8	4.9%
	association, 3 to 15 percent			Organic matter content (1.00)		
	stony			Unstable excavation walls (0.01)		
			Chesuncook (25%)	Depth to saturated zone (1.00)		
				Dense layer (0.50)		

Map unit symbol	Map unit name	Rating	Component name (percent)	Rating reasons (numeric values)	Acres in AOI	Percent of AOI
				Unstable excavation walls (0.01)		
			Elliottsville (20%)	Depth to hard bedrock (1.00)		
				Slope (0.16)		
				Unstable excavation walls (0.01)		
			Ragmuff (9%)	Depth to saturated zone (1.00)		
				Depth to hard bedrock (1.00)		
				Unstable excavation walls (0.01)		
			Monson (3%)	Depth to hard bedrock (1.00)		
				Organic matter content (1.00)		
				Slope (0.63)		
				Unstable excavation walls (0.01)		
			Monarda (3%)	Depth to saturated zone (1.00)		
				Dense layer (0.50)		
				Unstable excavation walls (0.01)		
МВ	Monarda-Telos complex, 0 to 8 percent slopes, very stony	Very limited Monarda (45%)  Telos (40%)	Monarda (45%)	Depth to saturated zone (1.00)	39.7	7.8%
				Dense layer (0.50)		
				Unstable excavation walls (0.01)		
			Telos (40%)	Depth to saturated zone (1.00)		
			Organic matter content (1.00)			

Map unit symbol	Map unit name	Rating	Component name (percent)	Rating reasons (numeric values)	Acres in AOI	Percent of AO
				Unstable excavation walls (0.01)		
			Burnham (7%)	Ponding (1.00)		
				Depth to saturated zone (1.00)		
				Organic matter content (1.00)		
				Large stones (0.67)		
				Dense layer (0.50)		
			Chesuncook (4%)	Depth to saturated zone (1.00)		
				Dense layer (0.50)		
				Unstable excavation walls (0.01)		
			Ragmuff (3%)	Depth to hard bedrock (1.00)		
				Depth to saturated zone (1.00)		
				Unstable excavation walls (0.01)		
			Wonsqueak	Ponding (1.00)		
			(1%)	Depth to saturated zone (1.00)		
				Unstable excavation walls (0.01)		
ils for Area of Interest				507.9	100.0	

Rating	Acres in AOI	Percent of AOI	
Very limited	507.7	100.0%	
Somewhat limited	0.2	0.0%	
Totals for Area of Interest	507.9	100.0%	

# **Description**

**ENG** - Engineering

Shallow excavations are trenches or holes dug to a maximum depth of 5 or 6 feet for graves, utility lines, open ditches, or other purposes. The ratings are based on the soil properties that influence the ease of digging and the resistance to sloughing. Depth to bedrock or a cemented pan, hardness of bedrock or a cemented pan, the amount of large stones, and dense layers influence the ease of digging, filling, and compacting. Depth to the seasonal high water table, flooding, and ponding may restrict the period when excavations can be made. Slope influences the ease of using machinery. Soil texture, depth to the water table, and linear extensibility (shrink-swell potential) influence the resistance to sloughing.

The ratings are both verbal and numerical. Rating class terms indicate the extent to which the soils are limited by all of the soil features that affect the specified use. "Not limited" indicates that the soil has features that are very favorable for the specified use. Good performance and very low maintenance can be expected. "Somewhat limited" indicates that the soil has features that are moderately favorable for the specified use. The limitations can be overcome or minimized by special planning, design, or installation. Fair performance and moderate maintenance can be expected. "Very limited" indicates that the soil has one or more features that are unfavorable for the specified use. The limitations generally cannot be overcome without major soil reclamation, special design, or expensive installation procedures. Poor performance and high maintenance can be expected.

Numerical ratings indicate the severity of individual limitations. The ratings are shown as decimal fractions ranging from 0.01 to 1.00. They indicate gradations between the point at which a soil feature has the greatest negative impact on the use (1.00) and the point at which the soil feature is not a limitation (0.00).

The map unit components listed for each map unit in the accompanying Summary by Map Unit table in Web Soil Survey or the Aggregation Report in Soil Data Viewer are determined by the aggregation method chosen. An aggregated rating class is shown for each map unit. The components listed for each map unit are only those that have the same rating class as listed for the map unit. The percent composition of each component in a particular map unit is presented to help the user better understand the percentage of each map unit that has the rating presented.

Other components with different ratings may be present in each map unit. The ratings for all components, regardless of the map unit aggregated rating, can be viewed by generating the equivalent report from the Soil Reports tab in Web Soil Survey or from the Soil Data Mart site. Onsite investigation may be needed to validate these interpretations and to confirm the identity of the soil on a given site.

# **Rating Options**

Aggregation Method: Dominant Condition Component Percent Cutoff: None Specified

Tie-break Rule: Higher

LUPC Received 7/1/2025

# WETLAND, WATERCOURSE AND VERNAL POOL RECONNAISSANCE AND DELINEATION REPORT: PROPOSED UNDERGROUND UTILITY PROJECT: MAY 2025

Burnt Jacket Mountain and Moosehead Lake Beaver Cove, Maine





Prepared by: Flycatcher LLC 106 Lafayette Street, Suite 2A Yarmouth, ME 04096 http://www.flycatcherllc.com

May 2025

#### **Contents**

1.0	Introduction	1
2.0	Survey Area	
3.0	Methods	
٠.	Wetlands	1
3.2 3.3 3.4 4.0	Streams  Vernal Pool Survey  GPS Location  Findings	3 3
4.1 4.2 4.3 5.0	Wetlands	4
Appe	ndices	
Appen	dix A Figuresdix B Tablesdix C Photographs	7



#### 1.0 Introduction

As requested by JLF Architecture (JLF), in February 2025 Flycatcher LLC (Flycatcher) conducted a natural resources field review along 2.5 miles of Burnt Jacket Road in Beaver Cove, Maine (Survey Area). The extent of the Survey Area is depicted on Figure 1 - USGS Location Map and Figure 2 - Natural Resource Maps (Appendix A). The purpose of this reconnaissance level survey was to identify the rough boundaries of protected resources to inform the potential development of the underground utility, and siting aboveground splice boxes, which would power future development on the property (Project). The survey was completed during this timeframe to help the client continue site planning and design during the winter months. The results of this survey provided information for planning purposes and was not suitable for final engineering or permitting purposes in all areas.

On May 2, 2025 a Flycatcher biologist returned to the Survey Area to perform a wetland delineation and vernal pool survey in the portion of the Survey Area where the utility will transfer from above to below ground near the intersection of Burnt Jacket Road with Lily Bay Road, and in locations of proposed above ground splice boxes.

This report provides a description of the methods used and the findings of the surveys. Definitions and regulations referenced in this report follow those prescribed by the U.S. Army Corps of Engineers (USACE) and the Maine Land Use Planning Commission (LUPC), the lead agencies that oversee natural resources protection and permitting in Maine.

#### 2.0 Survey Area

**General Description:** As depicted on Figure 1, the approximately 18-acre Survey Area consists of a 40-foot swath, 20 feet on either side, of a 2.5 mile section of Burnt Jacket Road. The Survey Area extends westerly along Burnt Jacket Road from the intersection with Lily Bay Road to a previously delineated area at the intersection with Evergreen Point Road. Burnt Jacket Road is maintained to allow vehicle travel to Burnt Jacket Mountain and to the few existing houses and camps along Moosehead Lake.

#### 3.0 Methods

#### 3.1 Wetlands

Wetlands are defined by the federal government as: "Those areas that are inundated or saturated by surface or ground water at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions. Wetlands generally include swamps, marshes, bogs, and similar areas" (Federal Register, 1982).

The LUPC definition of Freshwater Wetland is "Freshwater swamps, marshes, bogs and similar areas that are inundated or saturated by surface or groundwater at a frequency and for a duration sufficient to support, and which under normal circumstances do support, a prevalence of wetland vegetation typically adapted for life in saturated soils and not below the normal high water mark of a body of standing water, coastal wetland, or flowing water." 1

#### 3.1.1 Wetland Reconnaissance Survey

Experienced wetland scientists from Flycatcher completed field reconnaissance for natural resources within the Survey Area during winter conditions in early 2025. The scientists utilized topography and the presence or absence of hydrophytic vegetation to determine the locations of the regulated natural resources.

<sup>&</sup>lt;sup>1</sup> Maine Land Use Planning Commission Chapter 2 of the Commission's Rules: Definitions. 2022. 01-672 CHAPTER 2



The vegetation wetland indicator status followed the current version USACE National Wetland Plant List<sup>2</sup>; being facultative (FAC), facultative upland (FACU), facultative wetland (FACW), obligate wetland (OBL), or upland (UPL). An area with a predominance of wetland dependent vegetation (FAC, FACW, or OBL) or upland vegetation (FAC, FACU, or UPL), informed the determination and grouping of site features into the three categories listed below:

#### Wetland:

- Located within low-lying areas and/or areas with pit and mound microtopography;
- Dominant vegetation is OBL, FACW, and/ or FAC; and
- Hydrology indicators were visible and observed.

#### **Upland:**

- Landscape position and topography are characteristic of upland areas;
- Dominant vegetation UPL, FACU, FAC; and
- Hydrology indicators were not observed.

#### Potential Wetland:

- Vegetation was neither dominant for wetland or upland indicator status species; and
- There was not enough information available on hydrology and topography to make a definite determination

The intent of this reconnaissance survey was to facilitate the avoidance and minimization of impacts to wetland features and it did not constitute a formal delineation.

#### 3.1.2 Wetland Delineation

Wetland delineations were conducted in accordance with the USACE Wetland Delineation Manual<sup>3</sup> and the Northcentral and Northeast Regional Supplement (Version 2.0).<sup>4</sup> The manual and supplement provide a repeatable methodology to identify and map wetland areas and are the accepted wetland delineation methodology of the LUPC and the USACE.

The USACE, as part of an interagency effort with the U.S. Environmental Protection Agency (EPA), the U.S. Fish and Wildlife Service (USFWS), and the U.S. Department of Agriculture NRCS, developed the 2016 National Wetland Plant List (NWPL). The NWPL is used to determine whether the hydrophytic vegetation parameter is met when conducting wetland determinations under the Clean Water Act. Plant names and hydrophytic determinations were based on the most current update to the NWPL.<sup>5</sup> Hydric soil determinations were based on Field Indicators for Identifying Hydric Soils in New England, Version 4,<sup>6</sup> Field

<sup>&</sup>lt;sup>5</sup> U.S. Army Corps of Engineers 2022. National Wetland Plant List, version 3.4 http://wetland-plants.usace.army.mil/U.S. Army Corps of Engineers Engineer Research and Development Center Cold Regions Research and Engineering Laboratory, Hanover, NH <sup>6</sup> New England Hydric Soils Technical Committee. 2018 Version 4, Field Indicators for Identifying Hydric Soils in New England. New England Interstate Water Pollution Control Commission, Lowell, MA.



<sup>&</sup>lt;sup>2</sup> U.S. Army Corps of Engineers. (2023). 2022 National Wetland Plant List, version 3.6. U.S. Army Engineer Research and Development Center, Vicksburg, MS

<sup>&</sup>lt;sup>3</sup> Environmental Laboratory. 1987. "Corps of Engineers Wetlands Delineation Manual," Technical Report Y-87-1, U.S. Army Engineer Waterways Experiment Station, Vicksburg, Miss.

<sup>&</sup>lt;sup>4</sup> U.S. Army Corps of Engineers. 2012. Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast Region (Version 2.0), ed. J. S. Wakeley, R. W. Lichvar, C. V. Noble, and J. F. Berkowitz. ERDC/EL TR-12-1. Vicksburg, MS: U.S. Army Engineer Research and Development Center.

*Indicators of Hydric Soils in the United States, Version 8.2,*<sup>7</sup> and the Maine Association of Professional Soil Scientist (MAPSS) Key for the Identification of Soil Drainage Class<sup>8</sup>.

#### 3.2 Streams

The LUPC definition of Flowing Water is: a channel that has defined banks created by the action of surface water and has two or more of the following characteristics:

- a) It is depicted as a solid or broken blue line on the most recent edition of the U.S. Geological Survey 7.5-minute series topographic map or, if that is not available, a 15-minute series topographic map.
- b) It contains or is known to contain flowing water continuously for a period of at least six months of the year in most years.
- c) The channel bed is primarily composed of mineral material such as sand and gravel, parent material or bedrock that has been deposited or scoured by water.
- d) The channel contains aquatic animals such as fish, aquatic insects or mollusks in the water or, if no surface water is present, within the stream bed.
- e) The channel contains aquatic vegetation and is essentially devoid of upland vegetation. Such waters are commonly referred to as rivers, streams, and brooks. Flowing water does not mean a ditch or other drainage way constructed, or constructed and maintained, solely for the purpose of draining storm water or a grassy swale.

LUPC further defines the term Flowing Water as follows:

<u>Major Flowing Water</u>: A flowing water downstream from the point where such water drains 50 square miles or more.

<u>Minor Flowing Water</u>: A flowing water upstream from the point where such water drains less than 50 square miles.

Watercourse identification relied upon the LUPC definitions and the methods outlined in the Maine Department of Environmental Protection (MDEP) *Identification Guide for Rivers, Streams, and Brooks*<sup>9</sup>.

During the reconnaissance mapping the wetland scientists mapped approximate locations of streams within the Survey Area. Evidence of a channel was used to identify potential streams; however, due to snow cover during the survey some channels were obscured and not observed.

As part of the May 2025 delineation the wetland scientist mapped streams and recorded data for evidence of hydrology, substrate, bankfull widths, Ordinary High Water Mark widths, water depths, and presence of aquatic organisms and vegetation.

#### 3.3 Vernal Pool Survey

Vernal pools are temporarily/seasonally flooded wetlands that provide the primary breeding habitat for vernal pool indicator species, and a host of secondary faunal species. Wood frogs (*Lithobates sylvaticus*) spotted salamanders (*Ambystoma maculatum*), blue spotted salamanders (*Ambystoma laterale*), and fairy shrimp (*Eubranchipus spp.*) are vernal pool indicator species that depend on vernal pools for breeding habitat. Because they are generally judged by the regulatory authorities based on productivity of breeding

<sup>&</sup>lt;sup>9</sup> Danielson, T. J. 2018. Natural resources Protection Act (NRPA) Streams, Rivers, and Brooks. Maine Department of Environmental Protection, Augusta, ME.



<sup>&</sup>lt;sup>7</sup> United States Department of Agriculture, Natural resources Conservation Service. 2018. Field Indicators of Hydric Soils in the United States, Version 8.2. L.M. Vasilas, G.W. Hurt, and J.F. Berkowitz (eds.). USDA, NRCS, in cooperation with the National Technical Committee for Hydric Soils.

<sup>&</sup>lt;sup>8</sup> Maine Association of Professional Soil Scientists. 2013. Key for the Identification of Soil Drainage Class. Revised.

vernal pool species, vernal pools must be assessed during the breeding season (generally mid-April to Late-May).

The Maine Association of Wetland Scientists (MAWS) Vernal Pool Technical Committee Vernal Pool Survey Protocol (April 2014) <sup>10</sup> methods were relied upon for performing surveys. During the reconnaissance mapping the wetland scientists mapped potential vernal pools in accordance with Section 3.4.4, Non-Breeding Season Survey. The wetland scientists relied on topography, best professional judgement, and evidence of inundation to identify potential vernal pools.

During the May 2025 delineation the wetland scientist conducted a vernal pool survey in the spring breeding season to assess breeding activity. This survey followed the definitions provided in Chapter 335 of the NRPA<sup>11</sup>, USACE Maine General Permit<sup>12</sup>, and the methods described in the MAWS Vernal Pool Protocol.

#### 3.4 GPS Location

Features (e.g., wetlands, streams, vernal pools, estimated wetland boundaries) located during the on-site survey were geolocated using a mapping grade global positioning system (GPS) unit (Juniper Systems' Geode GPS Antenna and ESRI's ArcGIS Collector software).

#### 4.0 Findings

Wetland scientists completed the reconnaissance survey of the Survey Area on February 4, 2025. The site was covered in approximately 1-3 feet of snow. Due to the site conditions, our reconnaissance efforts were largely informed by the visible plant species and potential topography/hydrology present. Soil explorations were not possible due to frozen ground. These findings were considered preliminary and intended to only inform design activities.

On May 2, 2025 a Flycatcher biologist returned to the Survey Area to perform a wetland delineation and vernal pool survey for a portion of the Survey Area where the utility would transition from above to below ground near the intersection of Burnt Jacket Road with Lily Bay Road, and to site above ground splice boxes at multiple locations along Burnt Jacket Road.

#### 4.1 Wetlands

The locations of delineated wetlands and reconnaissance mapped approximate wetland areas are depicted in the Figure 2 map set in Appendix A and summary descriptions of the delineated wetlands including covertype<sup>13</sup>, vegetation, hydrology, and hydric soil indicators are provided in Table 1, Appendix B. When the reconnaissance survey indicated that a wetland might be present but a wetland delineation was not completed, these areas are labelled as "Estimated Wetland" and "Potential Wetland" on Figure 2 in Appendix A.

#### 4.2 Streams

The location of each delineated stream is depicted in the Figure 2 map set in Appendix A and summary descriptions are provided in Table 2, Appendix B.

<sup>&</sup>lt;sup>13</sup>Wetland classifications per USFWS' Cowardin et al. 1979 (<a href="https://www.fws.gov/wetlands/Documents/Classification-of-Wetlands-and-Deepwater-Habitats-of-the-United-States.pdf">https://www.fws.gov/wetlands/Documents/Classification-of-Wetlands-and-Deepwater-Habitats-of-the-United-States.pdf</a>).



<sup>&</sup>lt;sup>10</sup> MAWS (2014). Vernal Pool Technical Committee Vernal Pool Survey Protocol. April 2014.

<sup>&</sup>lt;sup>11</sup> MEDEP. Significant Wildlife Habitat. Chapter 335, Section 9.

<sup>&</sup>lt;sup>12</sup> USACE (2020). Department of the Army General Permits for the State of Maine. Section IV. 20.

#### 4.3 Vernal Pools

Three vernal pools were mapped during the spring breeding season survey. As all of these were determined to be man-made features and therefore would not meet a Significance determination by the MDIFW, a second follow-up visit was not conducted. The location of each vernal pool is depicted in the Figure 2 map set in Appendix A and summary descriptions are provided in Table 3, Appendix B.

#### 5.0 Conclusions


An underground utility with associated above-ground splice boxes is proposed to provide power to a potential development in the vicinity of Burnt Jacket Road in Beaver Cove, Maine. A reconnaissance survey was completed in early 2025 in order to provide a high-level assessment of potential resources along the roadway so as to inform the final design. A formal field survey was completed in the Spring of 2025 to delineate wetlands and streams as well as survey for vernal pools. The field effort identified eleven wetlands and three streams along the portion of Burnt Jacket Road where the utility line will be underground. Three vernal pools were also located, although none of these met the state definition of a Significant Vernal Pool.




### **Appendix A Figures**


Figure 1. USGS Survey Area Location Map Figure 2. Natural Resource Maps








dinate System: NAD 1983 StatePlane Maine East FIPS 1801 Fee




e System: NAD 1983 StatePlane Maine East FIPS 1801 Feet




nate System: NAD 1983 StatePlane Maine East FIPS 1801 Feet




nate System: NAD 1983 StatePlane Maine East FIPS 1801 Feet



ate System: NAD 1983 StatePlane Maine Fast FIPS 1801 Fee






inate System: NAD 1983 StatePlane Maine East FIPS 1801 Fee



nate System: NAD 1983 StatePlane Maine East FIPS 1801 Feet



## **Appendix B Tables**

Table 1. Delineated Wetlands
Table 2. Delineated Streams
Table 3. Delineated Vernal Pools



Table 1. Delineated Wetlands									
Resource ID	Cowardin Classification1	Hydrology Indicators	Dominant Vegetation	Hydric Soil Indicators	Description & Notes				
W-RDK-500	PFO	Surface Water (A1), High Water Table (A2), Saturation (A3), Sparsely Vegetated Concave Surface (B8), Water-stained Leaves (B9), Drainage Patterns (B10), Geomorphic Position (D2), Microtopographic Relief (D4), FAC-Neutral Test (D5)	Balsam fir (Abies balsamea), yellow birch (Betula alleghaniensis), sensitive fern (Onoclea sensibilis), cottongrass bullrush (Scirpus cyperinus),	Depleted Below Dark Surface (Allb)	Wetland was apparently part of a larger wetland located to the north of Burnt Jacket Road that was bisected by the road construction; still connected by a culvert under the road. Contains VP-CWF-1.				
W-RDK-501	PFO	Surface Water (A1), High Water Table (A2), Saturation (A3), Sparsely Vegetated Concave Surface (B8), Water-stained Leaves (B9), Drainage Patterns (B10), Geomorphic Position (D2), Microtopographic Relief (D4), FAC-Neutral Test (D5)	Balsam fir, yellow birch, red maple ( <i>Acer rubrum</i> ), bluejoint ( <i>Calamagrostis canadensis</i> )	Histic epipedon (A2)	Small, isolated man-made wetland. Old borrow located south of Burnt Jacket Road and west of Lily Bay Road. Contains VP-RDK-500.				
W-RDK-502	PFO	Surface Water (A1), High Water Table (A2), Saturation (A3), Sparsely Vegetated Concave Surface (B8), Water-stained Leaves (B9), Drainage Patterns (B10), Geomorphic Position (D2), Microtopographic Relief (D4), FAC-Neutral Test (D5)	Eastern arborvitae (Thuja occidentalis), balsam fir, broad- leaf cat-tail (T <i>ypha latifolia</i> )	Histosol (A1)	Large, forested wetland located north of Burnt Jacket Road and west of Lily Bay Road. Connected to W-RDK-500 by culvert under Burnt Jacket Road.				
W-RDK-503	PFO	Surface Water (A1), High Water Table (A2), Saturation (A3), Sparsely Vegetated Concave Surface (B8), Water-stained Leaves (B9), Geomorphic Position (D2), Microtopographic Relief (D4), FAC- Neutral Test (D5)	Balsam fir, yellow birch, red maple, eastern arborvitae, sensitive fern, broad-leaf meadowsweet ( <i>Spiraea</i> <i>latifolia</i> ), bluejoint	Depleted Matrix (F3a)	Large, forested wetland located south of Burnt Jacket Road. Connected to W-RDK-504 by culvert under Burnt Jacket Road.				

W-RDK-504	PFO	Surface Water (A1), High Water Table (A2), Saturation (A3), Sparsely Vegetated Concave Surface (B8), Water-stained Leaves (B9), Geomorphic Position (D2), Microtopographic Relief (D4), FAC- Neutral Test (D5)	Balsam fir, yellow birch, red maple, eastern arborvitae, sensitive fern, broad-leaf meadowsweet (Spiraea latifolia), bluejoint	Depleted Matrix (F3a)	Large, forested wetland located north of Burnt Jacket Road. Connected to W-RDK-503 by culvert under Burnt Jacket Road.
W-RDK-505	PFO	Surface Water (A1), High Water Table (A2), Saturation (A3), Sparsely Vegetated Concave Surface (B8), Water-stained Leaves (B9), Drainage Patterns (B10), Geomorphic Position (D2), Microtopographic Relief (D4), FAC-Neutral Test (D5)	Black spruce ( <i>Picea mariana</i> ), balsam fir, eastern arborvitae, yellow birch, red maple, speckled alder ( <i>Alnus incana</i> ), bluejoint, steeplebush ( <i>Spiraea</i> tomentosa), lamp rush ( <i>Juncus</i> effusus), large cranberry ( <i>Vaccinium macrocarpon</i> ), leatherleaf ( <i>Chamaedaphne</i> calyculata)		Large black spruce bog located on the south side of Burnt Jacket Road. Connected to W-RDK-506 by culvert under Burnt Jacket Road.
W-RDK-506	PFO	Surface Water (A1), High Water Table (A2), Saturation (A3), Sparsely Vegetated Concave Surface (B8), Water-stained Leaves (B9), Drainage Patterns (B10), Geomorphic Position (D2), Microtopographic Relief (D4), FAC-Neutral Test (D5)	Black spruce, balsam fir, eastern arborvitae, yellow birch, red maple, speckled alder, bluejoint, steeplebush, lamp rush, large cranberry, leatherleaf	Histosol (A1)	Large black spruce bog located on the north side of Burnt Jacket Road. Connected to W-RDK-505 by culvert under Burnt Jacket Road.
W-RDK-507	PEM/PSS	Saturation (A3), Sparsely Vegetated Concave Surface (B8), Water-Stained Leaves (B9), Drainage Patterns (B10), Geomorphic Position (D2), Microtopographic Relief (D4), FAC- Neutral Test (D5)	Interrupted fern ( <i>Osmunda</i> claytoniana ), ostrich fern ( <i>Matteuccia struthiopteris</i> ), gray willow ( <i>Salix bebbiana</i> ), sensitive fern, red maple	Depleted Matrix (F3b)	Portion of a larger forested wetland outside the Survey Area, within Survey Area is a log landing where trees were cut and soil regraded. Flows into ditch along Burnt Jacket Road which outlets as stream S-RDK-501.

W-RDK-508	PFO	High Water Table (A2), Saturation (A3), Drainage Patterns (B10), Geomorphic Position (D2), Microtopographic Relief (D4), FAC-Neutral Test (D5)	Eastern arborvitae, balsam fir, yellow birch, sensitive fern	Depleted Matrix (F3a)	Narrow, forested swale with a discontinuous channel that flows to the Burnt Jacket Road ditch. The ditch downslope is maintained and not wetland or a stream. That water flows through a culvert under Burnt Jacket Road and the outlet is channelized and is stream S-RDK-502.
W-RDK-509	PEM	Surface Water (A1), High Water Table (A2), Saturation (A3), Drainage Patterns (B10), Geomorphic Position (D2), Microtopographic Relief (D4), FAC-Neutral Test (D5)	Fringed sedge (Carex crinita), yellow birch, balsam fir, eastern arborvitae, meadow horsetail, (Equisetum pratense), evergreen wood fern, sensitive fern, interrupted fern (Osmunda claytoniana)	Depleted Matrix (F3)	The area is a manmade wetland, excavated culvert outlet that is not maintained and has wetland parameters.
W-RDK-510	PEM/PSS	High Water Table (A2), Saturation (A3), Drainage Patterns (B10), Geomorphic Position (D2), Microtopographic Relief (D4), FAC-Neutral Test (D5)	Red maple, gray willow, fringed sedge, sensitive fern, balsam fir, speckled alder	Depleted Matrix (F3a)	Portion of a larger forested wetland outside the Survey Area, within Survey Area is a log landing where trees were cut and soil regraded. Flows into ditch along Burnt Jacket Road. The ditch downslope is maintained and not wetland or a stream. That water flows through a culvert under Burnt Jacket Road and the outlet is wetland W-RDK-509.

<sup>1.</sup> Wetland classifications per USFWS' Cowardin et al. (1979) (https://www.fws.gov/wetlands/Documents/Classification-of-Wetlands-and-Deepwater-Habitats-of-the-United-States.pdf).

<sup>\* =</sup> Morphological Adaptations

Table 2. De	Table 2. Delineated Streams									
Resource Field ID(s)	Flow Regime	Flow Direction	Dominant Substrates	Approximate Width (ft.)	Approximate Depth (ft.)	Associated Resources	Description			
S-RDK-500	Perennial	Northwest	Muck, sand, gravel	4 to 6	1.0 – 2.0	None	Meanders through large forested swamp and crosses under Burnt Jacket Road. Upstream of the road the substrate is muck and downstream is sand and gravel.			
S-RDK-501	Intermittent	Northeast	Sand, gravel	2 to 3	0.5	None	Wetland W-RDK-507 drains to a Burnt Jacket Road ditch which flows through a culvert under the road. The stream begins at the road culvert flowing within a man-made ditch through an upland. The water flow has created a channel within the ditch.			
S-RDK-502	Intermittent	Northeast	Sand, gravel	2 to 3	0.5	Forested swamp	Several wetlands drain to a Burnt Jacket Road ditch which flows through a culvert under the road. The stream begins at the road culvert flowing within a man-made ditch through an upland. The water flow has created a channel within the ditch.			

Table 3. Delineated Vernal Pools									
		Vernal Pool Indicator Species Use				lse			
	(based on one survey)								
Resource ID	Pool Origin	Wood Frog Egg Masses	Spotted Salamander Egg Masses	Blue Spotted Salamander Egg Masses	Fairy Shrimp or RTE	NRPA Significant*	Associated Resources	Description	
VP-CWF-1	Unnatural	15	2	15	0	No	W-RDK-500	Excavation: large roadside borrow near the intersection of Burnt Jacket and Lily Bay Roads.	
VP-RDK- 500	Unnatural	13	0	0	0	No	W-RDK-501	Excavation: large roadside borrow near the intersection of Burnt Jacket and Lily Bay Roads.	
VP-RDK- 501	Unnatural	18	0	0	0	No	Large forested swamp	Small set of ruts adjacent to Burnt Jacket Road within a large wetland complex.	

<sup>\*</sup>Vernal pool significance determined in breeding season by the criteria found in: MDEP. Significant Wildlife Habitat. Chapter 335, Section 9.

PVP-NIA-1 & 2 observed outside vernal pool breeding season; potential vernal pool survey results.

Wetland, Watercourse and Vernal Pool Reconnaissance and Delineation Report: May 2025 Proposed Underground Utility Project

**Appendix C Photographs** 





Wetland W-RDK-500



Wetland W-RDK-501





Wetland W-RDK-502



Wetland W-RDK-503





Wetland W-RDK-504



Wetland W-RDK-505





Wetland W-RDK-507



Wetland W-RDK-508





Stream S-RDK-500



Stream S-RDK-501





Stream S-RDK-502




Vernal Pool VP-CWF-1





Vernal Pool VP-RDK-500



Vernal Pool VP-RDK-501



#### **EXHIBIT 24B - WATER AND AIR QUALITY:**

The project area at its closet point is located approximately 921 feet from Moosehead Lake and will not impact mapped wetlands or streams outside of existing previously disturbed roadways. Groundwater discharge and extraction are not planned or anticipated as part of this utility extension.

Air emissions from the project area are limited to traffic exhaust during construction. Traffic is anticipated to be minimal after construction and limited to residential and land management uses. The project does not require an Air Emissions License from the MEDEP Bureau of Air Quality. There are no odors anticipated, or potential odor sources identified for the proposed project.

#### EXHIBIT 25 - EROSION, SEDIMENTATION, AND DRAINAGE CONTROL MEASURES:

The project will result in soil disturbance less than one acre. Adequate soil erosion prevention measures will comply with the Basic Standards of MEDEP Chapter 500. All Erosion and Sedimentation Control Devices will be constructed in conformance with the Maine Erosion and Sediment Control Best Management Practices (BMPs) Manual for Designers and Engineers, dated October 2016, as currently revised. A Construction Stormwater Pollution Prevention Plan (SWPPP) prepared by SME is attached as Exhibit 25B. Erosion and sediment control details and specifications are included as part of the SWPPP. A copy of the SWPPP will be maintained on-site during construction and available for contractor reference.

# CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN (SWPPP) UTILITY EXTENSION BURNT JACKET ROAD BEAVER COVE, MAINE

Prepared for

## **BURNT JACKET HOLDING I, LLC**

May 2025

4 Blanchard Road P.O. Box 85A Cumberland, ME 04021 SME SEVEE & MAHEI

#### **TABLE OF CONTENTS**

Section No.	Title	Page No.
1.0 INTRODUCTION		1-1
2.0 PROJECT DESCRIPTION		2-1
3.0 EROSION AND SEDIMENTA	TION CONTROL (MCGP APPENDIX A)	3-1
	n	
3.1.1 Buffers a	nd Perimeter Controls	3-1
3.2 Preserve Native To	psoil, Unless Infeasible	3-1
3.3 Minimize Soil Com	paction	3-1
3.4 High Infiltration Ca	pacity Soils	3-2
3.5 Sediment Barriers .		3-2
3.6 Stabilized Construc	tion Entrance	3-3
3.7 Temporary Sedime	nt Basins	3-3
3.8 Cationic Treatment	Chemicals	3-4
3.9 Temporary Stabiliza	ation	3-4
3.10 Removal of Temp	orary Measures	3-4
3.11 Permanent Stabili	zation	3-5
3.12 Winter Constructi	on	3-6
3.13 Laydown and Stag	ring Areas	3-6
3.14 Parking Area		3-7
3.15 Roads		3-7
3.16 Culverts		3-7
3.17 Stormwater Chan	nels	3-7
3.18 Utility Trench		3-7
3.19 Additional Require	ements	3-7
4.0 INSPECTION AND MAINTEI	NANCE (MCGP APPENDIX B)	4-1
4.1 Inspection		4-1
4.2 Maintenance and C	Corrective Action	4-1
4.3 Documentation		4-2
4.4 Perimeter Fence		4-2
4.5 Additional Require	ments	4-2
5.0 HOUSEKEEPING (MCGP AP	PENDIX C)	5-1
5.1 Spill Prevention		5-1
5.2 Groundwater Prote	ection	5-3
5.3 Fugitive Sediment a	and Dust	5-3
5.4 Debris and Other N	Naterials	5-4
5.5 Excavation De-Wat	ering	5-4
5.6 Vehicle and Equipn	nent Washing	5-4
5.7 Authorized Non-Sto	ormwater Discharges	5-4
5.8 Unauthorized Non-	Stormwater Discharges	5-5
5.9 Additional Require	ments	5-5

#### **LIST OF APPENDICES**

APPENDIX A INSPECTION CHECKLIST AND REPORT FORM APPENDIX B DRAWINGS: C-101 THROUGH 104 AND C-300

#### **LIST OF FIGURES**

<u>Figure</u>	No.	Title	Page No.
1	SITE LOCATION MAP		2-2

# CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN UTILITY EXTENSION BURNT JACKET HOLDING I, LLC BEAVER COVE, MAINE

### 1.0 INTRODUCTION

This Stormwater Pollution Prevention Plan (Plan) was prepared for the construction of the proposed utility extension along Burnt Jacket Road in Beaver Cove, Maine (Project) in accordance with the Maine Department of Environmental Protection (MEDEP) Erosion and Sediment Control BMP Manual, and Maine Construction General Permit (MCGP).

#### 2.0 PROJECT DESCRIPTION

Burnt Jacket Holding I, LLC is proposing to extend three-phase power from Lily Bay Road to the intersection of Burnt Jacket Road and Evergreen Point Road in Beaver Cove, Maine. The project will connect to the existing overhead utility service along Lily Bay Road through three new utility poles, after which it will be buried in a privately owned and maintained conduit trench. The total length of the project will be roughly 12,500 feet (2.36 miles). Electrical concrete vaults will be located approximately every 1,000 feet to provide access to the cables and in two locations sectionalizer cabinets will be installed approximately 15 feet outside the edge of the road. See Figure 1, Site Location Map, for the site location on a 7.5-min USGS Topo Quad Map. More details on the project are shown in the engineering drawing set appended to this Plan.

The following sections of the Plan address the specific requirements for a Construction Activity of the MCGP and will be followed during construction of the Project.

#### 3.0 EROSION AND SEDIMENTATION CONTROL (MCGP APPENDIX A)

This section has been prepared to address Appendix A of the MCGP and provide further project details to demonstrate compliance with the requirements.

#### 3.1 Pollution Prevention

The project has been designed to minimize disturbed areas and protect the natural downgradient buffers as much as practicable. The Contractor will provide the appropriate Erosion Control Best Management Practices (BMPs) to control the stormwater volume and velocity within the site to minimize soil erosion. This will include minimizing impacts to steep slopes, controlling stormwater discharges, including both peak flow rates and volume to minimize erosion at outlets. The discharge from the site will be controlled to prevent erosion of any open drainage channels, swales, stream channels or stream banks; and upland, coastal, or freshwater wetlands off the project site.

#### 3.1.1 Buffers and Perimeter Controls

There will be no project disturbance within 50 feet of a protected natural resource other than what has been shown on the provided drawing set. BMP perimeter controls will be installed downslope from any exposed soil or disturbed areas within the project area. In areas of disturbance within 50 feet of a protected natural resource, perimeter controls will be doubled. All erosion and sedimentation control measures will be followed throughout this document and as shown within the approved drawing set.

#### 3.2 Preserve Native Topsoil, Unless Infeasible

Suitable topsoil within the project disturbance limits will be stripped and stockpiled for reuse in reclaiming disturbed land areas. When project construction results in excess topsoil, the Contractor will make every effort to spread it within the project site or will take it off-site after completion of final site reclamation. Topsoil will be stockpiled in a manner such that natural drainage is not obstructed, and no off-site sedimentation will occur. Stockpiles will not be located within 100 feet of wetlands and will be at least 50 feet upgradient of any perimeter silt fence. Stockpiles not actively being used shall be seeded and mulched to help prevent erosion and pollution.

### 3.3 Minimize Soil Compaction

In areas of the site where vegetation will be established, vehicle and equipment use will be restricted, or the soils will be rehabilitated through tilling or ripping to a depth that will leave an uncompacted root zone. In areas where new topsoil will be installed, topsoil will be lightly compacted to ensure a uniform and firm seedbed (excessive compaction will increase runoff and prevent seed rooting). Seeding and mulching will be applied as soon as possible upon final grading or as a temporary cover if final grading will not occur before 14 days.

	Topsoil Loam and Seed								
Description:	Topsoil provides a loose medium for root development, and a good quality-topsoil will contai decomposed organic matter which retains nutrients and water for plant growth. The topso should be friable, loamy and should be free of debris, trash, stumps, rocks, roots, weeds, or an substance that is toxic to plant growth.								
Maintenance and Compaction Requirements	<ul> <li>Topsoil should not be placed on frozen, muddy, or an extremely wet subgrade.</li> <li>Prior to spreading the topsoil, the subgrade should be loosened or scarified to a depth of at least 2 inches to ensure bonding.</li> <li>The topsoil should be 4 inches deep and uniform. Rototilling for a deeper rooting zone on poor subsoils (sloping wet sites or with sand and gravels) is recommended.</li> <li>Lightly compact the topsoil to ensure a uniform and firm seedbed (excessive compaction will increase runoff and prevent seed rooting).</li> <li>The sideslopes of the topsoil stockpile will not exceed 2:1. Topsoil stockpiles will be surrounded with siltation fencing and will be temporarily seeded with Aroostook rye, annual or perennial ryegrass within seven days of formation, or temporarily mulched.</li> <li>Inspected after 1-inch rain event, replace loam and seed on bare soils</li> </ul>								
Design Specifications	See Drawing C-300 and C-301								

#### 3.4 High Infiltration Capacity Soils

The proposed project will preserve the natural landscape and Hydrologic Soil Groups A and B as much as practicable, and to the extents shown on the plans. There will be no disturbance to HSG A and B soils within the project limits.

In areas where the project site will be worked on for longer than seven days, temporary sediment traps and basins will be constructed over HSG A and B soils where possible to promote infiltration of construction site runoff.

### 3.5 Sediment Barriers

Sediment barriers will be installed prior to any soil disturbance at the project site in accordance with the attached drawings. Sediment barriers (i.e., silt fence, erosion control berm, and silt socks) will be monitored on a regular basis. The contractor will ensure that structures are functioning properly and will perform necessary maintenance described in the Maine Construction General Permit and the MEDEP Erosion Control BMP Manual. The details and specifications for all temporary and permanent erosion controls to be installed at the site are provided in Drawing C-300, Erosion Control Notes and Details in the project plan set.

#### **SPECIFIC PERIMETER CONTROLS**

	SILT FENCE							
Description:  Silt fence is a permeable geotextile fabric which intercepts overland runoff, reduces flow velocity and promotes the settlement of sediments. The geotextile fabric will degrade due to sun exposur and its life span is approximately one field season. Pre-manufactured silt fencing with attache posts is used in most situations.								
Maintenance Requirements  The following actions are recommended after storm events:  Repair and replace damaged silt fence prior to next storm event.  Remove sediment build up once sediment reaches half-way up the fence.  Signs of undercutting at the center or edges of fencing, replace with stone check dam								
Design Specifications	See Drawing C-300 – Erosion and Sediment Control Notes							
	EROSION CONTROL MIX SEDIMENT BARRIER							
1	osion control mix (ECM) are effective on frozen ground, outcrops of bedrock, and heavily rooted other temporary erosion and sediment control measures are not practicable							
Maintenance Requirements  Sediment deposits should be removed when they reach approximately one-half the heig the barrier.  Replace sections of berm that decompose, become clogged with sediment, or other become ineffective. The barrier should be reshaped as needed.  Erosion control mix barriers can be removed or spread into the landscape after construct Any sediment deposits remaining in-place after the barrier is no longer required should spread to conform to existing grade, seeded and mulched.								
Design Specifications	See Drawing C-300 – Erosion and Sediment Control Notes							

#### 3.6 Stabilized Construction Entrance

Prior to construction, stabilized construction entrances will be installed wherever construction vehicles will access and egress from the site. The construction entrance will be stabilized to reduce the tracking of sediment off-site.

STABILIZED CONSTRUCTION ENTRANCE								
Description:	A pad of coarse aggregate at the construction entrance/exit will reduce the tracking of soil from							
	construction traffic onto a public street. Sediments from the tire treads are knocked loose by the							
	angular stones and are trapped in the voids between the stones.							
Maintenance	Maintain 6-inch thick of 2-inch crushed stone.							
Requirements	Sweep or shovel to paved road to remove sediment, complete within same day observed.							
Design Specifications	See Drawing C-300 – Erosion and Sediment Control Notes							

#### 3.7 Temporary Sediment Basins

Where required, temporary sediment basins will be sized to store the 2-year/24-hour storm or provide 3,600 cubic feet of storage per acre draining to the basin. Erosion controls (i.e., sediment barriers, etc.) and velocity dissipation (i.e., riprap outlet protection, riprap overflows) will be used at the discharge of the sediment basin to dissipate velocity and prevent erosion.

Sediment basins, where required, will be equipped with an outlet control structure per the MEDEP Erosion Control BMP Manual, and will discharge to a stabilized riprap apron in a natural drainage channel, or undisturbed area. Exceptions may include periods of extended cold weather, where alternate outlets are

LUPC Received 7/1/2025

required during frozen periods. If the outlet control structure is infeasible for a portion or the entire construction period, the Contractor shall document the site conditions that prevent it from being a viable solution.

Accumulated sediment must be removed when needed to maintain at least half of the design capacity of the basin and respread on-site and stabilized with temporary seed.

#### 3.8 Cationic Treatment Chemicals

The project does not anticipate the use of cationic treatment chemicals to control turbidity in the construction site stormwater. If polymers, flocculants, or other positively charged chemicals are required to reduce turbidity in stormwater, the Contractor will notify MEDEP in advance and obtain authorization for the use. The request for approval will include appropriate controls and implementation procedures to ensure the use will not lead to a violation of water quality standards. In addition, the request will include:

- The types of soil likely to be treated;
- The chemicals to be used;
- The method and quantity of the application;
- Manufacturer's recommendations for use; and
- Proof of training by personnel who will handle and apply the chemicals.

#### 3.9 Temporary Stabilization

Disturbed areas not to be worked on within 14 days of disturbance will be temporarily stabilized within seven days of the disturbance. Areas within 75 feet of a downgradient protected natural resources will be temporary stabilized within 48 hours of disturbance or prior to any storm event, whichever comes first.

### 3.10 Removal of Temporary Measures

Temporary erosion control measures shall remain in-place and be maintained by the Contractor until all related construction is complete and the drainage area is stable. An area is considered stable if 90 percent of grass cover has been established or riprap or other permanent measures are in-place and functioning properly.

Silt barriers shall be removed and disposed of legally and properly off-site. Sediment trapped behind these controls shall be distributed to an area undergoing final grading and graded in an aesthetic manner to conform to the topography and fertilized, seeded, and mulched in accordance with the "PERMANENT SEEDING" specifications included on the drawings provided and presented in Section 3.11 of this Plan. The sediment trapped by these devices shall not be regraded within the existing drainageways.

Once the trapped sediments have been removed from the temporary sedimentation devices, the disturbed areas must be loamed (if necessary), fertilized, seeded, and mulched.

#### 3.11 Permanent Stabilization

If the project area will not be worked for more than one year, or has been brought to final grade, the Contractor will permanently stabilize the area within seven days by planting vegetation, seeding, sod, or through the use of permanent mulch, or riprap, or road sub-base, or other final surface finishes. If using vegetation for stabilization, select the proper vegetation for the light, moisture, and soil conditions; amend areas of disturbed subsoils with topsoil, compost, or fertilizers; protect seeded areas with mulch or, if necessary, erosion control blankets; and schedule sodding, planting, and seeding so to avoid die-off from summer drought and fall frosts. Newly seeded or sodded areas must be protected from vehicle traffic, excessive pedestrian traffic, and concentrated runoff until the vegetation is well-established. If necessary, areas must be reworked and restabilized if germination is sparse, plant coverage is spotty, or topsoil erosion is evident. One or more of the following may apply to a particular site.

- <u>Seeded areas</u>. For seeded areas, permanent stabilization means a 90 percent cover of the disturbed area with mature, healthy plants with no evidence of washing or riling of the topsoil.
- <u>Sodded areas</u>. For sodded areas, permanent stabilization means the complete binding of the sod roots into the underlying soil with no slumping of the sod or die-off.
- <u>Permanent Mulch</u>. For mulched areas, permanent mulching means total coverage of the exposed area with approved mulch material. Erosion Control Mix may be used as mulch for permanent stabilization according to the approved application rates and limitations.
- <u>Riprap</u>. For areas stabilized with riprap, permanent stabilization means that slopes stabilized with riprap have an appropriate backing of a well-graded gravel or approved geotextile to prevent soil movement from behind the riprap. Stone must be sized appropriately. It is recommended that angular stone be used.
- <u>Agricultural Use</u>. For construction projects on land used for agricultural purposes (e.g., pipelines
  across crop land), permanent stabilization may be accomplished by returning the disturbed land
  to agricultural use.
- <u>Paved Areas</u>. For paved areas, permanent stabilization means the placement of the compacted gravel subbase is completed.
- <u>Ditches, Channels, and Swales</u>. For open channels, permanent stabilization means the channel is stabilized with mature vegetation at least three inches in height, with well-graded riprap lining, or with another non-erosive lining capable of withstanding the anticipated flow velocities and flow depths without reliance on check dams to slow flow. There must be no evidence of slumping of the lining, undercutting of the banks, or downcutting of the channel.

Permanent erosion control measures will be implemented during site construction. Materials and construction methods for permanent measures shall be as specified on Drawing C-300.

#### 3.12 Winter Construction

The winter construction season is from November 1 through April 15 of each year, <u>OR</u> outside of the period if the ground is frozen or snow covered. If construction areas are not stabilized with temporary or permanent measures by November 15, then the site will be protected with additional stabilization measures as outlined below:

- <u>Site Stabilization</u>. For winter stabilization, hay mulch is applied at twice the standard temporary stabilization rate. At the end of each construction day, areas that have been brought to final grade must be stabilized. Mulch may not be spread on top of snow;
- <u>Sediment Barriers</u>. All areas within 75 feet of a protected natural resource must be protected with a double row of sediment barriers;
- <u>Ditch</u>. All vegetated ditch lines that have not been stabilized by November 1, or will be worked
  during the winter construction period, must be stabilized with an appropriate stone lining backed
  by an appropriate gravel bed or geotextile unless specifically released from this standard by the
  department; and
- <u>Slopes</u>. Mulch netting must be used to anchor mulch on all slopes greater than 8 percent unless erosion control blankets or erosion control mix is being used on these slopes.

Winter excavation and earthwork will be completed to minimize exposed areas while satisfactorily completing the project. Limit exposed areas to those areas in which work is to occur during the following 15 days and that can be mulched in one day. All areas will be considered denuded until the subbase gravel is installed in roadway areas, or the areas of future loam and seed have been loamed, seeded, and mulched.

#### 3.13 Laydown and Staging Areas

Construction laydown areas will occur on existing impervious surfaces where possible, or if within the limits of disturbance of the project will be:

- On an upland area outside of existing drainage patterns where possible;
- Outside of any wet areas hydraulically connected to downgradient protected natural resource and/or justified use of these areas based on site limitations. Temporary structures (e.g., swales, dikes) will be provided to intercept upgradient stormwater and divert it away; and

LUPC Received 7/1/2025

Designed to provide stormwater quality treatment in compliance with the Application Chapter

500 standard for areas which will be used for more than 12 months.

The laydown areas within the project footprint that are not to remain as a finished surface after

construction shall be removed, the soil below ripped or tilled, and the area loamed, seeded, and mulched.

3.14 Parking Area

During construction, the site will be accessed by pick-up trucks, delivery trucks, and vehicles daily to

deliver and install equipment. Construction crews will park along the side of Burnt Jacket Road in areas

where they will not prohibit the flow of traffic. Outside of the construction period, the project will not

change the volume of traffic along the road.

3.15 Roads

The existing gravel road is crowned and graded to direct stormwater to the stabilized drainage swales on

either side of the road. Disturbed areas of the road will be regraded to match existing conditions and

maintain drainage pathways.

3.16 Culverts

No culverts are proposed as part of this project.

3.17 Stormwater Channels

No new stormwater channels are proposed as part of this project. All existing ditches, swales, and other

open stormwater channels in the project area will be stabilized at the end of each workday and maintained

on a daily basis.

3.18 Utility Trench

All trenches will be backfilled and temporarily stabilized, including spoil and/or backfill piles, at the end of

each workday.

3.19 Additional Requirements

There are no additional requirements identified for this site.

SWPPP\_Utility Extension
Sevee & Maher Engineers, Inc. (231136)

3-7

#### 4.0 INSPECTION AND MAINTENANCE (MCGP APPENDIX B)

The following standards will be met during construction of this project.

#### 4.1 Inspection

Inspections will be undertaken by the Contractor's resident environmental inspector certified by the MEDEP for erosion control BMPs to assure that the controls are properly installed and correctly functioning, and that additional erosion control measures are installed if needed. A series of routine inspections shall be completed to allow for the early identification of potential problems, and to guide routine maintenance activities. Such inspections will occur weekly and within 24 hours after each rainfall event during construction until permanent stabilization measures have been properly installed. Inspections of specific measures will be carried out in accordance with the Schedule included in Appendix B of this Plan. Dates and observations shall be recorded for each inspection on an improved Inspection Log for the site specific BMPs.

#### 4.2 Maintenance and Corrective Action

Routine maintenance activities are designed to ensure proper function of the erosion control measures and minimize pollutant transport from the site. During construction, inspections will be undertaken by the Contractor's Representative to assure that temporary or permanent erosion and sedimentation controls are property installed and functioning correctly and will be completed at the frequency outlined in the inspection checklist included in Appendix A. Corrective actions (supplemental maintenance activities or repairs) should be started within the following workday and should be completed within seven days of the inspection identifying the problem. Each maintenance activity will be recorded on the attached inspection report included in Appendix A.

If the same routine maintenance requirements are needed repeatedly, the Contractor will either complete work to fix any subsequent repeat occurrences of the same problem, or document in the inspection report why the specific reoccurrence should still be addressed as a routine maintenance item.

If BMPs need significant repair or if additional BMPs are necessary, implementation will be completed within seven calendar days, and will be documented in the inspection log why it is infeasible to complete the repair or installation, and document the schedule for installing the BMP and making it operational.

The maintenance needs for most vegetative and stabilization measures may be found in the Maine Erosion and Sediment Control BMPs manual as published in 2016 (or latest version) and/or the Maine Stormwater Best Management Practices Manual.

#### 4.3 Documentation

The Contractor will keep a log summarizing the inspections and corrective action taken in accordance with the log included in Appendix A.

The inspection log will be maintained on site and made accessible to MEDEP staff upon request. The log shall be maintained for a minimum of three years from the completion of permanent stabilization.

### 4.4 Perimeter Fence

The project will not require a perimeter fence.

### 4.5 Additional Requirements

There are no additional requirements for this specific project.

#### 5.0 HOUSEKEEPING (MCGP APPENDIX C)

The following details the anticipated requirements for Housekeeping during construction activity at the project site.

#### 5.1 Spill Prevention

The following measures are proposed to prevent pollutants from construction and waste materials stored on-site from entering stormwater. It outlines the necessary controls, preventive measures, and response strategies to manage spills effectively.

- Identification of Potential Spill Sources
  - o Site Assessment: Conduct a thorough assessment to identify areas where spills are likely to occur, such as storage locations for construction materials and waste.
  - o Inventory Management: Maintain an up-to-date inventory of all hazardous materials stored on-site, including their quantities and storage conditions.
- Preventive Measures
  - o Proper Storage:
    - Store materials in covered areas or containers to minimize exposure to stormwater.
    - Use weather-resistant and leak-proof containers for hazardous materials.
  - o Handling Procedures:
    - Implement safe handling procedures to reduce the risk of spills during transportation and use as specified by the manufacturer.
    - Ensure that all containers are properly labeled and secured.
- Containment Strategies
  - o Physical Barriers:
    - Install barriers such as berms or dikes around storage areas to contain spills and prevent them from spreading.
  - Secondary Containment:
    - Use spill pallets, containment sumps, or other secondary containment systems to capture any leaks or spills.
- Response Procedures
  - o Immediate Actions:
    - Ensure that spill kits are readily available next to all chemicals on-site.

#### o Notification Protocols:

• Notify the site supervisor or foreman of the spill immediately.

#### o Documentation:

- Keep detailed records of spill incidents, including the cause, response actions taken, and any follow-up measures.
- Conduct post-incident reviews to identify areas for improvement.

#### Training and Communication

- o Training Programs:
  - Conduct regular training sessions for all personnel on spill prevention and response protocols.
  - Include spill response drills to ensure readiness.

#### o Communication Channels:

- Maintain clear communication channels for reporting spills and coordinating response efforts.
- Emergency contact information and spill response procedures will be located around all chemicals.

#### • Implementation and Maintenance

- o Regular Inspections:
  - Perform regular inspections of storage areas and containment systems to ensure they are in good condition and functioning properly.
  - Address any deficiencies promptly.

### o Plan Updates:

 Review and update the spill prevention plan periodically to incorporate new information, changes in site conditions, or lessons learned from previous spill incidents.

#### o Emergency Drills:

 Conduct emergency drills to test the effectiveness of the spill response procedures and ensure personnel are prepared to handle real spill events.

### • Regulatory Compliance

- o Adherence to Regulations:
  - Ensure compliance with relevant regulations, such as the Spill Prevention, Control, and Countermeasure (SPCC) rule.

LUPC Received 7/1/2025

Stay informed about any changes in regulations and update the plan accordingly.

By developing and implementing these spill prevention guidelines, operators can effectively manage and mitigate the risks associated with spills, ensuring environmental protection and compliance with regulations.

Any spill or release of toxic or hazardous substances must be reported to the Department.

- For oil spills, call 1-800-482-0777 which is available 24 hours a day.
- For spills of toxic or hazardous material, call 1-800-452-4664 which is available 24 hours a day.
- For more information, visit the Department's website at: http://www.maine.gov/dep/spills/emergspillresp/

#### 5.2 Groundwater Protection

Liquid petroleum products and other hazardous materials with the potential to contaminate groundwater will not be handled or stored in areas of the site draining to an infiltration area. An "infiltration area" is any area of the site that by design or as a result of soils, topography, and other relevant factors accumulates runoff that infiltrates into the soil. Dikes, berms, sumps, and other forms of secondary containments that prevent discharge to groundwater as described in Section 5.1 of this Plan will be provided to isolate portions of the site for the purposes of storage and handling of these materials.

#### 5.3 Fugitive Sediment and Dust

Measures will be provided to ensure that activities do not result in noticeable erosion of soils or fugitive dust emissions during or after construction. Oil will not be used for dust control. If off-site tracking occurs, the roadway will be swept immediately and no less than once a week prior to significant stormwater event. Dust control methods shall entail:

- Stabilize all laydown areas and all unpaved surfaces with a base gravel or coarse gravel as soon as possible;
- Use traffic control to restrict speed and route;
- Water Application with frequent reapplication during warm sunny days will mitigate dust. The distribution of water should not cause turbid runoff; and
- Sweep and Vacuum paved road surface when dry. Sweep from the centerline to the edge of the travel way. Do not sweep into a waterbody or wetland.

The public roadway may also require sweeping.

5-3

#### 5.4 Debris and Other Materials

Construction waste will be contained in a dumpster and hauled off. Waste containers will be provided by the contractor on-site to collect the construction waste. Construction and demolition debris will be disposed of off-site by a commercial hauler. The construction debris will be hauled to a licensed landfill. Waste containers will prevent litter, construction debris, and chemicals exposed to stormwater from becoming a pollutant source.

#### 5.5 Excavation De-Watering

Water collected through excavation dewatering will be spread through natural wooded buffers or routed to a sedimentation basin. The water will not be allowed to flow over disturbed areas of the site. Dewatering water will be collected from the ponded area and disposed of in accordance with notes on Drawing C-300 and the drawings attached to this Plan.

#### 5.6 Vehicle and Equipment Washing

Equipment and vehicles will be washed outside of natural resources and out of the drainage patterns to the natural resource. The polluted water will be contained on-site in designated areas. No soaps, solvents, detergents or other cleaning solutions will be used on-site.

When washing applicators and containers for concrete applications, wash wastewater will be directed into a leak-proof lined pit. The washout area will not be located adjacent to site drainage features, storm inlets, and receiving waters in accordance with the drawings provided with this Plan.

#### 5.7 Authorized Non-Stormwater Discharges

Identify and prevent contamination by non-stormwater discharges. Where allowed non-stormwater discharges exist, they must be identified, and steps should be taken to ensure the implementation of appropriate pollution prevention measures for the non-stormwater component(s) of the discharge. Authorized non-stormwater discharges are:

- Discharges from firefighting activity;
- Fire hydrant flushing;
- Vehicle wash water if detergents are not used and washing is limited to the exterior of vehicles (engine, undercarriage and transmission washing is prohibited);
- Dust control runoff in accordance with permit conditions and Appendix (C)(3);
- Routine external building washdown, not including surface paint removal, that does not involve detergents;

- Pavement wash water (where spills/leaks of toxic or hazardous materials have not occurred unless all spilled material has been removed) if detergents are not used;
- Uncontaminated air conditioning or compressor condensate;
- Uncontaminated groundwater or spring water;
- Foundation or footer drain-water where flows are not contaminated;
- Uncontaminated excavation dewatering;
- Potable water sources including waterline flushing; and
- Landscape irrigation.

Allowable non-stormwater discharges cannot be authorized under this permit unless they are directly related to and originate from a construction site or dedicated support activity (e.g., a pressure washing company cannot broadly use this general permit for their business operations, because general vehicle washing is not associated with a construction site).

### 5.8 Unauthorized Non-Stormwater Discharges

The Department's approval under this Chapter does not authorize a discharge that is mixed with a source of non-stormwater, other than those discharges in compliance with MCGP Appendix C (7). Specifically, the Department's approval does not authorize discharges of the following:

- Wastewater from the washout or cleanout of concrete, stucco, paint, form release oils, curing compounds or other construction materials;
- Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance; and
- Soaps, solvents, or detergents used in vehicle and equipment washing.

### 5.9 Additional Requirements

There are no additional requirements specific to this project.

### **APPENDIX A**

### **INSPECTION CHECKLIST AND REPORT FORM**



### MAINE EROSION AND SEDIMENT CONTROL BMPs - 10/2016

EROSION AND SEDIMENT CONTROL MEASURES AND ACTIVITY	INSPECTION FREQUENCY				
	Weekly	Before and After a Storm	After Construction		
SEDIMENT BARRIERS					
Sediment barriers are installed prior to soil disturbances	Х	X			
Silt fences are keyed in and tight	Х	Х			
Barriers are repaired and replaced as necessary	Х	Х			
Barriers are removed when the site is stabilized - Silt			X		
fence should be cut at the ground surface					
TEMPORARY STABILIZATION	Ι	T	T		
Areas are stabilized if idle for 14 days or more	X	X			
Daily stabilization within 100 ft of a natural resource	<u> </u>	<u> </u>			
MULCH	I	ı	T		
Seed and mulch within 7 days of final grading. Ground is not visible	Х	Х			
Erosion control mix is 4-6 inch thick	Х	X			
Erosion control blankets or hay mulch are anchored	Х	Х			
VEGETATION					
Vegetation provides 90% soil cover	X		X		
Loam or soil amendment were provided	Х		X		
New seeded areas are mulched and protected from	χ	X	X		
vehicle, foot traffic and runoff	Λ		^		
Areas that will remain unworked for more than 1 year	X				
are vegetated with grass					
SLOPES AND EMBANKMENTS	T	1	T		
Final graded slopes and embankments are stabilized	Х	X	X		
Diversions are provided for areas with rill erosion	X	X	Х		
Areas steeper than 2:1 are riprapped	X				
Stones are angular, durable and various in size	Х				
Riprap is underlain with a gravel layer or filter fabric	Х				
STORMWATER CHANNELS AND CULVERTS		T	l		
Ditches and swales are permanently stabilized—	V		V		
channels that will be riprapped have been over-	Х	X	X		
excavated					
Ditches are clear of obstructions, accumulated sediments or debris	X	X	X		
	Х	Х	X		
Ditch lining/bottoms are free of erosion  Check dams are spaced correctly to slow flow velocity	X		^		
Underlying filter fabric or gravel is not visible	X	Х	X		
Culvert aprons and plunge pools are sized for			^		
expected flows volume and velocity	X				
Stones are angular, durable and various in size	Х				
Culverts are sized to avoid upgradient flooding	X	Χ			
Culvert protection extends to the maximum flow					
elevation within the ditch	X	X	X		
Culvert is embedded, not hanging	X	X	X		

### MAINE EROSION AND SEDIMENT CONTROL BMPs - 10/2016

CATCH BASIN SYSTEMS			
Catch basins are built properly	Х		
Accumulated sediments and debris are removed from		ν,	V
sump, grate and collection area		X	X
Floating debris and floating oils are removed from trap			Х
ROADWAYS AND PARKING SURFACES			
The gravel pad at the construction entrance is clear	V	V	
from sediments	X	X	
Roads are crowned		Х	Х
Cross drainage (culvert) is provided	Х		
False ditches (from winter sand) are graded		Х	Х
BUFFERS			
Buffers are free of erosion or concentrated flows		Х	Х
The downgradient of spreaders and turnouts is stable		Х	Х
Level spreaders are on the contour			Х
The number of spreaders and ditch turnouts is		V	V
adequate for flow distribution		X	X
Any sediment accumulation is removed from within		V	V
spreader or turnouts		X	X
STORMWATER BASINS AND TRAPS		·	
Embankments are free of settlement, slope erosion,		Х	Х
internal piping, and downstream swamping		^	^
All flow control structure or orifices are operational and		х	Х
clear of debris or sediments		^	^
Any pre-treatment structure that collects sediment or		x	Χ
hydrocarbons is clean or maintained		^	
Vegetated filters and infiltration basins have adequate			Χ
grass growth			
Any impoundment or forebay is free of sediment		X	X
WINTER CONSTRUCTION (November 1st-April15th)			
Final graded areas are mulched daily at twice the	Daily		
normal rate with hay, and anchor (not on snow)			
A double row of sediment barrier is provided for all	<b>.</b>		
areas within 100 ft of a sensitive resource (use erosion	Daily		
control mix on frozen ground)	D - 11		
Newly constructed ditches are riprapped	Daily		
Slopes greater than 8% are covered with an erosion	Daily		
control blanket or a 4-inch layer of erosion control mix	<u> </u>		
HOUSEKEEPING PUNCH LIST			
All disturbed areas are permanently stabilized, and			V
plantings are established (grass seeds have			X
germinated with 90% vegetative cover)			
All trash, sediments, debris or any solid waste have			X
been removed from stormwater channels, catch basins, detention structures, discharge points, etc.			^
All ESC devices have been removed: (silt fence and			
posts, diversions and sediment structures, etc.)			Χ
All deliverables (certifications, survey information, as-		-	
built plans, reports, notice of termination (NOT), etc.) in			
accordance with all permit requirements have been			Χ
submitted to town, Maine DEP, association, owner, etc.			
Capitation to town, maine DEI, association, owner, etc.			


### MAINE EROSION AND SEDIMENT CONTROL BMPs - 10/2016

CONSTRUCTION INSPECTION FORM FOR EROSION AND SEDIMENT CONTROL								
General Information:								
Site Name:	Date:		Inspect	ed by:				
Owner:								
Retained 3PI:	Last Rain Date:		ı	Amount:				
Reason for Inspection:	Weekly	Winter	Final	Rain Event	Complaint			
Description of disturbed area:								
Photos:								
	YES/NO/NA		C	OMMENTS				
1. Is an Erosion and Sediment Control Pla	n available?							
ESC plan on-site and followed								
Other:								
2. Are all erosion control practices installed	ed proper <mark>l</mark> y, ma	intained a	nd funct	i <mark>oning?</mark>				
Disturbed areas stable								
Concentrated flow inlet/outlet protection								
All areas at final grade								
Disturbed dormant areas stabilized								
Access roads and parking								
Hillsides and stockpiles								
Other:								
3. Are all sedimentation control practices	installed prope	rly, mainta	ained an	d functioning	?			
Construction entrance								
Sedimentation basins/traps/diversions								
Perimeter controls								
Check dams								
Other:								
4. Is maintenance of ESC measures, cons	truction activiti	es and ho	usekeep	ing kept-up?				
Sedimentation/erosion in ditches								
Tracked Sediment or dust at exits								
Hazardous material storage and spill control practices								
Waste management (concrete, hazardous material, etc.)								
Other:								
5. Violation, Corrective Actions, Recommo	endations	1						
Sediment discharged from site?								
Corrective action required?								
Site compliant with all permits?								
Notice of violation or stop work order issued?								
Comments/Corrective Actions (complete corr	rective actions be	efore the n	ext rain e	event and withi	n 7 day)			


### **APPENDIX B**

DRAWINGS: C-101 THROUGH 104 AND C-300







Phonometrial committee in spectrated from the SCS and COSCS COSCS COSCS (SCSCS) and



Phonyect Bennete Enach petrus Perside \$4.5 E.U. \$505 Mg. (170), 600005 17 EU. (n)



enveloplescontellites Asjectical Parklatis LTL (2005 eng. C-10), 600005 12 ST 13 PU, qn.



Interved this example from A gest standing late \$4.55.101, \$50,0 erg, C-101, \$90,005 12 STS PU, you

SILT FENCE FABRIC

#### EROSION CONTROL NOTES:

#### A. GENERAL

- All soil erosion and sediment control will be done in accordance with: (1) the Maine Erosion and Sediment Control Handbook: Best Management Practices, Maine Department of Environmental Protection (MEDEP), October 2016.
- The site Contractor (to be determined) will be responsible for the inspection and repair/replacement/maintenance of all erosion control measures, disturbed areas, material storage areas, and vehicle access points until all disturbed areas are stabilized.
- Disturbed areas will be permanently stablized within 7 days of final grading. Disturbed areas not to be worked upon within 14 days of disturbance will be temporarily stabilized within 7 days of the disturbance.
- In all areas, removal of trees, bushes and other vegetation, as well as disturbance of topsol will be kept to a minimum while allowing proper site operations.
- 5. Any suitable topsoil will be stripped and stocipied for reuse as directed by the Owner, Toppid will be stocipied in a manner such that notural drainage is not obstructed and within 100 feet of welfands and will be all leads 50 feet upgedient of the stocipied is perimeter all fence. The sideslapes of the toppid stocipied will not exceed 2.1. Sit fence will be initialled around the perimeter of all toppid stocipies. Toppid stocipies from well be initialled around the perimeter of all toppid stocipies. Toppid stocipies force will be initialled around the perimeter of all toppid stocipies. Toppid stocipies force will be initialled around the perimeter of all toppid stocipies. Toppid stocipies force will be initialled around the perimeter of all toppid stocipies. Toppid stocipies force will be stocipied to the perimeter of all toppid stocipies. will be surrounded with sitation fencing and will be temporarily seeded with Aroostook rye, annual or perennial ryegrass within 7 days of formation, or temporarily mulched.
- 6. Winter excavation and earthwork will be completed so as to minimize exposed areas Winter excavation and earthwork will be completed so as to minimize exposed areas while satisfactory completing the project. Limit exposed areas to those areas in which work is to occur during the following 15 days and that can be mulched in one day. All areas will be considered denueld until the subbase gravel is installed in roadway areas or the areas of future tarm and seed have been loamed, seeded, and mulched.

Install any added measures necessary to control erosion/sedimentation. The particular measure used will be dependent upon site conditions, the size of the area to be protected, and weather conditions.

To minimize areas without erosion control protection, continuation of earthwork operations on additional areas will not begin until the exposed soil surface on the area being worked has been stabilized.

#### B. TEMPORARY MEASURES

#### 1. STABILIZED CONSTRUCTION ENTRANCE/EXIT

A crushed stone stabilized construction entrance/exit will be placed at any point of vehicular access to the site, in accordance with the detail shown on this sheet.

- Silt fence will be installed prior to all construction activity, where soil disturbance may result in erosion. Silt fence will be erected at locations shown on the plans and/or downgradient of all construction activity.
- Silt fences will be removed when they have served their useful purpose, but not before the upgradient areas have been permanently stabilized.
- c. Silt fences will be inspected immediately after each rainfall and at least daily during prolonged rainfall. They will be inspected if there are any signs of erosion or sedimentation below them. Any required repairs will be made immediately. If there are signs of undercotting at the center or the edges, or impounding of large volumes of water belind them, they will be replaced with a temporary crustled storce check.
- d. Sediment deposits will be removed after each storm event if significant build-up has occurred or if deposits exceed half the height of the barrier.

Stone check dams will be installed in grass-lined swales and ditches during construct Remove stone check dams when they have served their useful purpose, but not befor upgradient areas have been permanently stabilized.

#### 4. EROSION CONTROL MIX SEDIMENT BARRIER

- Where approved, erosion control mix sediment barriers may be used as a substitute for silt fence. See the details in this drawing set for specifications.
- B. Rock Fifter Berms: To provide more filtering capacity or to act as a velocity check dam, a berm's center can be composed of clean crushed rock ranging in size from the french drain stone to riprap.

#### 5. TEMPORARY SEEDING

Stabilize disturbed areas that will not be brought to final grade and reduce problems associated with mud and dust production from exposed soil surface during construction with temporary vegetation.

#### 6 TEMPORARY MULCHING

Use temporary mulch in the following locations and/or circumstances:

- In sensitive areas (within 100 feet of streams, wetlands and in lake watersheds) temporary mulch will be applied within 7 days of exposing spill or prior to any.
- Apply temporary mulch within 14 days of disturbance or prior to any storm event. Apply templace y unsur-monatory templace in all other area been temporarily or permanently seeded will be mulched immediately following seeding.
   American which have been temporarily or permanently seeded will be mulched for over-winter protection and the area will be seeded at the beginning of the

- growing season.

  Mulch can be used in conjunction with tree, shrub, vine, and ground cover
- plantings.

  Much anchoring will be used on slopes greater than 5 percent in late fall (past October 15), and over-winter (October 15 April 15).

#### The following materials may be used for temporary mulch:

- Hay or Straw material shall be air-dried, free of seeds and coarse material. Apply 2 bales/1,000 sf or 1.5 to 2 tons/acre to cover 90% of ground surface.
- B. Erosion Control Mix: It can be used as a stand-alone reinforcement:
   on slopes 2 horizontal to 1 vertical or less;
   on frozen ground or forested areas; and
   at the edge of gravel parking areas and areas under construction.
- c. Erosion control mix alone is not suitable:
- troson control mix alone is not suitable:
  on alopse with groundwater seepage;
  at low points with concentrated flaws and in guilles;
  at the bottom of steep permitted sopes exceeding 100 feet in length;
  below culvert outlet aprons; and around catch basins and dosed storm systems.
- d. Chemical Mulches and Soil Binders: Wide ranges of synthetic spray-on materials are marketed to protect the soil surface. These are emulsions that are mixed with water and applied to the Soil. They may be used alone, but most often are used to hold wood fiber, hydro-mulches or state to the soil surface.

- Erosion Control Blankets and Mats: Mats are manufactured combinations of mulch
  and netting designed to retain soil moisture and modify soil temperature. During th
  growing season (April 15 to October 15) use mats indicated on drawings or North
  American Green (NAG) 575 (or mulch and netting) on:
- the base of grassed waterways:
- steep slopes (15 percent or greater); and any disturbed soil within 100 feet of lakes, streams, or wetlands.

During the late fall and winter (October 15 to April 15) use heavy grade mats indicated on drawings for all areas.

To prevent the blowing and movement of dust from exposed soil surfaces, and reduce the presence of dust, use water or calcium chloride to control dusting by preserving the moisture level in the road surface materials.

- Water from construction de-watering operations shall be deaned of sediment before reaching wetlands, water bodies, streams or site boundaries, Utilize temporary sedime basins, erosion control soil filter berms backed by staked hay bales, A Dirt Bag SS' sediment filter bag by ACF Environmental, or other approved Best Management.
- In sensitive areas near streams or ponds, discharge the water from the de-watering operation into a temporary sediment beam created by a surrounding filter berin of details). Lossed the temporary sediment beam elabes of lose from the nearest water body, such that the efficient water will flow through undisturbed vegetated soil areas prior to neaching the water body or property line.

#### E DERMANENT MEASURES

- 1. Riprapped Aprons: All storm drain pipe outlets and the inlet and outlet of culverts will have riprap aprons to protect against scour and deterioration.
- Topsoil, Seed, and Mulch: All areas disturbed during construction, but not subject to other restoration (paving, riprap, etc.) will be barned, limed, ferblized, seeded, and mulched.

Seeded Preparation: Use stockpiled materials spread to the depths shown on the plans, if available. Approved topsoil substitutes may be used. Grade the site as needed.

a. Seeding will be completed by August 15 of each year. Late season seeding may be done between August 15 and October 15. Areas not seeded or which do not obtain satisfactory growth by October 15, will be seeded with Arosotock Rye or mulched. After November 1, or the first killing frost, disturbed areas will be seeded at double the specified application rates, mulched, and anchoral.

#### PERMANENT SEEDING SPECIFICATIONS

Mixture:	(lbs/acre)	(lbs/acre)
Kentucky Buegrass	20	55
White Cover	5	0
Creeping Red Fescue	20	55
Perennial Ryegrass	5	15

- b. Mulch in accordance with specifications for temporary mulching.
- If permanent vegetated stabilization cannot be established due to the season of the year, all exposed and disturbed areas not to undergo further disturbance are to have dormant seeding applied and be temporarily muched to protect the site.
- d. Any fertilizer used on the site to be free of phosphorous.
- Ditches and Channels: All ditches on-site will be lined with North American Green P30 erosion control mesh (or an approved equal) upon installation of loam and seed unless.
- F. WINTER CONSTRUCTION AND STABILIZATION
- Natural Resource Protection: During winter construction, a double-row of sediment barriers (i.e., six fence backed with hay bales or erosion control mic) will be placed between any natural resource and the disturbed area. Projects crossing the natural resource will be protected a minimum distance of 100 feet on either side from the
- Sediment Barriers: During frozen conditions, sediment barriers may consist of erosion control mix berms or any other recognized sediment barriers as frozen soil prevents the proper installation of his bales or slit fences.

#### 3 Mulching

- All areas will be considered to be denuded until seeded and mulched. Hay and straw mulch will be applied at a rate of two to the normal accepted rate. Mulch will not be spread on top of small per penty and to the control of the contr
- 5. Soil Stockpiling: Stockpiles of soil or subsoil will be mulched for over-winter protection Soil shotspiles; stockples of soil or subsoil will be another for over-writer protection with an expensive stockples of the control of the co
- 6. Seeding: Dormant seeding may be placed prior to the placement of mulch or erosion control almosts. If dommant seeding is used for the site, all daturbed areas will receive seeding. All areas seeded during the writer vill be imposed on the spring for adequate catch. All areas insufficiently vegetated (less than 75 percent catch) will be revergetated by relating learn, seed, and mulch.

If dormant seeding is not used for the site, all disturbed areas will be revegetated in the spring.

- Maintenance: Maintenance measures will be applied as needed during the entire
  construction season. After each rainfall, snow storm, or period of thawing and run
  and at least once a week; the site Contractor will perform a visual inspection of all
  installed eroxion; control measures and perform repairs as needed to ensure their
- Identified repairs will be started no later than the end of the net work day and be completed within seven (7) relander days.

Following the temporary and/or final seeding and mulching, the Contractor will, in the spring, inspect and repair any damages and/or bare spots. An established vegetative cover means a minimum of 85 to 90 percent of areas vegetated with vigorous growth

#### G. OVER-WINTER CONSTRUCTION EROSION CONTROL MEASURES.

1. Stabilization of Disturbed Soil: By October 15, all disturbed soils on areas having a slope less than 15 percent will be seeded and mulched. If the Contractor fails to stabilize these soils by this date, then the Contractor shall stabilize the soil for late fall and winter, by using either temporary seeding or mulching.

- Stabilization of Disturbed Slopes: All slopes to be vegetated will be completed by October 15. The Owner will consider any area having a grade greater than 15 perces (6.5%:10) to be a slope. Slopes not vegetated by October 15 will receive one of the following actions to stabilize the slope for late fall and winter:
- Stabilize the soil with temporary vegetation and erosion control mesh.
   Stabilize the slope with erosion control mix.
   Stabilize the slope with stone riprap.
   Stabilize the slope with stone riprap.

- 3. Stabilization of Ditches and Channels: All stone-lined ditches and channels to be used to convey runoff through the winter will be constructed and stabilized by November 15.

  Grass-lined ditches and channels will be complete by September 15. Grass-lined ditches not stabilized by September 15 shall be lined with either sod or riprap.

Routine Maintenance: Inspection will be performed as outlined in the project's Erosion Control Flan. Inspection will be by a qualified person during wat weather to ensure that the facility performs as intended. Inspection priorities will include checking erosion controls for accumulation of addiments.

- Splil prevention. Controls must be used to prevent pollutants from being discharged from materials on site, including storage practices to minimize exposure of the mater to stormwater, and appropriate splil prevention, containment, and response planning and implementation.
- 2. Groundsate protection, During construction, faind settleture modulate and other hearance on metals with the potential to contaminate groundwater may not be stored or handled in areas of the site dishing to an infiliation or area. An "infiliation area" is any size of the site that by design or a set and if seek, longitively and other redesignment and the size of the proposed of size and shading of these metals of the size for the proposed of storage and handling of these metals.
- Fugitive sediment and dust. Actions must be taken to ensure that activities do not result in noticeable erosion of soils or fugitive dust emissions during or after construction. Oil may not be used for dust control. If offerthe tracking occurs readways should be awept immediately and no loss once a week and prior to significant some events.
- Debris and other materials. Litter, construction debris, and chemicals exposed to stormwater must be prevented from becoming a pollutant source.
- 5. Trench or foundation de-watering. Trench de-watering is the removal of water from the control of the cont
- Authorized Non-stormwater discharges. Identify and prevent contamination by non-stormwater discharges. Where allowed non-stormwater discharges exist, they must be identified and steps should be taken to ensure the implementation of appropriate pollution prevention measures for the non-stormwater component(s) of the discharge. n prevention measures for the non-s ized non-stormwater discharges are:
- (a) Discharges from firefighting activity:
- (c) Vehicle washwater if detergents are not used and washing is limited to the exterior of vehicles (engine, undercarriage and transmission washing is prohibited);
- (d) Dust control runoff in accordance with permit conditions and section 13
- (e) Routine external building washdown, not including surface paint removal, that does
- (f) Pavement washwater (where spills/leaks of toxic or hazardous materials have not occurred, unless all spilled material had been removed) if detergents are not used;
- (a) Uncontaminated air conditioning or compressor condensate:
- (h) Uncontaminated groundwater or spring water:
- (i) Foundation or footer drain-water where flows are not contaminated
- (i) Uncontaminated excavation dewatering (see requirements in section IS):
- (k) Potable water sources including waterline flushings; and
- Unauthorized non-stormwater discharges. The Department's approval under this
  Chapter does not authorize a discharge that is mixed with a source of non stormwater,
  other than those discharges in complance with section IS. Specifically, the Department's
  approval does not authorize discharges of the following:
- a) Wastewater from the washout or cleanout of concrete, stucco, paint, form release oils, curing compounds or other construction materials;
- (b) Fuels, oils or other pollutants used in vehicle and equipment operation and
- (c) Soaps, solvents, or detergents used in vehicle and equipment washing; and
- (d) Toxic or hazardous substances from a spill or other release.
- 8. Additional requirements. Additional requirements may be applied on a site-specific basis

#### J. CONSTRUCTION SEQUENCE

In general, the expected sequence of construction for each phase is provided below. Construction is proposed to start in Summer 2025 and end in Winter 2026.

- Mobilization
- nstall temporary erosion control measures

- Install temporary erosion control measures
   Clearing and grubbing as necessary
   Install overhead utility poles
   Excavate trench and install electrical utilities
   Backfill and compact trench
   Site stabilization, loam and seed as necessary
   Remove temporary erosion control measures



#### EROSION CONTROL MIX SEDIMENT BARRIER

BOSION CONTROL REX OW RE HAME/RCTURED ON OR OFF THE SITL. IT MUST CONSIST PREMARED OF ORGANIC MATERIAL SEPARATIO AT THE POINT THE STREET, AND THAT REQUESTED RESPONSE THE POINT OF THE POINT THE STREET OF THE POINT OF THE POINT OF THE POINT OF THE STREET POINT OF THE POINT OF THE STREET OF THE POINT OF THE POINT OF THE STREET OF THE POINT OF THE PO

THE NATION POSTITION SHALL HEET THE FOLLOWING STANDARDS.

THE NATION STANDARDS.

B. PARTICLE SIZE BY WIGHT, 1,00% PASSING BY SCREEP, TO-BYN PASSING GAT'S SCREEN.

C. THIS COMMUNICATION FAIR TO BE REFINED, AND EDUCATION FAIR TO SCREEN.


D. LAKES FOR THIS COLUMN STANDARD OF BROADS AND ENGINE ACTOR STANDARD OF BROADS.

D. LAKES FOR THE STANDARD SEET THAN A GRAND ACTOR FAIR IN THE MID.


F. PR. S.A. D. G. CONTROL SHALL BE SEET THAN A GRAND-COLUMN STANDARD OF BROADS.

- ON SLOPES LESS THAN 5W OR AT THE BOTTOM OF SLOPES 2:1 OR LESS UP TO 20 FEET LONG, THE BARRIER MUST CONFORM TO THE ABOVE DIMENSIONS. ON THE LONGER OR STEEPER SLOPES, THE BARRIER SHOULD BE WIDER TO ACCOMMODATE THE ADDITIONAL PLOW.
- THE BARRIER MUST BE PLACED ALONG A RELATIVELY LEVEL ELEVATION, IT MAY BE RECESSARY TO CUT TALL GRASSES OR WOODY VEGETATION TO AVOID
  CREATING VOIDS AND BRIDGES THAT WOULD BHABLE FINES TO WASH UNDER THE BARRIER THROUGH THE GRASS BLADES OR PLANT STEMS.

- 4. LOCATION WHERE OTHER IMPS SHOULD BE USED:
  A 11 LOW FORITS OF CONCENTRATION FOR
  A 11 LOW FORITS OF CONCENTRATION FOR
  C MINERAL PROVINGS STREAM-LONG BESCADE CONTICEL, MEX. APPLICATION HAS PAULD
  D. AT THE BOTTOM OF SIZE PREMIETES ACKIPS THAT ARE MORE THAN 50 FIRST FROM TOP TO BOTTOM (LARGE UPGRAGENT WATERSHED
  D. AT THE BOTTOM HOSE FOR CALLEGES FOR THOM TO PROVING THE PROVING THE PROVINCE OF THE
- 5. THE EROSION CONTROL MIX BARRIERS SHOULD BE INSPECTED REGULARLY AND AFTER EACH LARGE RAINFALL REPAIR ALL DAMAGED SECTIONS OF BERM INNEDIATELY BY REPLACING OR ADDING ADDITIONAL NATERIAL REACH ON THE BERN TO THE DESIRED HEIGHT AND WIDTH.
- 6. IT MAY BE NECESSARY TO REINFORCE THE BARRIER WITH SILT FENCE OR STONE CHECK DAMS IF THERE ARE SIGNS OF UNDERCUTTING OR THE IMPOUNDMENT OF LARGE VOLUMES OF WATER.
- 7. SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER
- REPLACE SECTIONS OF BERM THAT DECOMPOSE, SECONE CLOGGED WITH SEDIMENT OR OTHERWISE SECONE INEFFECTIVE. THE BARRIER SHOULD BE RESIMPED AS INSERED. EROSION CONTROL MIX BARRIERS CAN BE LEFT IN PLACE AFTER CONSTRUCTION. ANY SECIMENT DEPOSITS REMAINING IN PLACE AFTER BARRIER IS NO LONGER REQUIRED SHOULD BE SPREAD TO CONFORM TO THE ESTITING GRADE AND BE SECRED MICH LICHED WOODY VEGETATION CAN BE PLANTED INTO HE BARRIERS, OR THEY CAN BE OFFISEDED WITH LIGHTINGS, IF THE BARRIER NEDS TO BE REMOVED, IT CAN BE FRAIGHD LITTLE NUMBOURS.
- 10. IF TEMPORARY BERMS ARE USED AS SILT BARRIERS, THEY ARE PROHIBITED AT THE BASE OF SLOPES STEEPER THAN 8% OR WHERE THERE IS FLOWING WATTR WITHOUT THE SUPPORT OF ADDITIONAL MINASURES SUCH AS SILT FIRECE.



SURFACE DRAINAGE SEDIMENT CONTROL




- 1. LOCATE SOIL STOCKPILLS AS FAR FROM PROTECTED RESOURCES AS POSSIBLE (PONDS, RIVERS, STOCKPILLS AS FAR FROM PROTECTED RESOURCES AND FROM AREAS OF CONCENTRATED STREAMS, BOCOS, & NETLANDS, LOCATE SOIL STOCKPILS AND FROM AREAS OF CONCENTRATED.

  5. FROM STANDARD AREAS (SLIT FROM EACH OF LOCATED AND EACH OF STOCKPILS AND SEASON OF MALL TEST AND ALL THE CHARGE AND EACH OF LOCATED CANNEL AND EACH OR LOCATED CANNEL AND EACH O PREMARENT SEED (< 990 VEGETATED), EROSON CONTRO, BILANET OR BROSON CONTRO, MY, BEGGOON CORTION, MY CAN DE MANIBLE/TURED ON 100 OF THE ST. IT, MIST COSSIST PRIMARILY OF DIGGOON CHAPTER) ASSISTANT AT THE POINT OF GREWATION, AND MAY INCLUDE: SHEEZED FROM WATER-LIME (LICE OF LICE OF LIC

  - 0.75' SCREEN.
    C. THE ORGANIC PORTION NEEDS TO BE FIBROUS AND ELONGATED.
    D. LARGE PORTIONS OF SILTS, CLAYS OR FINE SANDS ARE NOT ACCEPTABLE
- IN THE MIX.

  E. SOLUBLE SALTS CONTENT SHALL BE LESS THAN 4.0 MMHOS/CM.


  F. PH: 5.0 8.0.



NOTES:

1. FILTER SOCK SHALL BE 12' DIAMETER MIN
2. SOCKS TO BE FILLED WITH BLODEGWADABLE COMPOST MATERIAL.
3. WOODER STAKES SHALL BE PLACED DOWNSLOPE OF THE FILTER SOCK IN AN X-SHAPE PATTERN.

SILT SOCK



MAINTAIN ENTRANCE IN A CONDITION THAT WILL PREVENT TRACKING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAY, IF WASHING IS REQUIRED PREVEI SEDIMENT FROM ENTERING WATERWAYS, DITCHES OR STORM DRAINS.

2. REMOVE STABILIZED CONSTRUCTION ENTRANCE TO FINISH ROAD

STABILIZED CONSTRUCTION ENTRANCE

REV. BY DATE STATUS BURNT JACKET HOLDING I. LLC UTILITY EXTENSION BEAVER COVE, MAINE

**EROSION CONTROL NOTES AND DETAILS** 

DESIGN BY: AID SME DRAWN BY: SJM SEVEE & MAHEI ENGINEERS DATE: 5/2025 AL . CIVIL. GEOTECHNICAL . WATER . COMPLIANO CHECKED BY: DPD 4 Blanchard Road, PO Box BSA, Cumberland, Maine 04021 Phone 207,829,5016 ◆ Fax. 207,829,5692 ◆ sme-engineers.com LMN: NONE

JOB NO. 231136 DWG FILE DETAILS-HTFI C-300

### **EXHIBIT 26 - WILDLIFE PASSAGE:**

The project will not impact existing stream or wetland crossings along Burnt Jacket Road. No wetland or vernal pool impacts are anticipated from construction of the project.

### **EXHIBIT 27 - SITE ACCESS:**

The project will be accessed off of Lily Bay Road.

The proposed utility line extension will follow Burnt Jacket Road for approximately 12,711 feet (i.e. +/- 60 feet above ground; and +/- 12,651 feet below ground). Burnt Jacket Road is a private road located entirely on the applicant's property. The remaining portion of the extension branches off Burnt Jacket Road and runs for an additional 4,004 feet through the applicants property along the proposed private road (refer to the Non-residential Permit RP-3313 issued on 6/25/2025). The applicant's property has historically been used as commercial timberlands, and Burnt Jacket Road was established as, and continues to be used as a gravel land management road. Portions of Burnt Jacket Road are maintained by a road association, Allagash Burnt Jacket Road Association, whose members are owners of properties that are accessed from Lily Bay Road, over Burnt Jacket Road and Allagash Road.

The project is discussed in Exhibit 17 above. The proposed project involves CMP's installation of poles and wires within approximately 60 feet of Lily Bay Road, adjacent to Burnt Jacket Road, to bring power into the property and construction of an approximately 12,651-foot long, 3-foot wide, underground utility line extension to provide power and communications services to a few residential and land management structures. The utility line extension will follow Burnt Jacket Road which is a privately owned and maintained gravel road. The extension will then branch off of Burnt Jacket Road, and follow the proposed private road through the applicant's property (see the Non-residential Permit RP-3313 issued on 6/25/2025).

Blasting may be required for construction of portions of the trench. The contractor selected for any necessary blasting will prepare and submit a blasting plan for approval prior to the start of blasting.

The proposed private underground utility line extension will be maintained by the applicant.

The project is located on a 1,423.5-acre forested lot within the direct watershed of Moosehead Lake. The lake is larger than 10 acres and is not At Risk for New Development or Severely Blooming. The project will create a disturbed area of more than one acre and is therefore required to consider phosphorous control. Using the Maine DEP Phosphorous Control Manual, the Project Phosphorous Budget (PPB) for the lot is 41.22 lbs P/year. The parcel size exceeds the Small Watershed Threshold (SWT) for Moosehead Lake and the PPB has been reduced accordingly. Coefficients for Greenville, ME were used for this calculation as none are given for Beaver Cove.

The disturbance area for the utility extension will be primarily within the limits of the existing gravel road and will not create any additional impervious area. In the areas of work beyond the road edge, disturbed vegetation will be allowed to regrow naturally post-construction and will not be landscaped. The utility extension project will not result in any new surface cover which contributes to phosphorous runoff. The pre-treatment Project Phosphorous Export (PPE) for the driveway project previously permitted on the same lot was calculated to be 10.79 lbs P/year. This includes all existing roads constructed on the lot after 1997 plus the proposed driveway and its associated landscaping. The PPE is well below the PPB, and as a result no treatment for phosphorous was required. PPB and PPE worksheets are included in Exhibit 30.

Ibs P/year

Worksheet 1 - PPB calculations								
Project Name: Beaconsfield Farm								
Lake Watershed: Moosehead Lake								
Town: Beaver Cove								
Standard Calculations								
Watershed per acre phosphorus budget (Appendix C)	PAPB	0.074	lbs P/acre/year					
Total acreage of development parcel:	TA	1423.5	acres					
NWI wetland acreage:	WA	85	acres					
Steep slope acreage:	SA	191.9	acres					
Project acreage: A = TA - (WA+ SA )	Α	1146.6	acres					
Project Phosphorus Budget: PPB = P x A	PPB	84.8484	lbs P/year					
Small Watershed Adjustment								
If Project Acreage (A) is greater than the threshold acreage for the spertinent lake and town info in the table in Appendix C), calculate ar and use this value if it is less than the the Standard Calculation PPE	alternativ							
Small Watershed Threshold (Appendix C):	SWT	416	acres					
Project acreage:	Α	1146.6	acres					
Allowable increase in town's share of annual phosphorus load to lake (Appendix C):	FC	122.63	lbs P/year					
Area available for development (Appendix C):	AAD	6654	acres					
Ratio of A to AAD (R=A/AAD)	R	0.172						
Project Phosphorus Budget								
If R < 0.5, PPB = [(FC x R)/2] + [FC/4]	PPB	41.223	lbs P/year					
	1							

If R> 0.5,

 $PPB = FC \times R$ 

PPB

21.131

1-15-09

## Worksheet 2 Pre-PPE and Post-PPE Calculations

Calculate phosphorus export from development for before and after treatment
Use as many sheets as needed for each development type (commercial, roads, residential lots, etc.)

Project name: Beaconsfield Farm Development type: \_\_\_\_\_ Sheet # \_\_\_\_

Land Surface Type or Lot #(s) with description	Acres or # of lots	Export Coefficient from Table 3.1 Table 3.2	Pre- treatment Algal Av. P Export (Ibs P/year)	Treatment Factor for BMP(s) from Chapter 6	Post- treatment Algal Av. P Export (Ibs P/year)	Description of BMPs
Driveway	1.98	1.75	3.465	1	3.465	
Landscaping	2.51	0.8	2.008	1	2.008	
Existing Roads (Post-1997)	3.04	1.75	5.32	1	5.32	
			0	1	0	
			0	1	0	
			0	1	0	
			0	1	0	
			0	1	0	
			0	1	0	
			0	1	0	
		Total Pre-PPE (Ibs P/year)	10.793	Total PostPPE (Ibs P/year)	10.793	

### Appendix D: Worksheet 3 - Mitigation credit

Project name: Beaconsfield Farm Project Development type: Driveway Sheet # 3 of 4

### Mitigation credit when a pre-existing source is being eliminated

Mitigation Source Area Land Use	Acres	Export Coefficient (lbs P/acre/year)	Modifier	Pre- treatment Historical P Export (lbs P/year)	Treatment Factor for Historical BMP(s) (1.0 if no BMPs)	Historical P Export (lbs P/year)		Mitigation Credit (lbs P/year)	Comments
			0.5	0	1	0		0	
			0.5	0	1	0		0	
			0.5	0	1	0		0	
			Total	source eliminatio	on mitiagion c	redit (SEC)	0	Ibs P/year	

### Mitigation credit when a pre-existing source is treated by a new BMP

Mitigation Source Area Land Use	Acres	Export Coefficient (lbs P/acre/year)	Modifier	Pre- treatment Historical P Export (lbs P/year)	Treatment Factor for Historical BMP(s) (1.0 if no BMPs)	Historical P Export (lbs P/year)		Treatment Factor for New BMP(s) Chapter 6	Mitigation Credit (lbs P/year)	Comments
			0.5	0	1	0	1 -		0	
			0.5	0	1	0	1 -		0	
			0.5	0	1	0	1 -		0	

Total source treatment mitiagion credit (STC) 0 lbs P/year

TOTAL MITIGATION CREDIT (SEC + STC) 0 lbs P/year

WORKSHEET 4 - PROJECT PHOSPHORUS EXPORT SUMMARY								
Summarizing the project's algal available phosphorus export (PPE)								
Project Name: Beaconsfield Farm								
Project Phosphorus Budget - Worksheet 1	PPB	41.22	lbs P/year					
Total Pre-Treatment Phosphorus Export - Worksheet 2	Pre-PPE	10.79	lbs P/year					
Total Post-Treatment Phosphorus Export - Worksheet 2	Post-PPE	10.79	lbs P/year					
Total Phosphorus Mitigation Credit - Worksheet 3	TMC	0.00	lbs P/year					
Project Phosphorus Export (Post-PPE - TMC)	PPE	10.79	lbs P/year					
Is the Project Phosphorus Export ≤ the Project Phospho	rus Budge	et? (PPE≤I	PPB)					
If <b>YES</b> , PPE is less than or equal to PPB and the project meets its phosphorus budget. If <b>NO</b> , PPE is greater than PPB, more reduction in phosphorus exrequired or the payment of a compensation fee may be an option	YES							
The amount of phosphorus that needs further treatment or compen	sation	0 lbs P/year						
Has Project Phosphorus Export been sufficiently reduce Is (Pre-PPE - Post-PPE)/Pre-PPE greater than 0.60?	d?							
If <b>YES</b> , in some watersheds the compensation fee is an available of <b>NO</b> , more treatment must be provided. PPE must be further redu	•	N/A						
The post-treatment phosphorus export must be less than 40% of the treatment export (Post-PPE < 0.4*Pre-PPE)	e pre-	N/A						
If the project is located in a watershed that is eligible for a compensation fee (or is a residential subdivision with buffers), a compensation fee may be appropriate as follows:								
If Project Export has been reduced by greater than 60% and less than 75%, \$25,000 per pound minus \$833 per 1% Percent Export								
If Project Export has been reduced by greater than 75%, \$12,500 pminus \$500 per 1% Project Export	er pound	N	/A					