

Total Bid \$ 8,479.00

Weston, Tracy

From: eastcoastx@aol.com
Sent: Tuesday, November 23, 2010 4:31 PM
To: Weston, Tracy
Subject: Re: Hooper Sands, BID
Attachments: Q 10-23.xls

Dear Tracy,
Attached please find the Bid requested for the Hooper Sands Well Abandonment Project.
Thank You for asking East Coast Explorations for a Bid on your project
Chris Palmer

-----Original Message-----

From: Weston, Tracy <Tracy.Weston@maine.gov>
To: eastcoastx@aol.com
Sent: Tue, Nov 23, 2010 9:13 am
Subject: Hooper Sands, Berwick, logs

Tracy Weston Kelly
ME Dept. of Environmental Protection
Division of Remediation
207-287-4862

Great Works Test Boring Inc

PO Box 491

Rollinsford, NH 03869

Estimate

Date

11/29/2010

Name / Address

MDEP

Attn: Tracy Weston Kelly

State House Station 17

Augusta, ME 04333

Terms

2% 10 ~ Net 30

Qty	Description	Cost	Total
2,000	<p>Hooper Sands Road Site - South Berwick, ME - Well Abandonment</p> <p>Abandon Existing Monitoring Wells In Place - [Remove Protective Casing; Cut PVC to 2'± BGS; Tremie Grout or Bentonite Chip Wells (within ME DEP guidelines) to 18" BGS; Sand to Surface; Restore to Existing Condition] * Complete Abandonment Reports & Submit</p> <p>Well Abandonment * Estimated Quantity From Logs as Submitted Equipment * Labor * Materials</p> <p>Estimated Prices To Remain Valid For A Period of One Hundred Twenty (120) Days GREAT WORKS would be available to begin work within 10 Days of acceptance of this estimate and awarding of the contract to complete the work.</p>	10.00	20,000.00
Hooper Sands Road Site - South Berwick, ME * Well Abandonment Attn Tracy Weston Kelly		Total	\$20,000.00

Phone #

Fax #

603-750-8006

207-698-1954

Weston, Tracy

From: Cheryl [Hilton@hughes.net]
Sent: Monday, November 29, 2010 3:38 PM
To: Weston, Tracy
Subject: Estimate from Great Works Test Boring Inc

Attachments: Est_112210SB_from_Great_Wor.pdf



Est_112210SB_fro
m_Great_Wor.pd...

Tracy,

Please review the attached estimate.

The cost as shown is by the foot and the total cost will be adjusted by the total amount of footage of the existing wells.

Feel free to contact us if you have any questions.

We look forward to working with you.

Sincerely,

Cheryl Dionne

Great Works Test Boring Inc
207-384-2546

Weston, Tracy

From: Brian Fons [bfons@envprojects.com]
Sent: Wednesday, December 01, 2010 3:26 PM
To: Weston, Tracy
Cc: probe@envprojects.com
Subject: EPI Quote for Hooper Sands Well Grouting

Hi Tracy,

Thank you for inviting us to submit a proposal for the Hooper Sands well grouting project. We reviewed everything that you sent over and prepared a cost estimate for you. Our proposal is based upon using chips for shallow wells <50' and a tremmie pipe/neat cement grout process for everything else. We do not have the in-house capability to over-drill wells to remove them so we have not included that in our cost. If the Department finds that it is necessary, we would use Northern Test Boring and mark them up 10% in accordance with our DEP contract. Since data isn't provided for every well, we have assumed that the average depth of 50' per well x 50 wells applies in estimating our total cost.

Mobilization \$2,500.00

Wells Abandoned by Chips and Rodding – Est. 500' x 5.00/foot = \$2,500.00

Wells Abandoned by Tremmied Grout – Est. 2000' x 9.00/foot = \$18,000.00

Estimated Total Cost \$23,000.00

- We have assumed that Enviroplug Medium or equivalent chips are acceptable to the Department
- We have assumed that no roads need to be cut in or clearing done to access each well.
- Brush clearing will be charged at \$125.00/hour (2 men and equipment).
- \$100 per well will be charged for EACH well we have to locate that doesn't require grouting.
- DEP to obtain landowner access for each site.

If you have any questions, please feel free to contact Dave Dionne or myself at 786-7390. Thank you,

Brian

Brian Fons
Environmental Projects, Inc.
P (207) 786-7390
F (207) 786-7396
www.envprojects.com