

STATE OF MAINE DEPARTMENT OF TRANSPORTATION 16 STATE HOUSE STATION AUGUSTA, MAINE 04333-0016

DAVID A. COLE

COMMISSIONER

April 29, 2009
Subject: Swans Island Ferry Terminal
Federal Project No: BH-7826(210)X
State Project No. 007826.21
Amendment No. 3

Dear Sir/Ms:

The following questions have been received:

Question: Item 530.70 Timber Piles delivered and installed, sheet W-04 Note #2 All timber vertical and batter piles shall have driven capacity of 16 tons - Please provide pile lengths required or minimum embedment length.

Response: Listed are the estimated timber pile lengths as requested. These lengths were estimated using borings from the site and expected subsurface conditions. Because of varying soil conditions at the site the contractor shall review the soil borings logs and make their own pile length estimations.

Estimated Pile Tip Elevations:

North Berthing Fence

Vertical and Batter Piles: -41 ft. MLLW

Southern Berthing Fence

Vertical and Batter Piles: -27 ft. MLLW

Western Wave Fence

Slipside Piles: -41 ft. MLLW Backside Piles: -20 ft. MLLW

Eastern Wave Fence

All Piles: -36 ft. MLLW

Question: Spec. Prov. 502 states that Dolphins are Method A. Page 165 of Spec Prov. Refers to reinforced concrete as well as pile fill as being part of the 504.501 Dolphin item. This spec also refers to grout. These are all listed under the Dolphin item so should we assume it is all method A including grout?

Response: No - Only the structural concrete for the dolphins as referred to in Special Provision 502 - Structural Concrete (QC/QA Acceptance Method) is done as method A. Pile fill and grout associated with the dolphins are not covered under this QC/QA Method but their cost is included in the overall pay item of 504.501.



Consider this information prior to submitting your bid on May 6, 2009.

Sincerely,
ATT Bullion

Scott Bickford

Contracts & Specifications Engineer