



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

January 27, 2009
Subject: **Dover-Foxcroft**
State Project No. STP-9199(00)X
State Pin No. 009199.00
Amendment No. 4

Dear Sir/Ms:

Make the following change to the Bid Document:

In the Bid Book, **INSERT** the attached "SPECIAL PROVISION, SECTION 502, STRUCTURAL CONCRETE, (Concrete Fill for Curb)" after page 78.

The following questions have been received:

Question: Item 502.56, Concrete Fill. What is this for? Base under curb?

Response: It will be used to set all granite curb as shown in the typical section of the plans.

Question: What will be the basis of low bid?

Response: Section 0001 only, see Notice to Contractors.

Question: In reference to Water and Sewer related items, how are the following items to be paid, Flaggers, Traffic Control, Signs, Cones Barrels, Loam, Seed, Mulch, Paving, of trenches, Hot top around shutoffs, Hot top around adjusted sewer manholes, Temp soil erosion, etc. ?

Response: These items will be paid for as shown in the Schedule Of Items under Section 0001 and will cover all sections in the Schedule Of Items.

Consider this change and information prior to submitting your bid on **January 28, 2009**.



PRINTED ON RECYCLED PAPER

Sincerely,

A handwritten signature in black ink, appearing to read "Scott Bickford". The signature is written in a cursive style with a large initial "S" and a distinct "B".

Scott Bickford
Contracts & Specifications Engineer

SPECIAL PROVISION
SECTION 502
STRUCTURAL CONCRETE
(Concrete Fill for Curb)

Description. This work shall consist of providing and placing concrete fill for the stabilization of curb.

MATERIALS

Materials. Concrete shall be in accordance with Standard Specification Section 502 - Structural Concrete, and shall be Class "Fill".

CONSTRUCTION REQUIREMENTS

At least 30 days prior to the first placement, a concrete fill mix design shall be submitted by the Contractor to the Department for approval. No concrete fill shall be placed on the project until the mix design is approved by the Department.

Concrete fill shall be placed at least to the pay limits shown on the plans. Forms may be omitted at the Contractor's option. Vibration of concrete will not be required.

Quality Control. One set of test cylinders for compressive strength will be required for each 50 cubic yards of concrete fill placed. Permeability cylinders will not be required.

Method of Measurement. Concrete Fill will be measured for payment by the number of cubic yards of concrete, in place, in accordance with the pay limits established, if such limits have been established. In the absence of pay limits, the Resident may use discretion to accept the delivered quantity as the measurement for payment.

Basis of Payment. Concrete Fill will be paid for at the contract unit price per cubic yard complete in place and accepted. This price shall include all materials, labor, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
502.56 Concrete Fill	Cubic Meter [Cubic Yard]