



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

January 15, 2009
Subject: **Old Town**
Federal Project No. BH-1104(300)X
State Pin No.011043.00
Amendment No. 2

Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book (page 43), **REMOVE** "SPECIAL PROVISION, SECTION 107, TIME, (Supplemental Liquidated Damages for Fabrication Time), 1 page dated December 19, 2008, and **REPLACE** with the attached new "SPECIAL PROVISION, SECTION 107, TIME, (Supplemental Liquidated Damages for Fabrication Time), 1 page dated January 13, 2009.

In the Plans, SHEET NUMBER 4 OF 32, **ADD** the "CONTRACTOR EXCLUSION AREA" where indicated on the attached plan sheet. Make this change in pen and ink.

In the Plans, SHEET NUMBER 26 OF 32, **CHANGE** the weld size for the web to flange connection to be a 5/16" fillet instead of 1/4". Make this change in pen and ink.

In the Plans, SHEET NUMBER 26 OF 32, **ADD** the following note, "8. The weld size for the bearing stiffener to flange connection is to be a 5/16" fillet weld." Make this change in pen and ink.

Consider these changes and information prior to submitting your bid on **January 28, 2009**.

Sincerely,

Scott Bickford
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SPECIAL PROVISION
SECTION 107

TIME

(Supplemental Liquidated Damages for Fabrication Time)

107.8.1 Fabrication Time.

The Department has budgeted for the following amounts of continuous full time fabrication/shop inspection for certain Work components:

<u>Element</u>	<u>Time</u>	<u>Supplemental LD</u>
1) Structural Steel	28 calendar days	\$500 per calendar day
2) Precast Deck Panels	14 calendar days	\$500 per calendar day

The Contractor is responsible for requiring their fabricators and suppliers to produce these products for the Work continuously until finished, including any needed actions to correct unacceptable workmanship or materials. If the Department determines that shop inspection beyond these times is required, then the corresponding Supplemental Liquidated Damages will be deducted as they occur from amounts otherwise due the Contractor. The Contractor will be notified by the Department when these times begin and when the allotted time will expire.

If a fabricator or supplier works more than one shift per day and the Department determines that inspection is required for each shift, each shift will count as a calendar day and the LD rate will be the noted amount per shift per calendar day in lieu of per calendar day.

Inspection is required for the following activities:

For metal fabrication work - welding, including tack welding, heat correcting, non-destructive examination, assembly verification, protective coating application.

For concrete work – tensioning of strands, batching and casting of concrete, breaking of test cylinders, de-tensioning.

File name: ... \100\bridge\msta\004_BDP\plan2.dgn
Division: BRIDGE
User name: Brian.J.Nichols
Date: 12/19/2008

