



Paul R. LePage
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

David Bernhardt
COMMISSIONER

April 4, 2011
Subject: **Kennebunk**
Federal Project No: STP-1121(810)X
State Pin No: 011218.10
Amendment No. 1

Dear Sir/Ms:

Make the following changes to the Bid Documents:

The following questions have been received:

Question: Can the geotechnical report and/or boring depths be provided on the website?

Response: The requested reports have been posted to our website.

Question: Reference Plan Sheet 11 of 130, General Note #4. Could the Department add an additional pay item to the bid items for wood retained by landowner?

Response: No, this needs to be factored into the clearing price.

Question: Reference Cross Sections, sheet 80 depicts a catch basin @ sta 78+50 LT. Plan view does not show this. Please clarify?

Response: CB at Sta. 78+50+/- is incorrect and will not be installed.

Question: From 38+26 to 45+40, does this area receive 3" of HMA? Will any reclaiming other than butt joints be required in this same area?

Response: Sta. 38+26 – 45+40+/- is a 1-1/4" overlay and will require only butt joints.

Question: Reference Item 607.24, Remove and Reset Fence. What type fence is this?

Response: Item 607.24 is a chain link fence.

Question: Item 607.24 – What kind of fence is it? 606.79 350's are designed with 6' post, is there a special end treatment that has a 7' post?

Response: Item 607.24 is a chain link fence. Item 606.79, 350 end treatments will have standard posts. 7' posts are for the guardrail beam.



PRINTED ON RECYCLED PAPER

Question: Will the work shown adjacent to the Southbound off and on ramps require concrete barrier placement?

Response: No concrete barrier placement is anticipated.

Question: Could the Department provide a map and list of signage required by the MTA for work zone traffic control in these areas?

Response: Please refer to MTA Work Permit General Requirements Sections 105.5.1 and 107.4.6. and the MUTCD.

Question: There are two references in the plans to Item 606.178, Guardrail Beam, but there is no pay item for Guardrail Beam.

Response: New end treatments will connect to existing beam. Item 606.178 is unnecessary and not a bid item.

Consider this information prior to submitting your bid on April 6, 2011.

Sincerely,



Scott Bickford
Contracts & Specifications Engineer