



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

July 9, 2009
Subject: **Portland Rail Trail**
Federal Project No: STP-1184(400)S
State Pin No: 011844.00
Amendment No. 3

Dear Sir/Ms:

The following questions have been received:

Question: There are 2 stone seat wall Details on page 27, what type goes to what location? (page 24)

Response: The Stone Seatwall from 61+25 6'L to 61+43 6'L (stationing approximate) shall be Double Faced Wall; all other Stone Seatwall depicted on the plans shall be Single Faced Wall, except for 20' at each end of wall (to be Double Faced Wall). All ends of Stone Seatwall shall be stone faced constructed per the Double Faced Wall detail, and the Granite Cap depicted on the details shall provide a 1" overhang at the top of walls (on all sides).

Question: Who provides the sand for paver work?

Response: Contractor provides (furnish and install) the sand. Previously Purchased Materials do not include sand. Sand is considered incidental to the pay items; refer to Supplemental Specifications Section 608-Sidewalks.

Question: Who provides the cement for paver work?

Response: Contractor provides (furnish and install) the cement. Previously Purchased Materials do not include cement. Cement (sand-cement base) is considered incidental to the pay items; refer to Supplemental Specifications Section 608-Sidewalks.

Consider this information prior to submitting your bid on **July 15, 2009**.

Sincerely,

File

Scott Bickford
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER