



STATE OF MAINE  
 DEPARTMENT OF TRANSPORTATION  
 16 STATE HOUSE STATION  
 AUGUSTA, MAINE  
 04333-0016

JOHN ELIAS BALDACCI  
 GOVERNOR

DAVID A. COLE  
 COMMISSIONER

April 2, 2009  
 Subject: **New Portland**  
 Maine Project No. 012635.00  
 State Pin No.012635.00  
**Amendment No. 1**

Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book (pages 4 through 9), **REMOVE** the “SCHEDULE OF ITEMS” 6 pages dated 090309 and **REPLACE** it with the attached new “SCHEDULE OF ITEMS” 7 pages dated 090402.

In the Plans, Sheet Number 2 of 39, **ADD** the following items to the “ESTIMATED QUANTITIES” in pen and ink:

<u>511.07</u>	<u>COFFERDAM: ABUTMENT NO. 1</u>	<u>1</u>	<u>LS</u>
<u>606.23</u>	<u>GUARDRAIL TYPE 3C- SINGLE RAIL</u>	<u>525</u>	<u>LF</u>
		<u>50</u>	<u>LF</u>
<u>606.231</u>	<u>GUARDRAIL TYPE 3C-15 FOOT RADIUS AND LESS</u>		
		<u>50</u>	<u>LF</u>
<u>606.265</u>	<u>TERMINAL END-SINGLE RAIL-GALVANIZED STEEL</u>	<u>3</u>	<u>EA”</u>

In the Plans, Sheet Number 2 of 39, **REMOVE** the following items from the “ESTIMATED QUANTITIES” list: Item No.606.17 and 606.21. Make this change in pen and ink.

In the Plans, Sheet Number 2 of 39, under “GENERAL CONSTRUCTION NOTES” **DELETE** in its entirety, note 21. Make this change in pen and ink.

In the Plans, Sheet Number 7 of 39 and Sheet Number 11 of 39, **CHANGE** the Guardrail Type from Type 3b to Type 3c. Make this change wherever Type 3b occurs in the Plans in pen and ink

The following questions have been received:

**Question:** On contract drawing #30 of 39, the diagrams are shown to be “B”, “G”, and “H”. Are these the same as “MB”, “MG”, and “MH” shown in the standard details?



PRINTED ON RECYCLED PAPER

**Response:** B, G, H are diaphragms denoted in English units and MG, MB, MH are the metric equivalents to those diaphragms thus denoted by the "M".

**Question:** The plans call for 3b rail, is this correct or should it be 3c rail?

**Response:** Type 3c is correct, please see the above change.

**Question:** The plans do not call for Terminal Ends. Shouldn't there be some?

**Response:** Yes – please see the new schedule of items.

Consider these changes and information prior to submitting your bid on April 8, 2009.

Sincerely,



*for*

Scott Bickford  
Contracts & Specifications Engineer

SCHEDULE OF ITEMS

CONTRACT ID: 012635.00

PROJECT(S): 012635.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.08 REMOVING BUILDING NO.: 1	LUMP	LUMP			
0020	202.15 REMOVING MANHOLE OR CATCH BASIN	EA 1.000				
0030	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0040	203.20 COMMON EXCAVATION	CY 650.000				
0050	203.24 COMMON BORROW	CY 1150.000				
0060	203.25 GRANULAR BORROW	CY 365.000				
0070	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	CY 1200.000				
0080	206.09 STRUCTURAL ROCK EXCAVATION - ABUTMENTS AND RETAINING WALLS	CY 10.000				
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY 1825.000				
0100	403.207 HOT MIX ASPHALT 19.0 MM HMA	T 435.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012635.00

PROJECT(S): 012635.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	36.000 T				
0120	403.210 HOT MIX ASPHALT 9.5 MM HMA	500.000 T				
0130	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	290.000 T				
0140	409.15 BITUMINOUS TACK COAT - APPLIED	220.000 G				
0150	501.231 DYNAMIC LOADING TEST	1.000 EA				
0160	501.46 STEEL H-BEAM PILES 73 LBS/FT, DELIVERED	139.000 LF				
0170	501.461 STEEL H-BEAM PILES 73 LBS/FT, IN PLACE	139.000 LF				
0180	501.90 PILE TIPS	5.000 EA				
0190	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0200	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0210	502.25 STRUCTURAL CONCRETE SUPERSTRUCTURE SLABS	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012635.00

PROJECT(S): 012635.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0230	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0240	502.56 CONCRETE FILL	22.000 CY				
0250	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	47600.000 LB				
0260	503.13 REINFORCING STEEL, PLACING	47600.000 LB				
0270	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP	LUMP			
0280	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0290	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0300	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			
0310	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0320	511.07 COFFERDAM: ABUTMENT NO.1	LUMP	LUMP			

SCHEDULE OF ITEMS

CONTRACT ID: 012635.00

PROJECT(S): 012635.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	512.081 FRENCH DRAINS	LUMP	LUMP			
0340	514.06 CURING BOX FOR CONCRETE CYLINDERS	EA 1.000				
0350	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0360	523.52 BEARING INSTALLATION	EA 5.000				
0370	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	EA 5.000				
0380	526.34 PERMANENT CONCRETE TRANSITION BARRIER	EA 4.000				
0390	603.169 15 INCH CULVERT PIPE OPTION III	LF 225.000				
0400	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	EA 1.000				
0410	604.246 CATCH BASIN TYPE F5	EA 1.000				
0420	606.1721 BRIDGE TRANSITION - TYPE 1	EA 4.000				
0430	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	LF 525.000				

SCHEDULE OF ITEMS

CONTRACT ID: 012635.00

PROJECT(S): 012635.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	50.000 LF				
0450	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	3.000 EA				
0460	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0470	609.31 CURB TYPE 3	500.000 LF				
0480	610.08 PLAIN RIPRAP	650.000 CY				
0490	615.0701 LOAM - PLAN QUANTITY	120.000 CY				
0500	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	5.500 UN				
0510	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	9.000 UN				
0520	619.12 MULCH	14.500 UN				
0530	619.1401 EROSION CONTROL MIX	240.000 CY				
0540	620.58 NON WOVEN GEOTEXTILE	825.000 SY				

SCHEDULE OF ITEMS

CONTRACT ID: 012635.00

PROJECT(S): 012635.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	2450.000 LF				
0560	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0570	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0580	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0590	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	10.000 HR				
0600	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	1020.000 SF				
0610	639.18 FIELD OFFICE TYPE A	1.000 EA				
0620	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0630	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0640	659.10 MOBILIZATION	LUMP	LUMP			
0650	834.322 DRY HYDRANT - INSTALL ONLY	LUMP	LUMP			
	SECTION 0001 TOTAL					

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012635.00

PROJECT(S): 012635.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
	TOTAL BID					