



STATE OF MAINE
 DEPARTMENT OF TRANSPORTATION
 16 STATE HOUSE STATION
 AUGUSTA, MAINE
 04333-0016

JOHN ELIAS BALDACCI
 GOVERNOR

DAVID A. COLE
 COMMISSIONER

November 21, 2007
 Subject: **Cape Elizabeth**
 Project No. STP-1309(000)X
 Pin No's 012992.00 & 013090.00
Amendment No. 2

Dear Sir/Ms:

Please make the following changes to the Bid Documents:

In the Bid Book, REMOVE the existing: "Schedule of Items" dated 071106, six pages total (pages 3 thru 8 of the book) and REPLACE with the attached updated: "Schedule of Items" dated 071121, seven pages total.

In the Plan Sheets, on sheet three of seventy-six titled: "Estimated Quantities & Earthwork Summary" under the "Estimated Quantities" CHANGE the following item: "606.24 - GR TY 3D - Single Rail" to: "606.247 Guardrail Type 3D - Single Rail - 7' Posts". Make this change in pen and ink.

On sheet three of seventy-six titled: "Estimated Quantities & Earthwork Summary" under the "Estimated Quantities" ADD the following item: "619.1201 - Mulch - 121 - UN". Make this change in pen and ink.

On sheet three of seventy-six titled: "Estimated Quantities & Earthwork Summary" under the "Estimated Quantities" ADD the following item: "631.32 - Culvert Cleaner (Including Operator) - 10.00 - HR". Make this change in pen and ink.

On sheet three of seventy-six titled: "Estimated Quantities & Earthwork Summary" under the "Estimated Quantities" CHANGE the following item: "645.280 - Wood Post" to: "606.47 - Wood Post". Make this change in pen and ink.

On sheet six of seventy-six titled: "Construction Notes" under: "509.2000 Aluminum Structural Plate Pipe Arch" CHANGE the existing Length to Longest Point measurements from 9.18 & 9.44 to 10.00 & 10.00. Make these changes in pen and ink.



PRINTED ON RECYCLED PAPER

The following questions have been received.

Question: There is no item # 619.1201 Mulch on this project, is this correct?

Response: No. See changes made earlier in this amendment.

Question: In regards to items: "304.10 Aggregate Subbase Course – Gravel" and "304.104 Aggregate Subbase Course (Plan Quantity)" where are these items to be used?

Response: Item 304.104 Aggregate Subbase Course (Plan Quantity) is for full construction areas (see general note #21) and Item 304.10 Aggregate Subbase Course – Gravel is for correcting shoulder cross slopes and other miscellaneous areas. (see general note #37)

Question: On the General Notes plansheet, general note #21 says that all computation methods are available, could we be provided with this information?

Response: Please contact the Project Manager in Region 1 as stated within general note #21.

Question: On Special Provision, Section 107, Prosecution and Progress, the last sentence states: "Only one paving operation will be allowed excluding hand placed paving unless otherwise approved by the Resident". Does this mean binder and surface must immediately follow foam asphalt?

Response: Two or more machine placement crews will not be allowed to concurrently work on the project. Binder placement on the foamed asphalt must wait at least 48 hours as stated in Special Provision 309.

Question: Please advise where we can find details or specifications for Item #645.280 Wood Post?

Response: See change earlier in this amendment changing the item number.

Consider these changes and information prior to submitting your bid on November 28, 2007.

Sincerely,

A handwritten signature in black ink, appearing to read "S. Bickford" with a stylized flourish at the end.

Scott Bickford

Contracts & Specifications Engineer

SCHEDULE OF ITEMS

CONTRACT ID: 012992.00

PROJECT(S): 012992.00
STP-1309(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 HIGHWAY ITEMS (BASIS OF AWARD)						
0010	201.11 CLEARING	0.188 AC				
0020	201.23 REMOVING SINGLE TREE TOP ONLY	8.000 EA				
0030	201.24 REMOVING STUMP	11.000 EA				
0040	202.203 PAVEMENT BUTT JOINTS	495.000 SY				
0050	203.2001 COMMON EXCAVATION - PLAN QUANTITY	3225.000 CY				
0060	203.25 GRANULAR BORROW	25.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1109.000 CY				
0080	304.104 AGGREGATE SUBBASE COURSE (PLAN QUANTITY)	2057.000 CY				
0090	309.35 FULL DEPTH RECYCLED PAVEMENT W/ FOAM ASPHALT 5 INCH DEPTH	23180.000 SY				

SCHEDULE OF ITEMS

CONTRACT ID: 012992.00

PROJECT(S): 012992.00
STP-1309(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	1960.000 T				
0110	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	140.000 T				
0120	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	3260.000 T				
0130	409.15 BITUMINOUS TACK COAT - APPLIED	950.000 G				
0140	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	243.000 CY				
0150	509.192 ALUMINUM ALLOY STRUCTURAL PLATE PIPE ARCH EXTENSION	LUMP	LUMP			
0160	509.201 CULVERT SLIPLINING	145.200 LF				
0170	509.203 HIGH DENSITY POLYETHYLENE FISH WEIRS	LUMP	LUMP			
0180	527.303 ENERGY ABSORBING SYSTEM (ET-2,000)	4.000 EA				
0190	603.16 15 INCH CULVERT PIPE OPTION I	463.500 LF				
0200	603.171 18 INCH CORRUGATED METAL PIPE	5.300 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012992.00

PROJECT(S): 012992.00

STP-1309(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	56.000 LF				
0220	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	56.000 LF				
0230	604.092 CATCH BASIN TYPE B1-C	2.000 EA				
0240	604.182 CLEAN EXISTING CATCH BASIN AND MANHOLE	5.000 EA				
0250	605.09 6 INCH UNDERDRAIN TYPE B	1350.000 LF				
0260	605.10 6 INCH UNDERDRAIN OUTLET	130.000 LF				
0270	605.12 15 INCH UNDERDRAIN TYPE C	550.000 LF				
0280	606.247 GUARDRAIL TYPE 3D - SINGLE RAIL - 7' POSTS	300.000 LF				
0290	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	18.000 EA				
0300	606.47 SINGLE WOOD POST	12.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012992.00

PROJECT(S): 012992.00

STP-1309(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0310	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0320	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0330	609.31 CURB TYPE 3	1560.000 LF				
0340	610.08 PLAIN RIPRAP	160.000 CY				
0350	610.18 STONE DITCH PROTECTION	420.000 CY				
0360	613.319 EROSION CONTROL BLANKET	1912.000 SY				
0370	615.07 LOAM	100.000 CY				
0380	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	8.000 UN				
0390	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	105.000 UN				
0400	619.1201 MULCH - PLAN QUANTITY	121.000 UN				
0410	620.58 EROSION CONTROL GEOTEXTILE	1560.000 SY				

SCHEDULE OF ITEMS

CONTRACT ID: 012992.00

PROJECT(S): 012992.00
STP-1309(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0420	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	21750.000 LF				
0430	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	90.000 SF				
0440	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0450	629.05 HAND LABOR, STRAIGHT TIME	55.000 HR				
0460	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	55.000 HR				
0470	631.14 GRADER (INCLUDING OPERATOR)	25.000 HR				
0480	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	50.000 HR				
0490	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	5.000 HR				
0500	631.28 BRUSH CHIPPER (INCLUDING OPERATOR)	5.000 HR				
0510	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR				
0520	639.19 FIELD OFFICE TYPE B	1.000 EA				

SCHEDULE OF ITEMS

CONTRACT ID: 012992.00

PROJECT(S): 012992.00
STP-1309(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	652.33 DRUM	100.000 EA				
0540	652.34 CONE	150.000 EA				
0550	652.35 CONSTRUCTION SIGNS	920.000 SF				
0560	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	177.000 CD				
0570	652.38 FLAGGER	3050.000 HR				
0580	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0590	659.10 MOBILIZATION	LUMP	LUMP			
0600	660.21 ON-THE-JOB TRAINING (BID)	1000.000 HR				
	SECTION 0001 TOTAL					.

SECTION 0002 UTILITY ITEMS - PORTLAND

0610	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	6.000 EA				
------	--	-------------	--	--	--	--

SCHEDULE OF ITEMS

CONTRACT ID: 012992.00

PROJECT(S): 012992.00
STP-1309(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0620	823.011 GATE VALVE BOX, INSTALL ONLY	6.000 EA				
0630	823.332 GATE VALVE BOX, ADJUST TO GRADE	20.000 EA				
	SECTION 0002 TOTAL					
	TOTAL BID					