



STATE OF MAINE
 DEPARTMENT OF TRANSPORTATION
 16 STATE HOUSE STATION
 AUGUSTA, MAINE
 04333-0016

JOHN ELIAS BALDACCI
 GOVERNOR

DAVID A. COLE
 COMMISSIONER

June 2, 2009
 Subject: **Portland**
 Federal Project No: STP-1310(400)S
 State Pin No: 013104.00
Amendment No. 1

Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book (pages 4 through 6), **REMOVE** the "SCHEDULE OF ITEMS", 3 pages dated 090508, and **REPLACE** with the attached, new "SCHEDULE OF ITEMS", 3 pages dated 090602.

In the Bid Book (page 60), "SPECIAL PROVISION, SECTION 403, TEXTURED ASPHALT PAVEMENT WITH COLOR COATING" in the last line **CHANGE** the "Pay Unit" from "Square Foot" to read "**Square Yard**". Make this change in pen and ink.

In the Bid Book (page 61), "SPECIAL PROVISION, SECTION 403, TEXTURED ASPHALT PAVEMENT WITH THERMOPLASTIC INLAY" in the last line **CHANGE** the "Pay Unit" from "Square Foot" to read "**Square Yard**". Make this change in pen and ink.

In the Plans, SHEET NUMBER 2 OF 5, ESTIMATED QUANTITIES, **CHANGE** the "QUANTITY" and "UNIT" for the below items;

ITEM	QUANTITY	UNIT
403.1021	90	SY
403.1022	150	SY

Make this change in pen and ink.

The following questions have been received:

Question: Item # 403.1021, Textured Asphalt Pavement with Color Coating. In the Description it is called ThermoPrint TM Running Bond Pattern with a "brick red" color.



PRINTED ON RECYCLED PAPER

Is this regular "StreetPrint" with what kind of pattern? Offset brick, Straight brick, not sure. No problem with the color if this is regular "StreetPrint".

Response: The "brick red" color is a generic color and the proposed color sample will need to be submitted for approval. The Running Bond Pattern is an offset brick pattern. The DuraTherm TM StreetPrint is an equivalent to the ThermoPrint TM Running Bond Pattern. The template pattern will need to be submitted for approval.

Question: Item # 403.1022 - Textured Asphalt Pavement with Thermoplastic Inlay. In the Description on this it is called ThermoPrint TM Running Bond Pattern, including ThermoPrint TM High-Traffic Surfacing System. Is this regular "DuroTherm" product through Integrated Paving Concepts??

Response: The DuraTherm TM thermoplastic inlay is an equivalent to the ThermoPrint TM thermoplastic inlay; they are not the same product.

Consider these changes and information prior to submitting your bid on **June 3, 2009**.

Sincerely,



Scott Bickford
Contracts & Specifications Engineer

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013104.00

PROJECT(S): STP-1310(400)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	403.1021 TEXTURED ASPHALT PAVEMENT	90.000 SY				
0020	403.1022 SURFACE TREATED ASPHALT PAVEMENT W/ THERMOPLASTIC INLAY	150.000 SY				
0030	608.26 CURB RAMP DETECTABLE WARNING FIELD	48.000 SF				
0040	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	2.000 EA				
0050	626.11 PRECAST CONCRETE JUNCTION BOX	3.000 EA				
0060	626.21 METALLIC CONDUIT	30.000 LF				
0070	626.22 NON-METALLIC CONDUIT	450.000 LF				
0080	626.31 18 INCH FOUNDATION	4.000 EA				
0090	626.34 SIGNAL POLE FOUNDATION	1.000 EA				
0100	626.35 CONTROLLER CABINET FOUNDATION	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013104.00

PROJECT(S): STP-1310(400)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	2000.000 LF				
0120	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	1350.000 SF				
0130	627.77 REMOVING PAVEMENT MARKINGS	1500.000 SF				
0140	643.80 TRAFFIC SIGNALS AT AUBURN ST. W/ LYSETH MOORE DR. & CROQUET	LUMP	LUMP			
0150	643.83 VIDEO DETECTION SYSTEM	LUMP	LUMP			
0160	643.90 INTERCONNECT WIRE BETWEEN LYSETH MOORE DR. AND SANBORN ST.	LUMP	LUMP			
0170	643.91 MAST ARM POLE W/ 60' MAST ARM	1.000 EA				
0180	643.92 PEDESTAL POLE	4.000 EA				
0190	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	1.000 EA				
0200	645.108 DEMOUNT POLE	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013104.00

PROJECT(S): STP-1310(400)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	1.000 EA				
0220	645.118 REINSTALL POLE	1.000 EA				
0230	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	37.000 SF				
0240	652.33 DRUM	60.000 EA				
0250	652.34 CONE	60.000 EA				
0260	652.35 CONSTRUCTION SIGNS	108.000 SF				
0270	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0280	652.38 FLAGGER	400.000 HR				
0290	659.10 MOBILIZATION	LUMP	LUMP			
	TOTAL BID					