



STATE OF MAINE
 DEPARTMENT OF TRANSPORTATION
 16 STATE HOUSE STATION
 AUGUSTA, MAINE
 04333-0016

JOHN ELIAS BALDACCI
 GOVERNOR

DAVID A. COLE
 COMMISSIONER

September 29, 2008
 Subject: **Wells**
 Federal Project No. BR-1561(100)X
 State Pin No.015611.00
Amendment No. 2

Dear Sir/Ms:

Make the following change to the Bid Document:

In the Bid Book, **REMOVE**, in its entirety, the "SCHEDULE OF ITEMS" (dated 080916, 5 pages and replaced in Amendment #1) and **REPLACE** with the attached, new "SCHEDULE OF ITEMS" (dated 080929, 5 pages).

In the Plans (Plan Sheet 2 of 17) **ADD** the following item, in pen and ink to the Estimated Quantities:

Item #	Quantity and Units
502.31 – Structural Concrete Approach Slabs	LUMP

The following questions have been received:

Question: On Plan Sheet 13 of 17, "ABUTMENT DETAILS", an Approach Slab with Dowels is shown. Item 502.31, Structural Concrete Approach Slab, appears to be missing from the Schedule Of Items.

Response: See the new Schedule of Items contained in this amendment.

Question: Schedule of Items, Rebar Quantity (Item 503.14) states 9000.00 lbs. I calculate 11,400.0 lbs. including Approach Slabs, Transition Barriers, and Precast Beam Abutment Pins.

Response: For information: It should be noted that the following bars are incidental and are not part of a pay quantity:

- a. Anything embedded in the precast slabs (i.e. curb stirrups) is incidental to the 535 precast item.
- b. The #8 anchor dowels are incidental to the 535 precast item.
- c. The transition barrier bars are incidental to the 526 item.



PRINTED ON RECYCLED PAPER

Question: How is the approach slab concrete and reinforcing steel to be paid for?

Response: See the new Schedule of Items contained in this amendment.

Question: Will the State or Town post a weight limit on the Bourne Ave. in the Spring?

Response: The answer is being looked into, however the Town may require the Contractor to carry a bond if they wish to travel heavy vehicles over the road.

Question: Would the DOT consider it prudent to consider something other than 9.5mm HMA on the approaches to this bridge?

Response: The 9.5mm needs to be used on the bridge decks. Other options may be considered for the approaches. The Department may consider other options at the time of paving

Consider these changes and information prior to submitting your bid on **October 1, 2008.**

Sincerely,

A handwritten signature in black ink, appearing to read "Scott Bickford" with a stylized flourish at the end.

Scott Bickford
Contracts & Specifications Engineer

MAINE DEPARTMENT OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE: 1
DATE: 080929
REVISED:

CONTRACT ID: 015611.00

PROJECT(S): BR-1561(100)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 PROJECT ITEMS

0010	202.19 REMOVING EXISTING BRIDGE	LUMP		LUMP			
0020	203.20 COMMON EXCAVATION	CY	675.000				
0030	203.2318 DISPOSAL OF SPECIAL WASTE	T	220.000				
0040	203.24 COMMON BORROW	CY	10.000				
0050	203.25 GRANULAR BORROW	CY	370.000				
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	CY	390.000				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY	720.000				
0080	403.210 HOT MIX ASPHALT 9.5 MM HMA	T	215.000				
0090	409.15 BITUMINOUS TACK COAT - APPLIED	G	65.000				
0100	501.231 DYNAMIC LOADING TEST	EA	2.000				

MAINE DEPARTMENT OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE: 2
DATE: 080929
REVISED:

CONTRACT ID: 015611.00

PROJECT(S): BR-1561(100)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	501.46 STEEL H-BEAM PILES 73 LBS/FT, DELIVERED	650.000 LF				
0120	501.461 STEEL H-BEAM PILES 73 LBS/FT, IN PLACE	650.000 LF				
0130	501.90 PILE TIPS	10.000 EA				
0140	501.91 PILE SPLICES	20.000 EA				
0150	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0160	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0170	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0180	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0190	503.14 EPOXY COATED REINFORCING STEEL, FABRICATED AND DELIVERED	9000.000 LB				
0200	503.15 EPOXY COATED REINFORCING STEEL PLACING	9000.000 LB				
0210	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			

SCHEDULE OF ITEMS

CONTRACT ID: 015611.00

PROJECT(S): BR-1561(100)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0230	514.06 CURING BOX FOR CONCRETE CYLINDERS	EA 1.000				
0240	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0250	526.34 PERMANENT CONCRETE TRANSITION BARRIER	EA 4.000				
0260	527.303 ENERGY ABSORBING SYSTEM (ET-2,000)	EA 4.000				
0270	535.62 PRESTRESSED STRUCTURAL CONCRETE BOX BEAM	LUMP	LUMP			
0280	606.1721 BRIDGE TRANSITION - TYPE 1	EA 4.000				
0290	606.234 GR TP 3C - SGL RAIL, 7' POSTS	LF 100.000				
0300	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	EA 8.000				
0310	610.08 PLAIN RIPRAP	CY 155.000				
0320	615.07 LOAM	CY 24.000				

SCHEDULE OF ITEMS

CONTRACT ID: 015611.00

PROJECT(S): BR-1561(100)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	4.000 UN				
0340	619.1201 MULCH - PLAN QUANTITY	4.000 UN				
0350	619.1401 EROSION CONTROL MIX	48.000 CY				
0360	620.58 EROSION CONTROL GEOTEXTILE	130.000 SY				
0370	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	1200.000 LF				
0380	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0390	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0400	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	10.000 HR				
0410	631.36 FOREPERSON	10.000 HR				
0420	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	406.000 SF				
0430	639.18 FIELD OFFICE TYPE A	1.000 EA				

MAINE DEPARTMENT OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE: 5
DATE: 080929
REVISED:

CONTRACT ID: 015611.00

PROJECT(S): BR-1561(100)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	652.38 FLAGGER	40.000 HR				
0450	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0460	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0470	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					