



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE  
04333-0016

JOHN ELIAS BALDACCI  
GOVERNOR

DAVID A. COLE  
COMMISSIONER

October 29, 2008  
Subject: **Bangor I-95**  
Federal Project Nos. BH-1651(000) &  
BH-1651(100)  
State Pin Nos. 016510.00 & 016511.00  
**Amendment No. 1**

Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book (page 1), NOTICE TO CONTRACTORS, after the paragraph that begins "Scope of Work..." **ADD** the following sentence "The basis of award will be Cost plus Time Total bid." Make this change in pen and ink.

In the Bid Book (pages 3 through 9), **REMOVE** the "SCHEDULE OF ITEMS" 7 pages dated 081014, and **REPLACE** with the attached new "SCHEDULE OF ITEMS" 10 pages dated 10/28/08.

In the Bid Book (page 29), SPECIAL PROVISION, SECTION 101.2.1, SUPPLEMENTAL DEFINITIONS, B Portion of the Work, in the sentence after "The following will not count toward the "B" portion:" **REMOVE** the word "Backwall" from the sentence that begins "Abutment, Backwall, New Structural steel painting..." Make this change in pen and ink.

The following questions have been received:

**Question:** SP 102.12 (page 32), 2<sup>nd</sup> paragraph states, "This number of calendar days shall be legibly written in ink in the place provided in the bid forms". This place does not exist?

**Response:** Please see the amended Schedule Of Items.

**Question:** SP 107, "Time" (page 44), last paragraph of page 1 of 6 states "The electronic version shall be done with Primavera Project Planner software or approved equivalent". Is the Department familiar with Microsoft Project and be willing to consider it an equivalent?



PRINTED ON RECYCLED PAPER

**Response:** Yes

**Question:** SP 107.6, first paragraph states "B portion time period will begin either 5:00AM Sunday March 26, 2009 or the date on which the Contractor commences ... whichever is earlier". Is there any restriction as to how early the Contractor can start?

**Response:** Yes, March 29, 2009.

Consider these changes and information prior to submitting your bid on November 12, 2008.

Sincerely,

A handwritten signature in black ink, appearing to read "Scott Bickford". The signature is written in a cursive, flowing style.

Scott Bickford  
Contracts & Specifications Engineer

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING : November 12, 2008

CALL ORDER : 001

CONTRACT ID : 016510.00

PROJECTS

-----

BH-1651(000)

BH-1651(100)

COUNTY : PENOBSCOT

CONTRACT ID : 016510.00

BANGOR, BRIDGE REHABILITATION. WORK INCLUDES INTERSTATE 95 NORTHBOUND BRIDGE NO. 5795 DECK REPLACEMENT, ABUTMENT REHABILITATION, AND OTHER INCIDENTAL WORK. INTERSTATE 95 SOUTHBOUND BRIDGE NO. 1428 DECK REPLACEMENT, ABUTMENT REHABILITATION, STRUCTURAL STEEL REPLACEMENT, AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT*	08/30/09	CALENDAR DAYS \$ 900.00

\*--INDICATES COST PLUS TIME SITE.  
SEE SCHEDULE OF ITEMS FOR ROAD USER COST PER DAY.

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

DATE:

REVISED: 10/28/08

CONTRACT ID: 016510.00

PROJECT(S): BH-1651(000)  
BH-1651(100)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 BRIDGE ITEMS						
0010	107.51 PROSECUTION OF WORK - INITIAL SCHEDULE	LUMP	LUMP			.
0020	107.53 PROSECUTION OF WORK - BIWEEKLY UPDATES	EA 6.000		.		.
0030	202.10 REMOVING EXISTING SUPERSTRUCTURE (PROPERTY OF CONTRACTOR)	LUMP	LUMP			.
0040	203.20 COMMON EXCAVATION	CY 40.000		.		.
0050	203.24 COMMON BORROW	CY 20.000		.		.
0060	203.25 GRANULAR BORROW	CY 50.000		.		.
0070	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	CY 70.000		.		.
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY 40.000		.		.
0090	403.207 HOT MIX ASPHALT 19.0 MM HMA	T 120.000		.		.
0100	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	T 80.000		.		.

SCHEDULE OF ITEMS

DATE:

REVISED: 10/28/08

CONTRACT ID: 016510.00

PROJECT(S): BH-1651(000)  
BH-1651(100)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	130.000 T	.	.	.	.
0120	409.15 BITUMINOUS TACK COAT - APPLIED	70.000 G	.	.	.	.
0130	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP	.	.	.
0140	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP	.	.	.
0150	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP	.	.	.
0160	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	18400.000 LB	.	.	.	.
0170	503.13 REINFORCING STEEL, PLACING	18400.000 LB	.	.	.	.
0180	504.701 STRUCTURAL STEEL FABRICATED AND DELIVERED, ROLLED	LUMP	LUMP	.	.	.
0190	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP	.	.	.
0200	504.8101 REMOVAL OF STRUCTURAL STEEL	10000.000 LB	.	.	.	.

SCHEDULE OF ITEMS

DATE:

REVISED: 10/28/08

CONTRACT ID: 016510.00

PROJECT(S): BH-1651(000)  
BH-1651(100)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	505.08 SHEAR CONNECTORS	LUMP	LUMP			.
0220	506.9102 ZINC RICH COATING SYSTEM (SHOP APPLIED)	LUMP	LUMP			.
0230	514.06 CURING BOX FOR CONCRETE CYLINDERS	EA 1.000		.		.
0240	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	SY 2500.000		.		.
0250	518.52 REPAIR OF UPWARD FACING SURFACES > 7.9 IN.	CY 30.000		.		.
0260	518.61 REPAIR OF VERTICAL SURFACES > 7.9 IN.	CY 30.000		.		.
0270	520.22 EXPANSION DEVICE - COMPRESSION SEAL	EA 3.000		.		.
0280	520.222 EXPANSION DEVICE- COMPRESSION SEAL - INSTALL ONLY PIER "A")	LUMP	LUMP			.
0290	520.222 EXPANSION DEVICE- COMPRESSION SEAL - INSTALL ONLY PIER "B")	LUMP	LUMP			.
0300	520.222 EXPANSION DEVICE- COMPRESSION SEAL - INSTALL ONLY PIER "C")	LUMP	LUMP			.

SCHEDULE OF ITEMS

DATE:

REVISED: 10/28/08

CONTRACT ID: 016510.00

PROJECT(S): BH-1651(000)  
BH-1651(100)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0310	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP	LUMP			.
0320	524.40 PROTECTIVE SHIELD	LUMP	LUMP			.
0330	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	LF 2400.000		.		.
0340	526.331 PERMANENT CONCRETE BARRIER TYPE III B	LUMP	LUMP			.
0350	526.40 RESETTING TEMPORARY CONCRETE BARRIER TYPE I	LF 2400.000		.		.
0360	527.34 WORK ZONE CRASH CUSHIONS	UN 6.000		.		.
0370	602.30 FLOWABLE CONCRETE FILL	CY 20.000		.		.
0380	606.1721 BRIDGE TRANSITION - TYPE 1	EA 8.000		.		.
0390	606.24 GUARDRAIL TYPE 3D - SINGLE RAIL	LF 200.000		.		.
0400	607.421 SCREENING FENCE	LF 700.000		.		.
0410	609.11 VERTICAL CURB TYPE 1	LF 220.000		.		.

SCHEDULE OF ITEMS

DATE:

REVISED: 10/28/08

CONTRACT ID: 016510.00

PROJECT(S): BH-1651(000)  
BH-1651(100)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0420	609.26 CURB TRANSITION SECTION B TYPE 1	8.000 EA	.		.	
0430	615.07 LOAM	30.000 CY	.		.	
0440	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	1.000 UN	.		.	
0450	619.12 MULCH	1.000 UN	.		.	
0460	619.1401 EROSION CONTROL MIX	60.000 CY	.		.	
0470	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	2000.000 LF	.		.	
0480	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP		LUMP		.
0490	629.05 HAND LABOR, STRAIGHT TIME	80.000 HR	.		.	
0500	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR	.		.	
0510	631.16 ROLLER, PAVEMENT (INCLUDING OPERATOR)	40.000 HR	.		.	
0520	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR	.		.	

SCHEDULE OF ITEMS

DATE:

REVISED: 10/28/08

CONTRACT ID: 016510.00

PROJECT(S): BH-1651(000)  
BH-1651(100)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	631.211 PAVEMENT SWEEPER (INCLUDING OPERATOR)	40.000 HR	.		.	
0540	631.212 SMALL PAVEMENT GRINDER (INCLUDING OPERATOR)	40.000 HR	.		.	
0550	639.18 FIELD OFFICE TYPE A	1.000 EA	.		.	
0560	652.30 FLASHING ARROW BOARD	2.000 EA	.		.	
0570	652.35 CONSTRUCTION SIGNS	1000.000 SF	.		.	
0580	652.38 FLAGGER	400.000 HR	.		.	
0590	652.381 TRAFFIC OFFICERS	400.000 HR	.		.	
0600	652.39 WORK ZONE TRAFFIC CONTROL	LUMP		LUMP		.
0610	652.41 PORTABLE - CHANGEABLE MESSAGE SIGN	4.000 EA	.		.	
0620	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP		LUMP		.
0630	659.10 MOBILIZATION	LUMP		LUMP		.
	SECTION 0001 TOTAL					.

SCHEDULE OF ITEMS

DATE:

REVISED: 10/28/08

CONTRACT ID: 016510.00

PROJECT(S): BH-1651(000)  
BH-1651(100)

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
ITEMS TOTAL						

COST PLUS TIME SITES	ROAD USER COST PER DAY	NUMBER OF DAYS BID
00 CONTRACT COMPLETION	\$10000	
TOTAL BID		

SCHEDULE OF ITEMS

CONTRACT ID: 016510.00

PROJECT(S): BH-1651(000)  
BH-1651(100)

LIST ITEMS ON THIS PAGE BY AMENDMENT

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
TOTAL BID				.		.

SPECIAL PROVISIONS ATTACHED