



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

June 11, 2010
Subject: **Dover-Foxcroft**
Federal Project No's: STP-1731(000)X,
STP-1731(100)X, STP-1729(000)X &
HPP-1759(700)X
State Pin No's: 017310.00, 017311.00,
017290.00 & 017597.00
Amendment No. 1

Dear Sir/Ms:

Make the following changes to the bid Documents:

In the Bid Book (page 8) SCHEDULE OF ITEMS, Line No 0500, Item No. 645.271 – REGULATORY WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I, **CHANGE** the quantity from 37.000 to read **42.000** SF. Make this change in pen and ink.

PIN 017290.00

In the Plans, Sheet Number 2 of 4, NOTES, **ADD** the following notes in pen and ink;

“24. Any exposed holes on the existing mast arm pole resulting from the removal of pedestrian features shall be thoroughly cleaned, tapped, coated with zinc-rich paint, and plugged with a screw-in type plug of the correct size. The plug shall be galvanized or completely coated with zinc-rich paint.

25. The 5-section vehicular signal head assembly currently located on the pedestrian pole located in the southeast quadrant of the intersection, which will be removed, is intended to be relocated to the new pedestrian signal pole to be installed at Station 12+95.0 Left. Payment will be incidental to Item 643.71.

26. All six locations proposed for installation of new pedestrian signals are intended to have new pedestal poles. Pedestal poles will be paid under Item 643.92 as indicated in the original schedule of bid items.

27. All new pedestrian signal assemblies are intended to include countdown heads and audible features.



PRINTED ON RECYCLED PAPER

28. The existing traffic signal controller is a Naztec Model 900-TxII/CL, v14.16.”

PIN 017597.00

In the Plans, Sheet Number 2 Of 3 and Sheet Number 3 Of 3, **CHANGE** the Scale under “PLAN” (lower right side of plan sheet) from “50 – 0 – 10 – 20” to read as follows; **“25 – 0 – 25 – 50”**, left to right. Make this change in pen and ink.

In the Plans, Sheet Number 3 Of 3, GENERAL NOTES, **ADD** the following notes in pen and ink;

“17. Install a 30”x30” R1-1 “STOP” sign at Station 59+03 LT.

18. Two-section red beacon assemblies on span wire shall be tethered at the bottom for stability. Payment will be incidental to Item 643.60.

19. In the red beacon assemblies, top beacons shall flash simultaneously and bottom red beacons shall flash simultaneously between assembly pairs, with top and bottom beacons flashing alternately. Yellow beacon pairs shall flash alternately.”

Consider these changes and information prior to submitting your bid on June 16, 2010.

Sincerely,

A handwritten signature in blue ink, appearing to read "Scott Bickford", followed by the word "FOR" in capital letters.

Scott Bickford
Contracts & Specifications Engineer Dover-