



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE  
04333-0016

JOHN ELIAS BALDACCI  
GOVERNOR

DAVID A. COLE  
COMMISSIONER

May 10, 2010  
Subject: **Lincoln**  
Federal Project No: IB-1731(200)E  
State Pin No: 017312.00  
**Amendment No. 3**

Dear Sir/Ms:

The following questions have been received:

**Question:** The Construction Notes for the project show work in Stations 61+50 to 64+00 and 71+00 to 77+75 being performed under both item 202.202, Removing Pavement Surface, and Item 203.20, Common Excavation. Under which item will the full depth pavement removal in this area be paid for?

**Response:** Full depth pavement removal will be paid under item 202.202 removing pavement surface.

**Question:** The Construction Notes for Item 609.31, Curb Type 3, identify 112LF of curb, the remainder (1278 LF) being miscellaneous as directed by the Resident. Can you provide more information or locations for where this curb will be used?

**Response:** The unidentified curb locations are attached.

Consider this information prior to submitting your bid on May 12, 2010.

Sincerely,

Scott Bickford  
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

Lincoln  
IB-1731(200)E  
PIN 17312.00

609.31 CURB TYPE 3

Station	Station	Side	Length (ft)	Comments
18+00	19+15	Lt.	115	Front of 3 ft. wide island
18+00	19+15	Lt.	115	Back of 3 ft wide island
19+65	20+15	Lt.	50	Front of 3 ft. wide island
19+65	20+15	Lt.	50	Back of 3 ft wide island
31+50	31+90	Lt.	40	Front of 3 ft. wide island
31+50	31+90	Lt.	40	Back of 3 ft wide island
34+20	34+35	Rt.	15	Front of 3 ft. wide isla extend existing island
34+20	34+35	Rt.	15	Back of 3 ft wide islar extend existing island
34+83	34+95	Rt.	12	Front of 3 ft. wide isla extend existing island
34+83	34+95	Rt.	12	Back of 3 ft wide islar extend existing island
38+75	39+75	Lt.	100	Back with loam and seed (5 ft. ± wide)
42+60	43+00	Lt.	40	Front of 3 ft. wide island
42+60	43+00	Lt.	40	Back of 3 ft wide island
43+45	43+85	Lt.	40	Front of 3 ft. wide island
43+45	43+85	Lt.	40	Back of 3 ft wide island
53+15	53+65	Rt.	50	Front of 3 ft. wide island
53+15	53+65	Rt.	50	Back of 3 ft wide island
54+05	54+70	Rt.	65	Front of 3 ft. wide island
54+05	54+70	Rt.	65	Back of 3 ft wide island
55+10	56+30	Rt.	120	Front of 3 ft. wide island
55+10	56+30	Rt.	120	Back of 3 ft wide island
66+05	66+85	Lt.	80	Replace existing curb in front of ERA McPhail Realty
67+00	67+32	Rt.	32	Replace existing curb between Irving & Dead River
Miscellaneous use as directed by			80	

TOTAL: 1,390 ft

Note: All Curb Type 3 placed on this project shall be Mold 2