



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE  
04333-0016

JOHN ELIAS BALDACCI  
GOVERNOR

DAVID A. COLE  
COMMISSIONER

June 25, 2007  
Subject: **Yarmouth, Cumberland,  
And Falmouth**  
Project No. IM-95-1293(800)E  
Pin No. 12938.00  
**Amendment No. 1**

Dear Sir/Ms:

Please make the following changes to the Bid Documents

- 1.) In the Construction Notes add the following Note. "Item 604.792 Guardrail 350 Median System – This is a flared median system that is 350 compliant. The contractor must supply the Resident with installation drawings and 350 compliance certificate before installation." Make this change in pen and ink.
- 2.) In Special Provision Section 424 "Low Modulus Crack Sealer" Under Construction requirements sub section "Weather" The first sentence delete the words, "after sunset or before sunrise". Make this change in pen and ink
- 3.) Add the attached Special Provision Section 645 Highway Signing (Flexible Reflectorized Delineator), dated May 3, 1999. one page.

Consider these changes prior to submitting your bid on June 27, 2007.

Sincerely,

  
Scott Bickford

Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SPECIAL PROVISION  
SECTION 645  
HIGHWAY SIGNING  
(Flexible Reflectorized Delineator)

Description This work shall consist of furnishing and installing flexible reflectorized delineators in accordance with the Manufacturer's recommendations in reasonably close conformity with the plans and specifications.

Materials Flexible reflectorized delineators shall be one of the following:

<u>Manufacturer</u>	<u>Model</u>
Safe-Hit Corp.	Safe-Hit Co-extruded Type SH248GP3 Safe-Hit Co-extruded Type SH254GP3 Safe-Hit Co-extruded Type SH348GP3

Construction Requirements Flexible delineators shall be installed in accordance with Section 645.062 Installation of Delineators, except that the mounted height of the delineator shall be 1200 mm [4 ft] above the edge of shoulder.

Method of Measurement Flexible reflectorized delineators will be measured by the number of units complete in place.

Basis of Payment The accepted reflectorized delineators will be paid for at the contract unit price each. Such payment will be full compensation for furnishing and installing the delineator and all associated hardware complete in place.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
645.306 Flexible Reflectorized Delineator	Each