

**ADDENDUM NO. 1 TO  
PLANS AND SPECIFICATIONS  
TOWN DOCK IMPROVEMENTS  
BUCKSPORT, MAINE**

**PIN 017897.00**

October 12, 2010

The following changes and clarifications have been made to the Specifications:

**SECTIONS 2-A, 2-B, 2-D and 3-B:** Project substantial completion will be **May 6, 2011**. Final acceptance date will be **May 27, 2011**.

**SECTION 4 - ITEM 4, HORIZONTAL BRACING:** Horizontal bracing shall be two braces with flanges top and bottom, welded at elevations 5.5' MHW and 0' MSL.

**SECTION 4 - ITEM 5, CROSS BRACING:** SYP cross bracing shall be attached to the dock's outer bearing piles in the location of the missing cross bracing.

**SECTION 4 - ITEM 9, PAINTING 3-PILE CLUSTER:** Painting is limited to the 4-foot zone, which is elevation -2.33 and 1.67.

**SECTION 4 - ITEM 10, PAINTING 4-PILE CLUSTER:** Painting is limited to the 4-foot zone, which is elevation -2.33 and 1.67.

**PINE TREE  
ENGINEERING**