



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE  
04333-0016

JOHN ELIAS BALDACCI  
GOVERNOR

DAVID A. COLE  
COMMISSIONER

May 21, 2007  
Subject: **Brownfield**  
Pin No's. 12685.00 & 12686.00  
**Amendment No. 1**

Dear Sir/Ms:

Please make the following changes to the Bid Documents:

In the Bid Book, REMOVE in its entirety the existing "Schedule of Items" dated 070427 four pages total and REPLACE with the attached updated "Schedule of Items" dated 070521 two pages total.

REMOVE the existing "Special Provision, Section 502, Structural Concrete, (Fish passage weirs)" dated October 23, 2006, one page total and REPLACE with the attached updated "Special Provision, Section 502, Structural Concrete, (Fish passage weirs)" dated January 17, 2007, one page total.

DELETE the existing "Special Provision, Section 652, Maintenance of Traffic, (Traffic Control)" dated May 12, 2003 one page total and REPLACE with the attached "Special Provision, Section 652, Maintenance of Traffic, (Traffic Control)" dated December 10, 2001, one page total.

Consider these changes prior to submitting your bid on May 23, 2007.

Sincerely,

Scott Bickford  
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

MAINE DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF ITEMS

PAGE: 1  
DATE: 070521  
REVISED:

CONTRACT ID: 012685.00

PROJECT(S): MSP 012685.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 MAIN ITEMS

0010	203.25 GRANULAR BORROW (BURNT MEADOW)	20.000 CY				
0020	502.325 STRUCTURAL CONCRETE CULVERT INVERT LINING	LUMP	LUMP			
0030	502.326 STRUCTURAL CONCRETE - FISH WEIRS	LUMP	LUMP			
0040	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	10600.000 LB				
0050	503.13 REINFORCING STEEL, PLACING	10600.000 LB				
0060	511.07 COFFERDAM: (BURNT MEADOW, UPSTREAM)	LUMP	LUMP			
0070	511.07 COFFERDAM: (BURNT MEADOW, DOWNSTREAM)	LUMP	LUMP			
0080	511.07 COFFERDAM: (TEN MILE, DOWN STREAM)	LUMP	LUMP			
0090	511.07 COFFERDAM: (TEN MILE, UPSTREAM)	LUMP	LUMP			
0100	606.36 GUARDRAIL REMOVED AND RESET	100.000 LF				

MAINE DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF ITEMS

PAGE: 2  
 DATE: 070521  
 REVISED:

CONTRACT ID: 012685.00

PROJECT(S): MSP 012685.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	610.09 HAND LAID RIPRAP	30.000 CY				
0120	620.54 STABILIZATION GEOTEXTILE	15.000 SY				
0130	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0140	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR) (BURNT MEADOW)	10.000 HR				
0150	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR				
0160	652.38 FLAGGER	80.000 HR				
0170	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0180	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0190	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

**SPECIAL PROVISION**  
**SECTION 502**  
**STRUCTURAL CONCRETE**  
(Fish passage weirs)

Section 502, Structural Concrete of the Standard Specifications is amended as follows:

502.03 Materials is revised to read as follows:

Materials shall meet the requirements specified in the following Sections of Division 700 Materials:

Portland Cement and Portland Pozzolan Cement	701.01
Water	701.02
Air Entraining Admixtures	701.03
Water Reducing Admixtures	701.04
Water Reducing, High Range Admixture	701.0401
Set Retarding Admixtures	701.05
Curing Materials	701.06
Water stops	701.07
Smoothed Surfaced Asphalt Roll Roofing (Formerly Heavy Roofing Felt)	701.08
Fly Ash	701.10
Calcium Nitrite Solution	701.11
Silica Fume	701.12
Ground Granulated Blast Furnace Slag	701.13
Fine Aggregate for Concrete	703.01
Coarse Aggregate for Concrete	703.02
Alkali Silica Reactive Aggregates	703.0201
Preformed Expansion Joint Filler	705.01
Bridge Drains	711.04

The fish weirs, including the vertical walls and channel bottom for the entire length between the weirs as shown on the plans shall be formed, cast, and stripped in the conventional manner; shotcrete will not be allowed for the formation of the weirs, vertical walls, or floor between the weirs. Concrete shall meet the requirements of class A concrete in the Specifications.

502.18 Method of Measurement: the first paragraph is revised to read as follows:

A. Structural concrete satisfactorily placed and accepted will be measured by the Lump Sum, in accordance with the dimensions shown on the Plans or authorized changes in the Plans. The accepted quantity of Structural Concrete Fish Weirs will be measured for payment by the Lump Sum.

502.19 Basis of Payment is amended by the addition of the following Pay Item and its associated Pay Unit:

<u>Pay Item</u>		<u>Pay Unit</u>
502.326	Structural Concrete Fish Weirs	Lump Sum (LS)

SPECIAL PROVISION  
SECTION 652  
MAINTENANCE OF TRAFFIC  
(Traffic Control)

652.7 Method of Measurement. This entire Subsection is revised to read:  
Traffic Control Supervisor, furnishing, installation, and maintenance of all traffic control devices will be measured as one **lump sum** for all work authorized and performed.

652.8 Basis of Payment. This entire Subsection is revised to read:  
Traffic Control will be paid for at the contract **lump sum** price. Payment will be full compensation for the Traffic Control Supervisor, approach signs, work area signs, drums, cones, panel markers, barricades, arrow boards etc. and maintenance thereof including the setting up and taking down of lane closures as many times as necessary shall be considered part of the lump sum price.

Maintenance of signs includes: replacing devices damaged, lost, or stolen, and cleaning and moving as many times as necessary throughout the life of the contract, regardless whether the work areas or projects are geographically separated or not separated.

The Lump Sum will be payable in installments as follows: 5% of the Lump Sum once the approach signing is complete and approved, with the 95% balance to be paid as the work progresses at a rate proportional to the percentage completion of the Contract.

Failure by the contractor to follow the Contracts 652 Special Provisions and/or The Manual on Uniform Traffic Control Devices (MUTCD) and/or The Contractors own Traffic Control Plan will result in a reduction in payment, computed by reducing The Lump Sum Total by 5% per occurrence. The Departments Resident or any other representative of The Department reserves the right to suspend the work at any time and request a meeting to discuss violations and remedies. The Department shall not be held responsible for any delay in the work due to any suspension under this item.

All other requirements under the Standard Specifications Section 652 will be a part of the lump sum item.

**There will be no extra payment for this pay item after the expiration of contract time.**

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
652.39 Work Zone Traffic Control	Lump Sum