

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 008151.60

PROJECTS

HP-8151(600)

COUNTY : CUMBERLAND

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 2

CONTRACT ID : 008151.60

GORHAM, NEW BYPASS BRIDGES WORK INCLUDES TWO, 135' SPAN
STEEL GIRDER BRIDGES AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES

CONTRACT	11/15/08	\$ 900.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

CONTRACT ID: 008151.60

PROJECT(S): HP-8151(600)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 BRIDGE ITEMS						
0010	203.25 GRANULAR BORROW	1400.000 CY				
0020	501.231 DYNAMIC LOADING TEST	2.000 EA				
0030	501.54 STEEL H-BEAM PILES 117 LBS/FT, DELIVERED	1200.000 LF				
0040	501.541 STEEL H-BEAM PILES 117 LBS/FT, IN PLACE	1110.000 LF				
0050	501.90 PILE TIPS	20.000 EA				
0060	501.91 PILE SPLICES	10.000 EA				
0070	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0080	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0090	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0100	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008151.60

PROJECT(S): HP-8151(600)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0120	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	37200.000 LB				
0130	503.13 REINFORCING STEEL, PLACING	37200.000 LB				
0140	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP	LUMP			
0150	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0160	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0170	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			
0180	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0190	512.081 FRENCH DRAINS	LUMP	LUMP			
0200	514.06 CURING BOX FOR CONCRETE CYLINDERS	2.000 EA				
0210	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			

SCHEDULE OF ITEMS

CONTRACT ID: 008151.60

PROJECT(S): HP-8151(600)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	526.34 PERMANENT CONCRETE TRANSITION BARRIER	8.000 EA				
0230	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0240	631.121 HEAVY DUTY ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0250	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0260	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0270	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

